SUMMARY OF QUANTITIES

WATER QUALITY INSPECTIONS	
TOTAL	30 MONTHS

WATER QUALITY MONITORING AND SAMPLING	
TOTAL	2 EACH

BARRIER FENCE (ORANGE) 4 FT	
TOTAL	6792 LF

EROSION CONTROL QUANTITIES

ITEM	UNIT	TOTAL
TEMPORARY SILT FENCE, TYPE C	LF	29530
MAINTENANCE OF TEMPORARY SILT FENCE, TYPE C	LF	14765
FLOATING SILT RETENTION BARRIER**	LF	500
STAKED SILT RETENTION BARRIER**	LF	1000
CONSTRUCTION EXIT	EACH	4
MAINTENANCE OF CONSTUCTION EXIT	EACH	8
MAINTENANCE OF INLET SEDIMENT TRAP	EACH	21
EROSION CONTROL MATS, SLOPES	SQ YD	10613
CONSTRUCT AND REMOVE SEDIMENT BASIN, TP 1	EACH	6
MAINTENANCE OF TEMPORARY SEDIMENT BASIN, TP 1	EACH	12
CONSTRUCT AND REMOVE BALED STRAW CHECK DAM	LF	7472
MAINTENANCE OF SEDIMENT BARRIER - BALED STRAW	LF	3736

** AS DIRECTED BY ENGINEER

VOID

EROSION CONTROL - CHECK DAMS / DITCH CHECKS

DITCH LOCATION	SIDE	DITCH LENGTH	CONSTRUCT AND REMOVE			MAINTAIN
		LIN. FT.	RIP RAP (EA)	TYPE C SILT FENCE (LF)	BALED STRAW (LF)	ALL TYPES (LF)
220+00.00 - 223+50.00	LT	350		168		84
223+50.00 - 231+50.00	LT	800		392		196
231+50.00 - 251+00.00	LT	1950		1092		546
254+50.00 - 261+00.00	LT	650		364		182
306+00.00 - 315+00.00	LT	900		532		266
231+50.00 - 238+00.00	MED	650		364		182
238+00.00 - 242+00.00	MED	400		224		112
242+00.00 - 246+00.00	MED	400		224		112
246+00.00 - 250+00.00	MED	400		224		112
250+00.00 - 254+00.00	MED	400		224		112
254+00.00 - 258+00.00	MED	400		224		112
258+00.00 - 261+50.00	MED	350		196		98
261+50.00 - 265+00.00	MED	350		196		98
265+00.00 - 269+50.00	MED	450		252		126
269+50.00 - 271+00.00	MED	150		84		42
271+00.00 - 274+00.00	MED	300		168		84
274+00.00 - 278+00.00	MED	400		224		112
278+00.00 - 283+50.00	MED	550		308		154
283+50.00 - 295+00.00	MED	1150		644		322
295+00.00 - 301+00.00	MED	600		336		168
301+00.00 - 303+75.00	MED	275		140		70
303+75.00 - 306+50.00	MED	275		168		84
220+00.00 - 221+00.00	RT	100		56		28
228+50.00 - 246+00.00	RT	1750		1008		504
249+00.00 - 251+00.00	RT	200		140		70
251+00.00 - 265+50.00	RT	1450		728		364
268+50.00 - 278+00.00	RT	950		448		224
298+50.00 - 315+00.00	RT	1650		812		406
TOTAL				9940		4970