SUMMARY OF QUANTITIES

EROSION CONTROL QUANTITIES

ITEM	UNIT	TOTAL
TEMPORARY SILT FENCE, TYPE C	LF	34320
MAINTENANCE OF TEMPORARY SILT FENCE, TYPE C	LF	17160
TEMPORARY SEDIMENT BARRIER**	LF	1500
MAINTENANCE OF TEMPORARY SEDIMENT BARRIER**	LF	750
FLOATING SILT RETENTION BARRIER	LF	450
CONSTRUCTION EXIT	EACH	6
MAINTENANCE OF CONSTUCTION EXIT	EACH	12
EROSION CONTROL MATS, SLOPES	SQ YD	10740
CONSTRUCT AND REMOVE SEDIMENT BASIN, TP 1	EACH	1
MAINTENANCE OF TEMPORARY SEDIMENT BASIN, TP 1	EACH	2
UNDERDRAIN PIPE INCL DRAINAGE AGGR**	LF	1000
CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN**	LF	2000

** AS DIRECTED BY ENGINEER

EROSION CONTROL - CHECK DAMS / DITCH CHECKS

DITCH LOCATION	SIDE	DITCH LENGTH	CONSTRUCT AND REMOVE			MAINTAIN
		LIN. FT.	RIP RAP (EA)	TYPE C SILT FENCE (LF)	BALED STRAW (LF)	ALL TYPES (LF)
11+00.00 - 38+00.00	LT	2700		594		297
11+00.00 - 37+50.00	RT	2650		594		297
44+00.00 - 63+00.00	LT	1900		418		209
44+00.00 - 63+00.00	RT	1900		418		209
63+00.00 - 80+00.00	LT	1700		374		187
63+00.00 - 81+00.00	RT	1800		418		209
86+00.00 - 107+00.00	LT	2100		550		275
86+00.00 - 106+50.00	RT	2050		484		242
106+50.00 - 118+53.00	RT	1200		242		121
107+00.00 - 14+00.00	LT	850		264		132
115+00.00 - 118+53.00	LT	350		88		44
RAMP A	LT	835		330		165
ROZAR CONNECTOR	LT	850		308		154
ROZAR CONNECTOR	RT	750		220		110
C.R. 138	LT	450		220		110
C.R. 138	RT	450		198		99
C.R. 348	LT	250		198		99
C.R. 348	RT	250		88		44
AS DIRECTED BY ENGINEER			20			
TOTAL			20	6006		3003

BARRIER FENCE (ORANGE) 4 FT

TOTAL	2661 LF

WATER QUALITY MONITORING AND SAMPLING

TOTAL	11 EACH

EMBANKMENT, INCL MATL AND HAUL**

LOCATION	SIDE	GRANULAR (CY)	ROCK (CY)
Sta. 39+50 - 41+50	LT-RT	6171	
Sta. 82+40 - 84+50	LT-RT	1317	
TOTAL		7488	

** TO BE INCLUDED IN EARTHWORK, SEE SPECIAL PROVISION 208

WATER QUALITY INSPECTIONS

TOTAL	24 MONTHS

GRASSING

AREAS	GRASSING	AGRIC. LIME	FERTILIZERS		MULCH	NAT. REST. AND RIPARIAN SEEDING
			MIXED GRADE	NITROGEN CONTENT		
	ACRES	TON	TON	LB	TON	ACRES
PERMANENT	21	42	6	1041	62	4
TEMPORARY	10		3		30	
DISTURBED					378	
TOTAL	31	42	9	1041	470	4

USE ON CONSTRUCTION

3/1/2007 GOUNT

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES
9/3/13
12/12/13
1/15/14

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN
SUMMARY OF QUANTITIES
STP00-0066-01(029)
DODGE COUNTY

DRAWING NO. 6-004