STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	STP00-0076-01(028)	173	227

USE ON CONSTRUCTION

SEE SHEET 24-001
FOR LEGEND

BEG PROJECT
STA 50+00.00
MP = 2.69
N 101015.2772
E 49015.3883
KC454

MARY ANN GODWIN

HENRI ELLEN ADAMS HUNT

ESMT FOR THE DEMOLITION OF BLDG

REMOVE SECTION OF PIPE WITH 2" TAP
INSTALL 4" 12" DIP AND (2) 12" SOLID SLEEVES

EXISTING 12" DIP WATER LINE TO REMAIN

MERRIBETH ADAMS STRATTON

BRYAN ARTHUR STRATTON & AMY STRATTON

TRACT 1 BEGIN V-GUTTER STA. 61+00.00

ADJUST WATER METER BOX TO GRADE AND RELOCATE EXIST WATER METER, INCL BOX TO 1' OUTSIDE R/W RECONNECT PRIVATE SERVICE

ANNETTE ADAMS BUSH & SUSAN RAE BUSH HISTORIC PROPERTY

EXISTING HYDRANT TO REMAIN
ADJUST HYDRANT TO GRADE (TYP.)

EXISTING WATER VALVES TO REMAIN
ADJUST WATER VALVE BOX TO GRADE (TYP.)

ORANGE FENCE

FRAME RES

BENCHMARK #3-SVA342

MATCHLINE STA. 65+00
SEE SHEET 44-004

ESA - HISTORIC BOUNDARY

50+00 | 55+00 | 60+00 | 65+00

1ST R/W | EXIST EOP 12' | BEG TAPER STA 54+00 | 660' TAPER | PROP EOP | CONSTUCTION CENTERLINE | SR 47 | 4' PAVED SHOULDER | EXIST EOP | 44°59'22.1" E | V-GUTTER TYPE 3 REQD | SPILLWAY REQD TP 3 | REQ'D R/W

EXISTING 2" COPPER WATER LINE TO BE ABANDONED

BST 12 PR FIBER OPTIC 100 PR COPPER

IN: GPC/45' T#756136

IN: GPC/45' T#52128

ESMT REQD FOR THE CONST. OF FENCE

RELOCATE 2 EXISTING METERS TO 1' OUTSIDE R/W. INSTALL 2- WATER SERVICE LINE, 3/4 IN LINES IN 1-1/2". HDPE CASING (TYP.) RECONNECT PRIVATE SERVICE

ADJUST WATER METER BOX TO GRADE AND RELOCATE EXIST WATER METER, INCL BOX TO 1' OUTSIDE R/W RECONNECT PRIVATE SERVICE RELOCATE EXIST WATER METER, INCL BOX TO 1' OUTSIDE R/W RECONNECT PRIVATE SERVICE

ADJUST WATER METER BOX TO GRADE AND RELOCATE EXIST WATER METER, INCL BOX TO 1' OUTSIDE R/W RECONNECT PRIVATE SERVICE

ADJUST WATER METER BOX TO GRADE AND RELOCATE EXIST WATER METER, INCL BOX TO 1' OUTSIDE R/W RECONNECT PRIVATE SERVICE

ADJUST WATER METER BOX TO GRADE AND RELOCATE EXIST WATER METER, INCL BOX TO 1' OUTSIDE R/W RECONNECT PRIVATE SERVICE

ADJUST WATER METER BOX TO GRADE AND RELOCATE EXIST WATER METER, INCL BOX TO 1' OUTSIDE R/W RECONNECT PRIVATE SERVICE RECONNECT EXISTING FAUCET

RELOCATE EXIST WATER METER, INCL BOX TO 1' OUTSIDE R/W RECONNECT PRIVATE SERVICE

STORM DRAIN OUTLET PROTECTION RIP RAP TP 3
DD = 1.5' FT
Q = 15.95 CFS
TW < 0.50
LA = 14 FT
300 = 4.5 FT
W = 28 FT
DSB = 1.5

STORM DRAIN OUTLET PROTECTION RIP RAP TP 3
DD = 2.8' FT
Q = 16.78 CFS
TW < 0.55
LA = 14 FT
300 = 7.5 FT
W = 36 FT
DSB = 1.5

STORM DRAIN OUTLET PROTECTION RIP RAP TP 3
DD = 2.8' FT
Q = 6.82 CFS
TW < 0.50
LA = 14 FT
300 = 6 FT
W = 28 FT
DSB = 1.5

END TAPER STA 57+60 24' RT

ESMT FOR THE CONST. & MAINT. OF DRAINAGE

ESMT FOR THE CONST. & MAINT. OF DRAINAGE

ESMT FOR THE CONST. & MAINT. OF DRAINAGE

DONNIE J. HORTON & MARY R. HORTON

RAY C. DENTON, JR.

JACQUELINE L. COCHRAN

BRIAN L. BUCHTA & ANNE F. MORRIS

GLADYS ANN SIMPSON

JOHN WESLEY FULLER, J. GRADY FULLER, JR. & STEPHANIE G. FULLER, WILLIAM MICHAEL SHARPTON

DAVID W. BROWN SR. & SANDRA P. BROWN

ATHAN L. IDSON & YNN M. UDSON

MICHAEL TED FAIRBURN & DANIEL

14' ASPHALT DR STA 54+21

14' ASPHALT DR STA 55+61

14' ASPHALT DR STA 57+43

14' ASPHALT DR STA 58+77

14' CONCRETE DR STA 61+72

14' DIRT DR STA 63+40

14' ASPHALT DR STA 63+03

"ComCast will relocate to Georgia Power Company's poles once they have relocated to clear construction ."

GEORGIA811 Utilities Protection Center, Inc
Know what's below. Call before you dig.

EXISTING WATER LINE (TO RETAIN)	EXISTING WATER METER	EXISTING FIRE HYDRANT
EXISTING WATER LINE (TO BE ABANDONED)	PROPOSED WATER METER	PROPOSED FIRE HYDRANT
PROPOSED WATER LINE	EXISTING WATER VALVE	
EXISTING FIBER OPTIC LINE	PROPOSED WATER VALVE	
	EXISTING COLUMBIA COUNTY FIBER OPTIC HANDHOLE	

SCALE IN FEET
0 50 100 200

REVISION DATES		
6/2/14		

PROPOSED PASSING LANE ON SR 47 SOUTHBOUND FROM CR 46 TO JUST NORTH OF KEG CREEK
COLUMBIA COUNTY WATER UTILITY
CCWU UTILITY RELOCATION PLANS
WASHINGTON ROAD SR 47 STA 50+00 - STA 65+00
STP00-0076-01(028)
COLUMBIA COUNTY
DRAWING No. 44-003

X:\GDOT PROJECTS\PI 231350 SR 47 Ridge Rd to Keg Creek Dr\ACTIVE cad files\PI 231350 SR 47 Ridge Rd to Keg Creek Dr STP00-0076-01(028).dwg, 9/5/2013 11:29:28 AM