STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	BRSTO-2938-00(004)	13	188

QUANTITIES REQUIRED ON CONSTRUCTION

DATE	DESCRIPTION	ITEM NO.	UNIT	ORIGINAL QUANTITY	REQD ON CONSTR QUANTITY	REQ'D BY AMEND. QUANTITY
02-10-11	Water Main Removal, 8 inch, PVC	610-2370	LF		40	DISTRICT 2 UTILITIES
"	Jack or Bore Pipe - 8 inch DIP	615-1000	LF		70	"
"	Water Main 6-inch PVC	670-1060	LF		20	"
"	Water Main 10-inch PVC	670-1100	LF	2280	2180	"
"	Water Main 8-inch DIP	670-1080	LF	60	120	"
"	Gate Valve with Valve Box, 6-inch	670-2060	EA		3	"
"	Gate Valve with Valve Box, 8-inch	670-2080	EA	1	2	"
"	Gate Valve with Valve Box, 10-inch	670-2100	EA	4	2	"
"	Fire Hydrant	670-4000	EA		3	"
"	Double Strap Service, 10-inch X 1-inch	670-8102	EA		4	"
"	Remove Existing Fire Hydrant	670-9920	EA		3	"
"	SERVICE CONNECTION ASSEMBLY	(SEE NOTE 1)	EA		4	"
"	10-INCH x 8-INCH MJ TEE, W/ THRUST RESTRAINT	(SEE NOTE 3)	EA		2	"
"	10-INCH x 6-INCH MJ TEE, W/ THRUST RESTRAINT	(SEE NOTE 3)	EA		3	"
"	10-INCH X 4-INCH MJ TEE, W/THRUST RESTRAINT	(SEE NOTE 3)	EA		1	"
"	10-INCH MJ 45° BEND WITH THRUST RESTRAINT	(SEE NOTE 3)	EA		8	"
"	8 INCH MJ 45° BEND WITH THRUST RESTRAINT	(SEE NOTE 3)	EA		8	"
"	8 INCH MJ 22.5° BEND WITH THRUST RESTRAINT	(SEE NOTE 3)	EA		1	"
"	4-INCH MJ CAP	(SEE NOTE 2)	EA		1	"
"	8-INCH MJ PLUG	(SEE NOTE 3)	EA		1	"
"	10-INCH MJ PLUG	(SEE NOTE 3)	EA		2	"
"	REMOVE EXISTING WATER VALVE BOX	(SEE NOTE 5)	EA		8	"

NOTES TO BE ADDED:

1. SERVICE CONNECTION ASSEMBLIES ARE CONSIDERED INCIDENTAL TO WATER SERVICE LINE CONSTRUCTION AND WILL NOT BE MEASURED FOR PAYMENT OR PAID FOR SEPERATELY, BUT SHALL BE INCLUDED IN THE BID PRICE FOR WATER SERVICE LINE, 1-INCH.

2. AIR RELEASE VALVE ASSEMBLY (ARV) - PAY ITEM SHALL INCLUDE THE FOLLOWING:

   A. RELOCATIONS OF EXISTING AIR RELEASE VALVE
   B. REMOVAL AND ABANDONMENT OF EXISTING ARV MANHOLE
   C. INSTALLATION OF ARV ASSEMBLY, NEW ARV MANHOLE, VALVES, FITTINGS, CONNECTIONS, STONE BEDDING, AND OTHER NECESSARY APPURTENANCES
   D. TESTING AND DISINFECTING NEW ARV ASSEMBLY
   E. SURFACE STABILIZATION AND RESTORATION, AS NECESSARY

3. PIPE FITTINGS ARE CONSIDERED INCIDENTAL TO WATER MAIN CONSTRUCTION AND WILL NOT BE MEASURED FOR PAYMENT OR PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE BID PRICE FOR WATER MAIN OF VARIOUS SIZES.

4. PAVEMENT CUTTING AND PATCHING, EXCAVATION, BACKFILL, COMPACTION, BEDDING, TESTING AND DISINFECTION ARE ALL CONSIDERED INCIDENTAL TO WATER MAIN CONSTRUCTION AND WILL NOT BE MEASURED FOR PAYMENT OR PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE BID PRICE FOR WATER MAIN OF VARIOUS SIZES AND MATERIALS.

5. VALVE BOXES ENCOUNTERED ON LINE TO BE ABANDONED SHALL BE REMOVED AND ARE CONSIDERED INCIDENTAL TO WATER MAIN CONSTRUCTION AND WILL NOT BE MEASURED FOR PAYMENT, OR PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE BID PRICE FOR WATER MAIN OF VARIOUS SIZES.

USE ON CONSTRUCTION

DATE	REVISIONS	DATE	REVISIONS
02-10-11	ADD & REV PAY ITEMS		

GEORGIA
DEPARTMENT OF TRANSPORTATION
QUANTITIES REQUIRED
ON CONSTRUCTION
PROJECT: BRSTO-2938-00(004)
COUNTY: MORGAN

DRAWING NO. 08-01

C:\245400\DGN Files\245400Amend&ConstQuan.dgn