SUMMARY OF QUANTITIES

REINF CONC APPROACH SLAB, INCL CURB	
LOCATION	SY
BRIDGE NO. 1	721
BRIDGE NO. 2	761
TOTAL	1482

CONCRETE BARRIER, TYPE 21	
LOCATION	LF
EXISTING OLD EVANS RR CROSSING	60
TOTAL	60

SAWED JOINTS IN EXIST PAVEMENTS - PCC	
TOTAL	2000 LF

TEMPORARY BARRIER		TEMPORARY BARRIER, METHOD NO. 1	TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR, TYPE 1
LOCATION	STAGE	LF	EA
13+80 11' LT - 15+80 11' LT TEMP ALIGNMENT A	1	200	2
122+50 0' LT - 132+50 10' RT RIVERWATCH PARKWAY	1 & 1A	1010	2
28+88 1' LT - 30+88 11' LT TEMP ALIGNMENT A	1	200	2
30+25 11' RT - 30+88 11' RT TEMP ALIGNMENT A	1	63	2
205+50 22.5' LT - 207+00 22.5' LT RIVERWATCH PARKWAY	1	150	2
205+50 2' RT - 207+00 2' RT RIVERWATCH PARKWAY	1	150	2
AS DIRECTED		1000	6
TOTALS		2773	18

WALL QUANTITIES

WALL NO.	LOCATION	CONCRETE SIDE BARRIER, TYPE 2S	CONCRETE SIDE BARRIER, TYPE 2C	CLASS A CONCRETE, RETAINING WALL	CLASS A CONCRETE, TYPE P1, RETAINING WALL	SOUND BARRIER, TYPE CONCRETE	CLASS B CONCRETE, RETAINING WALL	BAR REINF STEEL	GALV STEEL PIPE HANDRAIL, 2 IN, ROUND	PILING IN PLACE, STEEL H, HP 14 X 117	PILOT HOLES	FLOWABLE FILL	CH LK FENCE, ZC COAT, 6 FT, 9 GA
		LF	LF	CY	LF	SF	CY	LB	LF	LF	LF	CY	LF
1	STA. 125+17.14 - STA. 127+54.21, RIVERWATCH PKWY (LT)		249										
2	STA. 154+89.42 - STA. 155+60, RIVERWATCH PKWY (LT)						27		67				
3	STA. 211+05.50 - STA. 213+49.50, RIVERWATCH PKWY (RT)			192				13492		764	797	66	249
4	STA. 212+40 - STA. 213+20, RIVERWATCH PKWY (LT)						49		81				
5	STA. 217+90 - STA. 219+00, RIVERWATCH PKWY (RT)				110								
6	STA. 229+00 - STA. 229+80, RIVERWATCH PKWY (RT)				81								
7	STA. 28+30 - STA. 29+66, WASHINGTON RD (LT)						52		136				
8	STA. 30+40.25 - STA. 32+40, WASHINGTON RD (LT)						57		200				
9	STA. 36+27.47 - STA. 37+06.76, WASHINGTON RD (LT)						46		80				
10	STA. 37+27.20 - STA. 37+77.62, WASHINGTON RD (LT)						17		51				
11	STA. 38+11.62 - STA. 38+69, WASHINGTON RD (LT)						28		58				
12	STA. 144+20 - STA. 144+79.34, OLD PLANTATION RD (LT)						25		59				
SB1	STA. 144+10 - STA. 149+60, RIVERWATCH PKWY (RT)	551				11007							
SB2	STA. 162+96 - STA. 167+30, RIVERWATCH PKWY (LT)	435				8701							
	TOTAL	986	249	192	191	19708	301	13492	732	764	797	66	249

SB = SOUND BARRIER

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES
8/30/2013
10-17-13

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN
SUMMARY OF QUANTITIES
P. I. NO. 250470
DRAWING NO. 06-002

3/1/2007 GQUANT