3/26/2013	8:35:22 PM	Plot File	DGN	STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
USER:robert		PENTABLE:emcero.tbl		GA	STP00-7073-00(001)	214	232

VOID

DITCH PROTECTION TABLE					
BEGIN STA	END STA	SIDE	WIDTH	Dp	LINING TYPE
31+95	34+25	LT	4	1.1	GRASS

WATER QUALITY NOTE:
INSTALL INLET FILTERS IN STRUCTURES LOCATED AT STATION 38+60 & 41+75 L & R.
INLET FILTER SHALL BE FLEXSTORM PC PART NUMBER 62HDWM3PC OR EQUAL.

GEORGIA POWER COMPANY (160' ESMNT)

MITCHELL LANE

ESA-25' STREAM BUFFER *4 INTERMITTENT

20' SANITARY SEWER ESMNT

DOUBLE ROW TYPE C SILT FENCE

ESA-25' OW BUFFER *5

ORANGE BARRIER FENCE

NON-JURISDICTIONAL MAN MADE DITCH

WILLIAM FEW PKWY

MATCH LINE STA. 32+00

MATCH LINE STA. 44+00

Mb

St-Rp

Ch-Rp3

TP 1 RIPRAP 33 SY

TP 3 RIPRAP 7 SY

OPEN WATER *5

UPLAND

REQ'D R/W

EXIST. R/W

ESA-WETLAND BOUNDARY *3

DOUBLE ROW TYPE C SILT FENCEN

TP 1 RIPRAP 37 SY

Dn1 SPACING: S<0.2%, 500' S>2%, 200'

N

Mb MATTING AND BLANKETS SHALL BE APPLIED TO ALL CUT OR FILL SLOPES 2.5:1 OR STEEPER AND WITHIN 50' OF ALL CROSS DRAINS AND CULVERTS.

ESA NOTE:
SEE ENVIRONMENTAL RESOURCES IMPACT TABLE IN GENERAL NOTES FOR CONSTRUCTION RESTRICTIONS.

EMC ENGINEERING SERVICES, INC.
CIVIL MARINE ENVIRONMENTAL
4106 COLBEN BLVD.
SUITE 105
AUGUSTA, GA 30809
PH: 706-650-3057

SCALE IN FEET
0 50 100 200

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

BMP LOCATION DETAILS

PHASE III

WILLIAM FEW PKWY. EXT. PH 2
STA. : 32+00 - 44+00

DRAWING No. 54-21

3/1/2007 GPLN

...\p\07-8014\dgn\250620ER03-3.dgn 3/26/2013 8:35:22 PM