PARCEL 9 REQ'D R/W RW5057

PNT	OFFSET/ DIST ENGLISH	OFFSET/ DIST METRIC	STATION/ BEARING	ALIGNMENT
KC17589	108.267 L	33.000 L	11+767.591	S.R. 21 CONSTR. ℄
	171.945	52.409	N 84°17'08.8" E	
KC16939	108.267 L	33.000 L	11+820.000	S.R. 21 CONST. ℄
	262.651	80.056	N 86°26'00.2" E	
KC16957	98.425 L	30.000 L	11+900.000	S.R. 21 CONST. ℄
	344.487	105.000	N 84°17'08.8" E	
KC16958	98.425 L	30.000 L	12+005.000	S.R. 21 CONST. ℄
	48.707	14.846	N 37°47'00.3" E	
KC16959	49.212 R	15.000 R	19+960.000	CR47 CONST. ℄
ARC LENGTH =	216.535 FEET	(66.000 METERS)		
CHORD BEAR =	N 8°41'47.7" E			
LNTH CHORD =	215.094 FEET	(65.561 METERS)		
RADIUS =	541.337 FEET	(165.000 METERS)		
DEG =	34°43'28"			
KC16960	49.212 R	15.000 R	19+900.000	CR47 CONST. ℄
	107.551	32.782	N 31°06'35.1" E	
KC16961	39.370 R	12.000 R	19+870.000	CR47 CONST. ℄
ARC LENGTH =	129.270 FEET	(39.402 METERS)		
CHORD BEAR =	N 38°34'57.5" E			
LNTH CHORD =	128.952 FEET	(39.305 METERS)		
RADIUS =	531.495 FEET	(162.000 METERS)		
DEG =	35°22'3"			
KC16962	39.370 R	12.000 R	19+833.517	CR47 CONST. ℄
	274.005	83.517	N 45°33'00.9" E	
KC16963	39.370 R	12.000 R	19+750.000	CR47 CONST. ℄
	37.682	11.485	N 30°24'32.1" E	
KC16978	49.212 R	15.000 R	19+738.913	CR47 CONST. ℄
	23.392	7.130	S 42°03'08.8" E	
KC16586	25.840 R	7.876 R	19+739.212	CR47 CONST. ℄
	69.673	21.236	S 41°40'43.0" E	
KC16585	43.751 L	13.335 L	19+740.238	CR47 CONST. ℄
	5.476	1.669	S 40°13'25.8" E	
KC16979	49.212 L	15.000 L	19+740.361	CR47 CONST. ℄
	33.119	10.095	S 62°50'19.2" W	
KC16964	39.370 L	12.000 L	19+750.000	CR47 CONST. ℄
	274.005	83.517	S 45°33'00.9" W	
KC16965	39.370 L	12.000 L	19+833.517	CR47 CONST. ℄
ARC LENGTH =	381.772 FEET	(116.364 METERS)		
CHORD BEAR =	S 21°23'38.1" W			
LNTH CHORD =	370.562 FEET	(112.948 METERS)		
RADIUS =	452.755 FEET	(138.000 METERS)		
DEG =	41°31'7"			
KC16966	39.370 L	12.000 L	19+960.000	CR47 CONST. ℄
	44.544	13.577	S 52°01'15.3" E	
KC16967	98.425 L	30.000 L	12+052.000	S.R. 21 CONST. ℄
	275.255	83.898	N 84°17'08.8" E	
KC16968	98.425 L	30.000 L	12+135.898	S.R. 21 CONST. ℄
ARC LENGTH =	103.671 FEET	(31.599 METERS)		
CHORD BEAR =	N 85°17'09.8" E			
LNTH CHORD =	103.665 FEET	(31.597 METERS)		
RADIUS =	2969.154 FEET	(905.000 METERS)		
DEG =	6°19'51"			
KC16981	98.425 L	30.000 L	12+166.449	S.R. 21 CONST. ℄
	83.686	25.508	S 10°08'46.8" E	
KC16274	15.281 L	4.658 L	12+169.292	S.R. 21 CONST. ℄
	99.093	30.204	S 85°33'43.0" W	
KC16177	15.408 L	4.696 L	12+139.247	S.R. 21 CONST. ℄
	11.048	3.367	S 84°21'14.2" W	
KC16985	15.400 L	4.694 L	12+135.898	S.R. 21 CONST. ℄
	711.319	216.811	S 84°21'14.2" W	
KC16176	16.246 L	4.952 L	11+919.088	S.R. 21 CONST. ℄
	390.492	119.022	S 84°04'13.9" W	
KC16175	14.779 L	4.505 L	11+800.066	S.R. 21 CONST. ℄
	57.855	17.634	S 84°40'11.8" W	
KC17588	15.167 L	4.623 L	11+782.432	S.R. 21 CONST. ℄
	105.065	32.024	N 33°19'26.3" W	
KC17589	108.267 L	33.000 L	11+767.591	S.R. 21 CONST. ℄

REQD R/W = 173370.76 SF (16106.74 m2)
REQD R/W = 3.980 ACRES (1.611 ha)
REMAINDER = +/- 23.5 ACRES (+/- 9.51 ha) AREA 1
REMAINDER = +/- 3.95 ACRES (+/- 1.60 ha) AREA 2

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
R/W AND LIMIT OF ACCESS

RATIO=1:500
0 10 20 40
SCALE IN METERS

DATE	REVISIONS	DATE	REVISIONS

LAND LOT NO.
LAND DISTRICT
GMD 1638
PRF $$PENTABLE$$

GEORGIA
DEPARTMENT OF TRANSPORTATION
RIGHT OF WAY PLANS
PROJECT EDS-565(7)
COUNTY JENKINS
DATE 8/31/99 SH 10 OF 42

RWDOTO