

REVISED 5/10/04

GENERAL NOTES

1. THE FOLLOWING UTILITY OWNERS HAVE FACILITIES WHICH CONFLICT WITH CONSTRUCTION ON THIS PROJECT.

ATLANTA GAS LIGHT COMPANY
CORDELL CARTER, DESIGN ENGINEER
10 PEACHTREE PLACE, NE, 11TH FLOOR
ATLANTA, GA 30309
404-584-4712

BELLSOUTH
SUZANNE TAYLOR, MANAGER
2424 WILLIAMS ROAD
COLUMBUS, GA 31909
706-571-3661

BELLSOUTH TELECOMMUNICATIONS
DENNI S. COKER, ADMINISTRATIVE ASST.
2310 PARKLAKE DRIVE, NE, SUITE 530
ATLANTA, GA 30345
770-493-3754

BELLSOUTH TELECOMMUNICATIONS, INC
EDDIE KING, PROJECT MANAGER
2310 PARKLAKE DRIVE, NE, SUITE 530
ATLANTA, GA 30345
770-493-2006

CHARTER COMMUNICATIONS
ROGER WALIZER
43 WERZ INDUSTRIAL DRIVE
NEWNAN, GA 30263-5803
770-253-2668

COMCAST ENTITY (F/K/A AT&T BROADBAND)
CATHY CAMPBELL, CONST. COORDINATOR
2925 COURTYARDS DRIVE
NORCROSS, GA 30071
770-559-2668

COWETA COUNTY WATER & SEWER DEPARTMENT
HARRY HUGHES, SUPERINTENDENT
230 EAST NEWNAN ROAD
NEWNAN, GA 30263
770-254-3710

COWETA-FAYETTE EMC
OBIE YOUNGBLOOD, MANAGER OF ENIGEERING
3790 HIGHWAY 29 NORTH
NEWNAN, GA 30264
770-253-5626

FAYETTE COUNTY WATER SYSTEM
TONY V. PARROTT, MANAGER
P.O. BOX 190
245 MCDONOUGH ROAD
FAYETTEVILLE, GA 30214
770-461-1146

GEORGIA POWER COMPANY - BIN *36066
HAROLD COX, D.OT. CENTRALIZED ENGINEERING
829 JEFFERSON STREET NW
ATLANTA, GA 30318
404-506-4401

GEORGIA TRANSMISSION CORPORATION
TONY PRITCHETT, REGULATORY SPECIALIST
2100 EAST EXCHANGE PLACE
TUCKER, GA 30084-5336
770-270-7511

NEWNAN UTILITIES
DENNIS McENTIRE, GENERAL MANAGER
70 SEWELL ROAD
NEWNAN, GA 30263
770-683-0994

PEACHTREE CITY WATER AND SEWERAGE AUTHORITY
LARRY TURNER, GENERAL MANAGER
1127 HIGHWAY 74 SOUTH
PEACHTREE CITY, GA 30269
770-487-5183

THE CONTRACTOR SHALL ADHERE TO THE CALL BEFORE YOU DIG LAW BY CALLING THE UNDERGROUND PROTECTION CENTER AT 1-(800) 282-7411 BEFORE BEGINNING CONSTRUCTION

2. A NOTICE OF INTENT (N.O.I.) IS REQUIRED FOR THIS PROJECT.

3. THE CONTRACTOR SHALL CLEAN OUT ALL EXISTING PIPES THAT ARE TO BE RETAINED AND UTILIZED. COST SHALL BE INCLUDED IN OVERALL BID.

4. THERE IS NO SUITABLE SITE WITHIN THE PROJECT LIMITS TO BURY THE EXISTING LINE CREEK AND CSXT RAILROAD BRIDGES. THE CONTRACTOR IS REQUIRED TO DISPOSE OF THE BRIDGES AT NO ADDITIONAL COST TO THE DEPARTMENT.

5. TEMPORARY STRIPING AND TEMPORARY SIGNS REQUIRED FOR TIE-INS SHALL BE PAID AS PART OF TRAFFIC CONTROL.

6. ALL EXISTING SIGNAL MATERIALS FROM THE SIGNALIZED INTERSECTIONS (NOT INCLUDING SR-34 @ FISCHER ROAD AND SR-34 @ SR-54) SHALL BE REMOVED AND DELIVERED BY THE CONTRACTOR TO THE G.D.O.T. DISTRICT 3 SIGNAL SHOP IN THOMASTON, GEORGIA. THIS MATERIAL WILL REMAIN THE PROPERTY OF G.D.O.T. THE CONTRACTOR WILL COORDINATE WITH THE ENGINEER REGARDING THE DELIVERY DATE AND TIME OF THE SPECIFIC MATERIALS TO BE SALVAGED.

PROJECT SPECIFIC NOTES

1. POSITIVE DRAINAGE SHALL BE PROVIDED AT ALL TIMES. TEMPORARY DRAINAGE SHALL BE DESIGNED FOR A 10-YEAR STORM EVENT. THE COST FOR DESIGNING, INSTALLING AND REMOVING TEMPORARY DRAINAGE ITEMS NOT ALREADY SHOWN IN THE PLANS SHALL BE INCLUDED IN THE OVERALL BID PRICE SUBMITTED.
2. TEMPORARY PIPE MAY BE CORRUGATED METAL OR CONCRETE.
3. ALL TEMPORARY DRAINAGE STRUCTURES NOT TO BE INCLUDED IN THE FINAL WORK SHALL BE REMOVED OR FILLED WITH CLASS B CONCRETE OR FLOWABLE FILL.
4. ALL TEMPORARY CONCRETE AND CORRUGATED METAL PIPE SHALL BE EITHER REMOVED, FILLED WITH GROUT, OR PLUGGED.
5. THE COST OF REMOVING, FILLING, AND PLUGGING TEMPORARY PIPES AND STRUCTURES SHALL BE INCLUDED IN THE OVERALL PRICE BID SUBMITTED.
6. IF BLASTING IS REQUIRED, THE CONTRACTOR SHALL NOTIFY PEACHTREE CITY AND ALL OF THE UTILITY COMPANIES HAVING UTILITIES IN THE VICINITY OF THE BLASTING AREA AT LEAST 72 HOURS PRIOR TO THE COMMENCING OF BLASTING.
7. CLEARING AND GRUBBING IN THE VICINITY OF WETLAND NO. 1 (STA. 467+00 LT.) SHALL ONLY OCCUR UP TO THE CONSTRUCTION LIMIT AND NOT ALL THE WAY TO THE R/W LINE. THE REASON FOR THIS IS TO MINIMIZE THE IMPACT TO THE WETLAND AREA.
8. THE CONTRACTOR SHALL COORDINATE GRADING ACTIVITIES WITH NEWNAN UTILITIES FROM STA. 456+00 TO 459+00 RT. ALONG THE MAINLINE AND FROM STA. 111+00 TO 115+00 ALONG SR-54. THIS COORDINATION AND GRADING SHALL OCCUR IN ORDER TO ACCOMMODATE THE PROPOSED 24 INCH WATER MAIN AS SHOWN IN THE UTILITY PLANS. ONCE ROUGH GRADING IS COMPLETE, THE UTILITY WORK WILL BE COMPLETED BY NEWNAN UTILITIES IN 30 CALENDAR DAYS.
9. PROPERTY MANAGEMENT HAS NEITHER DONE THE ASBESTOS INSPECTION NOR THE ABATEMENT THE ROAD CONTRACTOR SHALL COMPLY WITH ALL EPD REGULATIONS BY IDENTIFYING AND REMOVING THE ASBESTOS FROM ALL STRUCTURES. THE COST FOR THESE IMPROVEMENTS SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR CLEARING & GRUBBING.

PARCEL	IMPROVEMENTS	STATION	OFFSET
249	1-STORAGE UNIT- BLDG. *5	524+12.85	95.44 FT RT

GEORGIA
DEPARTMENT OF TRANSPORTATION
PROJECT NOTE SHEET
PROJECT STP-164-1(30)
COWETA & FAYETTE CO.
DATE 1/20/04 SH 1 OF 1