| STATE | PROJECT NUMBER | SHEET NO. | TOTAL SHEETS |
|---|---|---|---|
| GA. | STP-164-1(30) | 13 | 406 |

REVISED & REDRAWN 8/30/04
USE ON CONSTRUCTION

## 30' REINFORCED CONCRETE APPROACH SLAB - GA STD 9017-R

| LOCATION | SY |
|---|---|
| STA 484+51 TO 484+81 | 360 |
| STA 487+09 TO 487+39 | 360 |
| STA 527+79.25 TO 528+09.25 | 367 |
| STA 530+17.75 TO 530+47.75 | 367 |
| TOTAL | 1454 |

## CONCRETE MEDIAN, 7½ IN. THICK

| LOCATION | SIDE | QUANTITY SY | REMARKS |
|---|---|---|---|
| STA 539+20 TO 542+10 | LT | 107 | TYPE 7 CONCRETE MEDIAN |
| | | | SEE GA STD 9032B |
| TOTAL | | 107 | |

## CONCRETE MEDIAN, 6 IN. THICK WITH TYPE 7 FACE

| LOCATION | QUANTITY SY |
|---|---|
| STA 457+50 (ISLAND RT) | 34 |
| STA 458+15 (ISLAND RT) | 218 |
| STA 518+50 (ISLANDS LT. & RT.) | 150 |
| STA 538+50 (ISLAND RT.) | 94 |
| STA 543+00 (ISLAND LT) | 430 |
| STA 543+85 (ISLAND RT) | 74 |
| TOTAL | 1000 |

## CONCRETE SIDEWALK, 4 IN THICK

| | |
|---|---|
| TOTAL | 6074 SQ. YD. |

THE 8' WIDE MEANDERING SIDEWALK SHOWN IN THE PLANS FROM STA 496+48 TO 526+80 LT. WILL BE CONSTRUCTED BY OTHERS AND IS NOT A PART OF THIS CONTRACT.

## CLASS B CONCRETE, RETAINING WALL

| LOCATION | QUANTITY CU. YD. |
|---|---|
| 501+40 TO 502+45, RT | 22 |

## TRAFFIC STRIPE

| DESCRIPTION | UNIT | QUANTITY PAINT | THERMOPLASTIC | PREFORMED PLASTIC |
|---|---|---|---|---|
| 5 IN SOLID WHITE | LIN FT | | 34 900 | 920 |
| 5 IN SOLID YELLOW | LIN FT | | 29 600 | 2 052 |
| 8 IN SOLID WHITE | LIN FT | | 6 906 | |
| 24 IN SOLID WHITE | LIN FT | | 827 | |
| 5 IN SKIP WHITE | GR LIN FT | | 25 897 | 1 368 |
| TRAFFIC STRIPE WHITE | SQ YD | | 8 449 | |
| TRAFFIC STRIPE YELLOW | SQ YD | | 803 | 1 039 |

## RAISED PAVEMENT MARKERS (EACH)

| TYPE 1 | TYPE 3 |
|---|---|
| 65 | 475 |

## ARROWS (EACH)

| DESCRIPTION | QUANTITY THERMOPLASTIC |
|---|---|
| TYPE 2 | 111 |
| TYPE 7 | 11 |

## WORDS (EACH)

| DESCRIPTION | QUANTITY THERMOPLASTIC |
|---|---|
| "ONLY" | 12 |

## RESET SIGN

| STATION | LOCATION | QUANTITY (EA) |
|---|---|---|
| 543+70 | SR 54, LT | 1 |
| TOTAL | | 1 |

## TEMPORARY TRAFFIC SIGNAL INSTALLATION

| | |
|---|---|
| SR-34 @ FISCHER ROAD | LUMP SUM |

## TEMPORARY PRECAST CONCRETE BARRIER - GA STD 4960, 4961

| | |
|---|---|
| METHOD 3 | 2950 LF |
| METHOD 4 | 1000 LF |

## TEMPORARY ATTENUATOR GA STD 4960, 4962

4 EACH

## Ø TRAFFIC CONTROL

| | |
|---|---|
| STP-164-1(30) | LUMP SUM |

Ø INCLUDES PAYMENT FOR TEMPORARY SIGNS, REMOVAL OF TRANSITIONS AND TEMPORARY TIE-INS, AND TEMPORARY SHORING AS NECESSARY FOR ROAD CONSTRUCTION.

GEORGIA
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 1/20/04 SH 3 OF 6

9/1/2004 11:39:35 AM \\GDOT-DSN1\GOPLOT\DGE\gg_bxp8002_paper_36x24.pcf cbbrown M:\322060\DGN Files\All Current DGN Files\32060gw3.pcf GG=BD3