STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	EDS - 19 (50)	14a	29

PARCEL 25 REQ'D R/W RW26

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
EXT78	82.17	L	179+45.01	US 19/SR3
	42.84		N 89°16'58.74" W	
R151	125.00	L	179+45.86	US 19/SR3
	1108.26		N 0°25'16.89" W	
R152	125.00	L	190+54.13	US 19/SR3
	92.69		S 88°52'23.48" E	
EXT599	32.35	L	190+51.62	US 19/SR3
	977.18		S 2°00'30.28" W	
EXT839	73.77	L	180+75.32	US 19/SR3

ARC LENGTH = 130.588
CHORD BEAR = S 3°16'01.11" W
LNTH CHORD = 130.577
RADIUS = 2972.387
DEGREE = 1° 55' 39''

EXT78	82.17	L	179+45.01	US 19/SR3

REQD R/W = 76523.68 SF
REQD R/W = 1.757 ACRES
REMAINDER = +/- 12.074 ACRES

PARCEL 27 REQ'D R/W RW25

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
EXT822	84.38	R	175+63.91	US 19/SR3
	149.59		N 88°51'10.1" W	
EXT821	65.15	L	175+68.01	US 19/SR3
	276.04		N 6°22'55.5" E	
R149	32.45	L	178+42.11	US 19/SR3

ARC LENGTH = 231.479
CHORD BEAR = N 4°11'43.0" E
LNTH CHORD = 231.422
RADIUS = 3032.387
DEGREE = 1° 53' 22''

R150	13.83	L	180+72.78	US 19/SR3
	978.10		N 2°00'30.3" E	
EXT34	27.64	R	190+50.00	US 19/SR3
	55.92		S 88°52'23.5" E	
EXT137	83.54	R	190+48.49	US 19/SR3
	1484.58		S 0°27'13.7" E	
EXT822	84.38	R	175+63.91	US 19/SR3

REQD R/W = 136315.26 SF
REQD R/W = 3.129 ACRES
REMAINDER = +/- 0.000 ACRES

PARCEL 18 REQ'D EASM'T. EASE3

PNT	OFFSET		STATION	ALIGNMENT
EASE143	84.53	R	173+00.00	US 19/SR3
EASE144	83.68	R	188+00.00	US 19/SR3
EASE145	92.00	R	187+50.00	US 19/SR3
EASE161	105.00	R	183+00.00	US 19/SR3
EASE184	105.00	R	175+00.00	US 19/SR3
EASE177	95.00	R	175+00.00	US 19/SR3
EASE186	95.00	R	173+00.00	US 19/SR3
EASE143	84.53	R	173+00.00	US 19/SR3

REQD EASMT AREA = 25559.32 SF

PARCEL 26 REQ'D R/W RW28

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
EXT599	32.35	L	190+51.62	US 19/SR3
	92.69		N 88°52'23.5" W	
R152	125.00	L	190+54.13	US 19/SR3
	917.94		N 0°25'17.1" W	
R153	125.00	L	199+72.06	US 19/SR3
	134.93		S 89°13'52.7" E	
EXT387	9.90	R	199+69.26	US 19/SR3
	488.32		S 2°23'46.4" W	
R154	14.10	L	194+81.53	US 19/SR3
	430.29		S 2°00'30.2" W	
EXT599	32.35	L	190+51.62	US 19/SR3

REQD R/W = 103768.81 SF
REQD R/W = 2.382 ACRES
REMAINDER = +/- 59.931 ACRES

PARCEL 28 REQ'D R/W RW27

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
EXT137	83.54	R	190+48.49	US 19/SR3
	55.92		N 88°52'23.5" W	
EXT34	27.64	R	190+50.00	US 19/SR3
	429.17		N 2°00'30.3" E	
EXT840	45.83	R	194+78.78	US 19/SR3
	489.82		N 2°23'46.4" E	
EXT605	69.91	R	199+68.02	US 19/SR3
	13.11		S 89°13'53.9" E	
EXT606	83.02	R	199+67.74	US 19/SR3
	919.25		S 0°27'13.8" E	
EXT137	83.54	R	190+48.49	US 19/SR3

REQD R/W = 32426.19 SF
REQD R/W = 0.744 ACRES
REMAINDER = +/- 0.000 ACRES

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
R/W AND LIMIT OF ACCESS

STONE & WEBSTER INC.
A SHAW GROUP COMPANY
3730 ROSWELL ROAD,
SUITE 100
MARIETTA, GEORGIA 30062

DATE	REVISIONS	DATE	REVISIONS

GEORGIA
DEPARTMENT OF TRANSPORTATION
RIGHT-OF-WAY PLAN
PROJECT: EDS - 19 (50)
COUNTY: SUMTER
DATE:
14A 29 SH

PLOTTED: Jan 30 09:48 SPRAMES FILENAME