STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-209-1(1)	13	513
REVISION DATES			
5/10/06			

SUMMARY OF QUANTITIES

LOCATION	PAVING QUANTITIES									CONCRETE QUANTITIES						MISC.			
	RECYC ASPH CONC,125 mm SUPERPAVE GP 2 ONLY, INCL POLYMER MODIFIED BITUM MATL& H.LIME	RECYC ASPH CONC 19 mm, SUPERPAVE GP 1 OR 2, INCL BITUM MATL & H.LIME.	RECYC ASPH CONC 25 mm, SUPERPAVE GP 1 OR 2, INCL BITUM MATL & H.LIME	GRADED AGG BASE CRS, INCL MATL 305 mm	BITUMINOUS TACK COAT	AGGREGATE SURFACE COURSE	RECYC ASPH CONC LEVELING INCL BITUM & H.LIME	PVMT REINF FABRIC STRIPS,TP 2, INCL BITUM BINDER		DRIVEWAY CONCRETE, 100 mm THK	CONCRETE VALLEY GUTTERS, w/CURB 150 mm THK	CONCRETE VALLEY GUTTERS, w/CURB 200 mm THK	DRIVEWAY CONCRETE, 150 mm THK			RIGHT OF WAY MARKERS	GROUND IN PLACE RUMBLE STRIPS (CONTINUOUS),400 mm WIDE	CLASS B CONC. BASE OR PAVEMENT WIDENING	
	Mg	Mg	Mg	Mg	L	Mg	Mg	Lm		m^2	m	m	m^2			EA	GLKm	m^3	
SR 74	17168	41693	38056	91717	152346		6187	15410		--	--	--	--			145	7		
SIERRA DR.	73						11			--	--	--	--			--			
DIVIDEND DR.	71	11	14	59	247		11			--	--	--	--			--			
CROSSTOWN DR.	502	115	144	715	1627		26			--	--	--	--			--			
TOK BLVD.	310	120	130	547	1072		34			--	--	--	--			--			
ACORN ST.	56	7	9	42	195		8			--	--	--	--			--			
KELLY DR.	33	5	6	35	113		0			--	--	--	--			--			
MCINTOSH TRL.	38	6	7	31	135		0			--	--	--	--			--			
PASCHALL RD.	36	12	14	68	148		0			--	--	--	--			--			
WILLOW RD.	42	21	26	98	127		0			--	--	--	--			--			
SR 54	171						0			--	--	--	--			--			
DRIVEWAYS	84	1121	3241	3368	2522		0			17	15	22	105			--			
SUBTOTAL	18584	43111	41647	96680	158532		6277	15410		17	15	22	105			145	7		
AS DIRECTED	216	1389	353	320	2468	1500	323	1090		13	10	36	45					50	
PROJECT TOTALS	18800	45000	42000	97000	161000	1500	6600	16500		30	25	30	150			145	7	50	

CONCRETE SPILLWAYS,

VOID EA

VN ON

PLANS AND / OR AS DIRECTED BY ENGINEER.

UNCLASSIFIED EXCAVATION

STP-209-1(1)

M^3 91713

BORROW EXACAVTION INCL MATL

STP-209-1(1)

M^3 38114

CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3

10 EACH

CLEARING AND GRUBBING

STP-209-1(1)

LUMP SUM

MILL ASPH CONC PVMT, VARIABLE DEPTH

15000 M2

TRAFFIC CONTROL

STP-209-1(1) LUMP

CLASS B CONCRETE, INCL REINF STEEL

10 M3

FIELD ENGINEER'S OFFICE, TP 3

1 EACH

SIDE DRAINS

LOCATION	SIDE (Lt./Rt.)	LENGTH (Lm) 450mm	600mm	750mm	FLARED END SECTION (Ea.) 450mm	600mm	750mm
11+160	RT	8			2		
11+200	RT	39			2		
11+460	RT	32			2		
11+540	RT	8			2		
11+880	RT		34			2	
11+880	LT	34			2		
12+280	RT		45			2	
12+980	LT			22			2
13+450	LT	26			2		
13+860	RT	25			2		
TOTALS		172	79	22	10	4	2

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF ROAD DESIGN

WIDENING AND RECONSTRUCTION S.R. 74 JOEL COWAN PKWY
SUMMARY OF QUANTITIES SHEET

DRAWING No.