SUMMARY OF QUANTITIES-STANDARD SIGNS

STATION	INSTL. NO.	CODE	SIGNS (TYPE III REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE	QTY	SQUARE METERS	TYPE 2 (0.10) SIZE	QTY	SQUARE METERS	SIGNS (TYPE VI REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE	QTY	SQUARE METERS	TYPE 2 (0.10) SIZE	QTY	SQUARE METERS	SQUARE TUBE POST TYPE 7 LENGTH METERS	QTY	TOTAL LENGTH	TYPE 8 LENGTH METERS	QTY	TOTAL LENGTH	TYPE 9 LENGTH METERS	QTY	TOTAL LENGTH	BREAKAWAY SIGN SUPPORT EACH
MAINLINE																								
SR 74																								
10+880		R2-1(600)(55)	600X750	1	0.45										3.96	1	3.96							
10+881		R2-1(600)(55)	600X750	1	0.45										3.96	1	3.96							
10+960		W6-1(900)	900X900	1	0.81													4.57	1	4.57				
10+961		W6-3(900)	900X900	1	0.81													4.57	1	4.57				
11+120		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
11+229		R1-1(900)							900 OCT	1	0.69				3.96	1	3.96							
11+230		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
11+242		R4-7(600)	600X750	1	0.45										3.96	1	3.96							
11+260		W4-2R(900)	900X900	1	0.81													4.57	1	4.57				
11+380		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
11+451		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
11+480		W6-2(900)	900X900	1	0.81													4.57	1	4.57				
11+481		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
11+487		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
11+490		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
		R6-2R(600)	600X750	1	0.45																			
11+495		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
11+523		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
11+560		W9-1R(900)	900X900	1	0.81													4.57	1	4.57				
11+580		W3-3(900)	900X900	1	0.81																			
		W16-8a(1500)										1500X750	1	1.125				4.63	2	9.26				2
11+600		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
11+662		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
11+670		R1-1(900)							900 OCT	1	0.69				3.96	1	3.96							
		R6-3a(900)	450X600	1	0.27																			
11+688		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
11+708		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
11+756		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
11+780		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
11+786		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
11+820		M3-3(600)	600X300	1	0.20										3.96	1	3.96							
		M1-5(600)(74)	600X750	1	0.45																			
11+854		R560-5	600X750	1	0.45										3.96	1	3.96							
11+858		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
11+872		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
11+892		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
11+692		R560-5	600X750	1	0.45										3.96	1	3.96							
11+903		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
11+910		R560-5	600X750	1	0.45										3.96	1	3.96							
11+956		M3-1(600)	600X300	1	0.20										3.96	1	3.96							
		M1-5(600)(74)	600X750	1	0.45																			
11+970		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
11+980		W2-2L(750)	750X750	1	0.56																			
		W16-8(1200)							1200X300	1	0.36							4.5	1	4.5				
12+000		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
12+040		W3-3(900)	900X900	1	0.81																			
		W16-18a(1500)										1500X750	1	1.125				4.63	2	9.26				2
12+062		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
12+080		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
12+090		M3-3(600)	600X300	1	0.20										3.96	1	3.96							
		M1-5(600)(74)	600X750	1	0.45																			
12+125		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
12+143		R1-1(900)							900 OCT	1	0.69				3.96	1	3.96							
		R6-3A	450X600	1	0.27																			
12+165		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
12+170		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
12+180		R8-3A(600)	600X600	1	0.36										3.65	1	3.65							
12+220		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
12+240		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
12+255		M3-1(600)	600X300	1	0.20										3.96	1	3.96							
		M1-5(600)(74)	600X750	1	0.45																			
12+300		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
12+319		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
12+321		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
12+329		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
12+420		W3-3(900)	900X900	1	0.81																			
		W16-8a(1500)										1500X600	1	0.90				4.48	2	8.96				2
12+421		W2-2R(750)	750X750	1	0.56																			
		W16-8(1200)							1200X300	1	0.36							4.5	1	4.5				
12+540		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
12+571		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
12+600		M3-3(600)	600X300	1	0.20										3.96	1	3.96							
		M1-5(600)(74)	600X750	1	0.45																			
12+632		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
12+641		R560-5	600X750	1	0.45										3.96	1	3.96							
12+660		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
12+676		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
12+691		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
12+696		R560-5	600X750	1	0.45										3.96	1	3.96							
12+721		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
12+744		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
12+745		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
12+750		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
12+789		M3-3(600)	600X300	1	0.20										3.96	1	3.96							
		M1-5(600)(74)	600X750	1	0.45																			
12+900		W3-3(900)	900X900	1	0.81																			
		W16-8a(1500)										1500X600	1	0.90				4.48	2	8.96				2
12+901		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
12+971		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
12+974		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
12+980		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
12+990		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
13+000		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+050		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+093		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+190		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
13+165		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
13+214		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+245		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
13+248		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
13+250		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
13+440		R3-2(750)	600X600	1	0.36										3.65	1	3.65							
13+440		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
13+440		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
13+470		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+550		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
13+631		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
13+647		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
13+651		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
13+653		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
13+675		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+698		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+710		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
13+728		R1-1(900)							900 OCT	1	0.69				3.96	1	3.96							
		R6-3A	450X600	1	0.27																			
13+743		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
		SUBTOTAL #1			43.80						8.52			4.05			333.81			68.29				8

USE ON CONSTRUCTION

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-209-1(1)	24	513

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF TRAFFIC OPERATIONS

SR 74
SIGNING AND MARKING PLANS
SUMMARY OF QUANTITIES

DRAWING No. SM-

$DATE$
\\gdot.ad.local\GDOT\Operations\Safety_Design\TO Design Common\TURPEAU\NEW 322350\SUMMARYOFQUANITIES\sign data.dgn(ON=1-63))
Not a PRF