STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-209-1(1)	25	513

REVISION DATES

SUMMARY OF QUANTITIES-STANDARD SIGNS

STATION	INSTL. NO.	CODE	SIGNS (TYPE III REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE	QTY	SQUARE METERS	TYPE 2 (0.10) SIZE	QTY	SQUARE METERS	SIGNS (TYPE VI REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE	QTY	SQUARE METERS	TYPE 2 (0.10) SIZE	QTY	SQUARE METERS	SQUARE TUBE POST TYPE 7 LENGTH METERS	QTY	TOTAL LENGTH	TYPE 8 LENGTH METERS	QTY	TOTAL LENGTH	TYPE 9 LENGTH METERS	QTY	TOTAL LENGTH	BREAKAWAY SIGN SUPPORT EACH
MAINLINE																								
SR 74																								
13+758		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+828		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
13+847		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+865		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
13+870		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
13+874		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
13+876		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
13+904		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
13+909		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
13+910		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
13+935		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
13+960		R2-5A(600)	600X750	1	0.45										3.96	1	3.96							
14+010		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
14+040		W3-3(900)	900X900	1	0.81																			
		W16-18a(1500)										1500X600	1	0.90				4.48	2	8.96				2
14+099		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
14+145		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
14+171		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
14+200		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
14+230		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
14+238		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
14+240		R560-5	600X750	1	0.45										3.96	1	3.96							
14+252		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
14+270		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
14+280		R560-5	600X750	1	0.45										3.96	1	3.96							
14+291		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
14+292		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
14+333		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
14+420		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
14+430		R3-7(750)	750X600	1	0.45										3.96	1	3.96							
14+500		W3-3(900)	900X900	1	0.81																			
		W16-8a(1500)										1500X600	1	0.90				4.48	2	8.96				2
14+540		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
14+570		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
14+640		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
14+648		R560-5	600X750	1	0.45										3.96	1	3.96							
14+650		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
14+663		R1-1(900)							900 OCT	1	0.69				3.96	1	3.96							
		R6-3A	450X600	1	0.27																			
14+672		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
14+678		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
14+679		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
14+688		R560-5	600X750	1	0.45										3.96	1	3.96							
14+692		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
14+760		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
14+820		W2-2(900)	900X900	1	0.81																			
		W16-8(900)										900X600	1	0.54				4.48	2	8.96				2
14+858		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
14+900		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
14+920		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
14+921		R560-5	600X750	1	0.45										3.96	1	3.96							
14+944		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
14+947		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
14+951		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
14+960		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
15+020		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
15+029		R1-1(900)							900 OCT	1	0.69				3.96	1	3.96							
		R6-3A	450X600	1	0.27																			
15+051		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
15+058		R560-5	600X750	1	0.45										3.96	1	3.96							
15+064		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
15+120		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
15+046		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
15+200		W2-2(900)	900X900	1	0.81																			
		W16-8(800)										800X300	1	0.24				4.48	2	8.96				2
15+260		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
15+280		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
15+300		W2-2(900)	900X900	1	0.81																			
		W16-8(900)										900X600	1	0.54				4.48	2	8.96				2
15+378		R560-5	600X750	1	0.45										3.96	1	3.96							
15+380		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
15+391		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
15+410		R1-1(900)							900 OCT	1	0.69				3.96	1	3.96							
		R6-3A	450X600	1	0.27																			
15+420		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
15+480		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
15+520		W3-3(900)	900X900	1	0.81																			
		W16-18a(1500)										1500X600	1	0.90				4.48	2	8.96				2
15+640		W2-2(900)	900X900	1	0.81																			
		W16-8(800)										800X300	1	0.24				4.48	2	8.96				2
15+680		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
15+732		R560-5	600X750	1	0.45										3.96	1	3.96							
15+738		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
15+747		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
15+778		R560-5	600X750	1	0.45										3.96	1	3.96							
15+840		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
16+000		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
16+040		W3-3(900)	900X900	1	0.81																			
		W16-18a(1500)										1500X600	1	0.90				4.48	2	8.96				2
16+422		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
16+424		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
16+425		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
16+448		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
16+520		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
16+540		W3-3(900)	900X900	1	0.81																			
		W16-18a(1425)										1425X600	1	0.86										2
16+600		R1-1(900)							900 OCT	1	0.69				3.96	1	3.96							
16+601		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
16+602		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
16+620		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
16+683		R2-5A(600)	600X750	1	0.45										3.96	1	3.96							
16+700		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
16+860		R2-1(600)(40)	600X750	1	0.45										3.96	1	3.96							
16+835		R2-1(600)(45)	600X750	1	0.45										3.96	1	3.96							
16+892		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
16+922		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
16+930		R560-5	600X750	1	0.45										3.96	1	3.96							
16+940		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
16+970		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
16+980		R560-5	600X750	1	0.45										3.96	1	3.96							
16+983		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
17+014		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
17+040		R2-1(600)(40)	600X750	1	0.45										3.96	1	3.96							
17+050		R5-1A(900)	900X600	1	0.56										3.96	1	3.96							
17+122		R5-1(750)	750X750	1	0.58										3.96	1	3.96							
17+122		R560-5	600X750	1	0.45										3.96	1	3.96							
17+150		R3-2(600)	600X600	1	0.36										3.65	1	3.65							
17+151		R1-2(900)							900 TRI	1	0.36				3.96	1	3.96							
17+154		R6-2R(600)	600X750	1	0.45										3.96	1	3.96							
17+178		W2-2(750)	750X750	1	0.58																			
		W16-18(1500)										1500X600	1	0.90										2
		SUBTOTAL		90	47.13					21	8.88		10	6.92	385.91	98	385.91							20

VOID

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF TRAFFIC OPERATIONS

SR 74
SIGNING AND MARKING PLANS
SUMMARY OF QUANTITIES

DRAWING No. SM-

$DATE$ DGN PRF
...\sign data.dgn 3/10/2006 10:00:25 AM