SUMMARY OF QUANTITIES-STANDARD SIGNS

STATION	INSTL. NO.	CODE	SIGNS (TYPE III REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE	QTY	SQUARE METERS	TYPE 2 (0.10) SIZE	QTY	SQUARE METERS	SIGNS (TYPE VI REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE	QTY	SQUARE METERS	TYPE 2 (0.10) SIZE	QTY	SQUARE METERS	SQUARE TUBE POST TYPE 7 LENGTH METERS	QTY	TOTAL LENGTH	TYPE 8 LENGTH METERS	QTY	TOTAL LENGTH	TYPE 9 LENGTH METERS	QTY	TOTAL LENGTH	BREAKAWAY SIGN SUPPORT EACH
DIVIDEND	DR																							
198 M		W3-3(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				2
FROM STOP	BAR	W16-18(1500)																						
TDK BLVD/	CROSSTOWN DR																							
150 M		W3-3(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				2
FROM STOP	BAR	W16-18(1500)																						
9+955		R560-5	600X750	1	0.45										3.96	1	3.96							
10+040		R560-5	600X750	1	0.45										3.96	1	3.96							2
10+116		W4-2R(900)	900X900	1	0.81													4.57	1	4.57				
10+135		R1-1(900)	900X900	1	0.81													4.57	1	4.57				
10+152		R1-1(900)	900X900	1	0.81													4.57	1	4.57				
10+220		W3-3(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				2
		W16-18(1500)																						
KELLY DR/	MCINTOSH TRL																							
80 M FROM		W3-3(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				2
STOP BAR		W16-18(1500)																						
10+030		R560-5	600X750	1	0.45										3.96	1	3.96							
10+011		R1-1(900)	900X900	1	0.81													4.57	1	4.57				
10+160		W3-3(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				2
		W16-18(1500)																						
PASCHALL	RD/WILLOW RD																							
9+920		W3-3(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				2
		W16-18(1500)																						
10+160		W3-3(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				2
		W16-18(1500)																						
SR 54			750X600	1	0.45										3.96	1	3.96							
10+180		W3-3(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				
		W16-18(1500)													3.30	1	3.30							
10+260		D2-1(1200)							1200X300	1	0.36				4.26	1	4.26							
10+295		M2-1	530X380	1	0.20																			
		M1-5(600)(54)	600X750	1	0.45										4.26	1	4.26							
10+300		M2-1	530X380	1	0.20																			
		M1-5(600)(54)	600X750	1	0.45													4.50	1	4.50				
10+320		MB4-5(600)	600X300	1	0.20																			
		M1-1(600)	600X600	1	0.30																			
		MB6-1L(600)	600X300	1	0.20																			
10+340		D1-3(1350)										1350X750	1	1.01				3.75	1	3.75				
10+360		1-5(600)	600X600	1	0.36										3.65	1	3.65							
		1-5P(600)	600X150	1	0.09																			
10+465		R560-5	600X750	1	0.45										3.96	1	3.96							
10+492		1-5(600)	600X600	1	0.36										3.65	1	3.65							
		1-5P(600)	600X150	1	0.09							1250X750	1	0.94							3.38	1	3.38	
10+506		D1-3(1250)													3.96	1	3.96							
10+521		R3-7(750)	750X600	1	0.45																			
10+580		M3-2(600)	600X300	1	0.20										3.96	1	3.96							
		M1-5(600)(74)	600X750	1	0.45																			
10+600		D2-1(1500)							1500X300	1	0.45				3.30	1	3.30							
10+640		M2-1	600X300	1	0.20										3.96	1	3.96							
		M1-5(600)(74)	600X750	1	0.45																			
10+660		W3-3(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				2
		W16-18(1500)																						
WESTPARK	DR																							
10+030		R560-5	600X750	1	0.45										3.96	1	3.96							
10+090		W3-1(900)	900X900	1	0.81							1500X600	1	0.90				4.48	2	8.96				2
		W16-18(1500)																						
SUBTOTAL #1					43.80						8.52			4.05			329.85			68.29				8
SUBTOTAL #2					42.86						8.52			6.94			377.99			88.64				20
SUBTOTAL #3					30.10						8.96			4.46			223.96			67.24			3.6	12
SUBTOTAL #4					18.51						0.81			10.95			58.06			116.13			3.38	20
GRAND TOTAL					135.27						26.81			26.40			993.82			340.30			6.98	60

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF TRAFFIC OPERATIONS

SR 74
SIGNING AND MARKING PLANS
SUMMARY OF QUANTITIES

DRAWING NO. SM-

USE ON CONSTRUCTION

STATE GA. | PROJECT NUMBER STP-209-1(1) | SHEET NO. 27 | TOTAL SHEETS 513

REVISION DATES