STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	BRN00-0006-04(032)	10	228

STATION	INSTL NO	HIGHWAY SIGNS										SQUARE TUBE POST		
		SIGN CODE	TP 1 MATL, REFL SHEETING, TP 3			TP 2 MATL, REFL SHEETING, TP 3			TP 1 MATL, REFL SHEETING, TP 9			TYPE 7		
			SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)
9+14	1	W8-13(30)							30 " x 30 "	1	6.25	14	1	14
13+09	2	I-3a(60)				60 " x 24 "	1	10.00				13	2	26
		I-3(18)	18 " x 12 "	1	1.50									
17+23	3	R5-1(30)							30 " x 30 "	1	6.25	13	1	13
17+24	4	I-3a(60)				60 " x 24 "	1	10.00				13	2	26
		I-3(18)	18 " x 12 "	1	1.50									
17+37	5	R4-7(24)	24 " x 30 "	1	5.00							13	1	13
21+19	6	W8-13(30)							30 " x 30 "	1	6.25	14	1	14
TOTALS					8.00			20.00			18.75			106

GRASSING

VOID

LOCATION	PERMANENT GRASSING	TEMPORARY GRASSING	MULCH	AGRIC. LIME	LIQUID LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT
	ACRE	ACRE	TON	TON	GAL	TON	LBS
SR 3/US 19	7	4	21	21	18	4	700
			* 89			* 1	
BRN00-0006-04(032) TOTAL	7	4	110	21	18	5	700

* QUANTITIES FOR TEMPORARY GRASSING.

PAVEMENT MARKERS (EACH)

LOCATION	REFLECTIVE-RAISED			REFLECTIVE-RECESSED			OPAQUE		JIGGLE BAR		CHANNEL MKR	
	YELLOW	CLEAR	CLEAR/ RED	YELLOW	CLEAR		WHITE	YELLOW				
	TYPE 1	TYPE 2	TYPE 3	TYPE 1	TYPE 2	TYPE 3	TYPE 5	TYPE 6	TYPE 7	TYPE 8	TYPE 9	TYPE 10
SR 3/ US 19	36		54									
TOTALS	36		54									

TEMPORARY PIPE SLOPE DRAIN

BRN00-0006-04(032)	750 LF

TEMPORARY SILT FENCE, TYPE C

BRN00-0006-04(032)	4800 LF

TO BE USED AT LOCATIONS SHOWN ON PLANS AND/OR AS DIRECTED BY ENGINEER.

MAINTENANCE OF SILT FENCE - TP C

BRN00-0006-04(032)	2400 LF

INLET SEDIMENT TRAP

LOCATION	EACH
11+10, LT	1
11+10, RT	1
13+09, LT	1
13+09, RT	1
17+13, LT	1
17+13, RT	1
18+00, LT	1
18+00, RT	1
20+71, RT	1
21+04, LT	1
22+00, RT	1
BRN00-0006-04(032) TOTAL	11

WATER MAIN ITEMS

DESCRIPTION	UNIT	QUANTITY
CLASS A CONCRETE	CY	5
WATER MAIN, 10 IN	LF	1243
WATER SERVICE LINE, ¾ IN	LF	25
RELOCATE EXIST WATER METER, INCL BOX	EA	1
BRN00-0006-04(032)		

WATER QUALITY MONITORING AND SAMPLING

	EACH
SR 3/US 19	2
BRN00-0006-04(032) TOTAL	2

MAINT. INLET SEDIMENT TRAP

LOCATION	EACH
11+10, LT	1
11+10, RT	1
13+09, LT	1
13+09, RT	1
17+13, LT	1
17+13, RT	1
18+00, LT	1
18+00, RT	1
20+71, RT	1
21+04, LT	1
22+00, RT	1
BRN00-0006-04(032) TOTAL	11

TRAFFIC STRIPE

DESCRIPTION	UNIT	QUANTITY	
		THERMOPLASTIC	PREFORMED PLASTIC
5" SOLID WHITE	LM	0.1	
5" SOLID YELLOW	LM	0.6	
5" SKIP WHITE	GLM	0.5	
5" SKIP YELLOW	GLM	0.2	
YELLOW STRIPING	SQ. YDS.	446	99
8" SOLID CONTRAST YELLOW	LIN FEET		1000
8" SKIP CONTRAST WHITE	LIN FEET		740
8" SKIP CONTRAST YELLOW	LIN FEET		580

ARROWS (EACH)

DESCRIPTION	QUANTITY	
	PAINT	THERMOPLASTIC
TYPE 1		
TYPE 2		5
TYPE 3		
TYPE 4		
TYPE 7		

NOTE: ALL ARROWS SHALL BE WHITE UNLESS OTHERWISE SPECIFIED. SEE PLANS FOR LOCATION.

WATER QUALITY INSPECTIONS

	MONTHS
SR 3/US 19	36
BRN00-0006-04(032) TOTAL	36

EROSION CONTROL MAT, SLOPES

LOCATION	SQ YD
8+76 - 13+31, LT	633
16+88 - 23+00, LT	2017
12+45 - 13+71, RT	231
16+59 - 21+50, RT	1913
13+00 - 13+71, LT	322
16+59 - 17+00, LT	191
19+50 - 23+00, LT	215
7+40 - 10+69, RT	928
10+84 - 11+62, RT	129
11+86 - 12+45, RT	78
16+89 - 20+00, RT	216
8+79 - 13+44, LT	375
16+89 - 19+50, LT	181
AS DIRECTED BY ENGINEER	71
BRN00-0006-04(032) TOTAL	7500

LIGHTING

DESCRIPTION	UNIT	QUANTITY
DIRECTIONAL BORE - 1½ IN	LF	100
LIGHTING STD, 40 FT MH, POST TOP	EA	16
LUMINAIRE, TP 3, 250 W, HP SODIUM-MC POST TOP	EA	16
CABLE TP XHHW, AWG NO 6	LF	330
CABLE TP XHHW, AWG NO 4	LF	1700
CABLE, TP XHHW, AWG NO 2	LF	3400
CONDUIT, RIGID, 1 IN	LF	410
CONDUIT, RIGID, 1½ IN	LF	115
CONDUIT, NONMETL, TP 2, 1 IN	LF	1300
MAIN SERVICE PICK UP POINT	LS	1
ELECTRICAL JUNCTION BOX, CONC GROUND MOUNTED	EA	3
ELECTRICAL JUNCTION BOX, GALVANIZED, SIZE 12 IN X 10 IN X 8 IN	EA	6
BRN00-0006-04(032)		

CONSTRUCTION EXIT

BRN00-0006-04(032)	4 EACH

MAINT. OF CONSTRUCTION EXIT

BRN00-0006-04(032)	4 EACH

ROCK EMBANKMENT

	CU. YD.
SR 3/US 19	180
BRN00-0006-04(032) TOTAL	180

TEMPORARY SEDIMENT BARRIER OR BALED STRAW CHECK DAMS

BRN00-0006-04(032)	2200 LF

MAINTENANCE OF SEDIMENT BARRIER OR BALED STRAW

BRN00-0006-04(032)	1100 LF

H:\GDOT\322922\DGN\322922qty.dgn[I-20, 60-64]

4/11/2011

PBS&J

DATE	REVISIONS	DATE	REVISIONS
04/11/11	REV. TEMP. SILT FENCE DESC.		
	TRAFFIC STRIPE QUANT.		

STATE OF GEORGIA
DEPARTMENT
OF
TRANSPORTATION

GEORGIA
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
PROJECT BRN00-0006-04(032)
S.R. 3 OVER POTATO CREEK
UPSON COUNTY

DRAWING NO. 6-3