STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	BRN00-0006-04(032)	11	228

VOID

DITCH PROTECTION

LOCATION (STATION)	SIDE	WIDTH (ft)	DEPTH OF PROTECTION (ft)	CONCRETE DITCH PAVING, 4 IN
				SY
12+45.00 TO 13+50.00	RT	2	1.0	47
AS DIRECTED BY ENGINEER				3
BRN00-0006-04(032) TOTAL				50

IRRIGATION SYSTEM

BRN00-0006-04(032)	LUMP SUM

BRIDGE NO. 1

LOCATION (STATION)	FOUND BKFILL MATERIALS, TYPE II	BRIDGE EXCAVATION, STREAM CROSSING	GROOVED CONCRETE	SUPERSTR CONCRETE, CL AA	CLASS AA CONCRETE	PSC BEAMS, AASHTO, BULB TEE, 54 IN	PSC BEAMS, AASHTO, BULB TEE, 72 IN	BAR REINF STEEL	SUPERSTR REINF STEEL	ALUM HANDRAIL, STD 3626	PILING IN PLACE, STEEL H, HP 14 X 89	PILING IN PLACE, STEEL H, HP 14 X 102	LOAD TEST, STEEL H, HP 14 X 89 (IF REQD)	LOAD TEST, STEEL H, HP 14 X 102 (IF REQD)	DRILLED CAISSON - 66 IN	REMOVAL OF EXISTING BR, STA NO - 15+00	STN DUMPED RIP RAP, TP 1, 24 IN	PLASTIC FILTER FABRIC	TEMPORARY BARRIER METHOD 2
	CY	CY	SY	LUMP	CY	LF	LF	LB	LUMP	LF	LF	LF	EA	EA	LF	LUMP	SY	SY	LF
13+44.00 TO 16+89.00	22	177	2683	1	328	918	2502	44526	1	681	1015	640	1	1	96	1	2216	2216	1100
TOTAL	22	177	2683	1	328	918	2502	44526	1	681	1015	640	1	1	96	1	2216	2216	1100

WALL NO. 1

LOCATION (STATION)	GEOGRID REINFORCEMENT, TP A	ALUM HANDRAIL, STD 3626	MSE WALL FACE, 0-10 FT HT, WALL NO - 1	MSE WALL FACE, 10-20 FT HT, WALL NO - 1	COPING A, WALL NO - 1	COPING B, WALL NO - 1	ADDITIONAL MSE BACKFILL
	SY	LF	SF	SF	LF	LF	CY
12+45.00 TO 13+69.00	98	95	323	1069	25	99	130
TOTAL	98	95	323	1069	25	99	130

LANDSCAPING ITEMS

DESCRIPTION	UNIT	QUANTITY
SOD - TIFWAY 419 BERMUDA	SY	4640
ILEX CORNUTA - ROTUNDA, "CARISSA", 3 GAL	EA	431
ILEX VOMITORIA SCHILLINGS - NANA, DWARF YAUPON, 3 GAL	EA	556
LAGERSTROEMIA INDICA - CRAPE MYRTLE, 10-12 FT HT, 5-6 FT SPR, MIN 3 TRUNKS, WHITE AND RED	EA	10
BRN00-0006-04(032)		

STONE FILTER BERM

LOCATION	CONSTRUCT & REMOVE STONE FILTER BERM	MAINTENANCE OF STONE FILTER BERM
	LF	LF
SR 3/US 19	611	305
AS DIRECTED BY ENGINEER	39	15
BRN00-0006-04(032) TOTAL	650	320

PBS&J

DATE	REVISIONS	DATE	REVISIONS
04/11/11	ADDED TEMP. BARRIER		

STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION

GEORGIA DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
PROJECT BRN00-0006-04(032)
S.R. 3 OVER POTATO CREEK
UPSON COUNTY

DRAWING NO. 6-4

4/11/2011 h:\GDOT\322922\DGN\322922qty.dgn[1-20, 60-64]