ITEM	DESCRIPTION	UNIT	QUAN
	ROADWAY ITEMS		
150-1000	TRAFFIC CONTROL - PROJECT STP-034-3-(37)	LS	LUMP
153-1300	FIELD ENGINEERS OFFICE TP 3	EA	1
210-0100	GRADING COMPLETE-PROJECT STP-034-3-(37)	LS	LUMP
310-1101	GR AGGR BASE CRS, INCL MATL	TN	16700
402-3502	RECYCLED ASPH CONC 12.5 mm SUPERPAVE, GP 2 ONLY, INCL POLYMER MODIFIED BITUM MATL & H LIME	TN	9400
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	1000
402-3190	RECYCLED ASPH CONC 19 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	3100
402-3121	RECYCLED ASPH CONC 25 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	9000
413-1000	BITUM TACK COAT	GL	5900
432-0208	MILL ASPH CONC PVMT, 2 IN DEPTH	SY	1600
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	87400
441-0104	CONC SIDEWALK, 4 IN	SY	50
441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	1250
441-3999	CONCRETE V GUTTER	LF	3725
446-1002	PVT REINF FABRIC STRIPS, TP 2, INCL BITUM BINDER	LF	12900
	DRAINAGE ITEMS		
550-1120	STORM DRAIN PIPE, 12 IN, H 1-10	LF	20
550-1150	STORM DRAIN PIPE, 15 IN, H 1-10	LF	28
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	1548
550-3318	SAFETY END SECTION 18 IN, SIDE DRAIN, 4:1 SLOPE	EA	2
550-4215	FLARED END SECTION 15 IN, STORM DRAIN,	EA	2
668-2100	DROP INLET, GP 1	EA	32
668-4300	STORM SEWER MANHOLE, TP 1	EA	9
	TEMPORARY EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	2
163-0240	MULCH	TN	25
163-0530	CONSTRUCT AND REMOVE BALED STRAW EROSION CHECK	LF	1000
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	47
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	750
165-0020	MAINTENANCE OF TEMPORARY SILT FENCE, TP B	LF	280
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	500
165-0070	MAINTENANCE OF BALED STRAW EROSION CHECK	LF	1000
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	47
167-1000	WATER QUALITY MONITORING	EA	1
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	1500
171-0020	TEMPORARY SILT FENCE, TYPE B	LF	280
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	1000
	PERMANENT EROSION CONTROL		
163-0300	CONSTRUCTION EXIT	EA	4
603-2181	STN DUMPED RIPRAP, TP 3, 18 IN	SY	100
603-7000	PLASTIC FILTER FABRIC	SY	100
700-6910	PERMANENT GRASSING	AC	4
700-7000	AGRICULTURAL LIME	TN	8
700-7010	LIQUID LIME	GL	10
700-8000	FERTILIZER MIXED GRADE	TN	1
710-9000	PERMANENT SOIL REINFORCING MAT	SY	88
	SIGNING ITEMS		
632-0003	CHANGEABLE VARIABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4
636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3	SF	139
636-1031	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 6	SF	647
636-2070	GALV STEEL POSTS, TP 7	LF	620
636-2080	GALV STEEL POSTS, TP 8	LF	938
	PAVEMENT MARKINGS		
652-0120	PAVEMENT MARKING, WORD, TP1	EA	6
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	76
653-0170	THERMOPLASTIC PVMT MARKING, ARROW, TP 7	EA	35
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	28000
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	22000
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	295
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	28400
653-3502	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, YELLOW	GLF	600
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	12400
653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	500
654-1001	RAISED PVMT MARKERS TP 1	EA	28
654-1003	RAISED PVMT MARKERS TP 3	EA	1173
654-1010	RAISED PVMT MARKERS TP 10	EA	54
	TRAFFIC SIGNAL		
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 1	LS	LUMP
639-4004	STRAIN POLE, TP IV	EA	4

VOLKERT & ASSOCIATES, INC.
CONSULTING ENGINEERS
2515 CLEVELAND HIGHWAY
SUITE 5
DALTON, GEORGIA 30721
(706)278-9288

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF CONSULTANT DESIGN

DATE	REVISIONS	DATE	REVISIONS

DONSSPECIFICATION$$$$$$$$$$$$$$$$$$$$$$$$$$$$
SHOWDATETIME$$$$$$

GEORGIA DEPARTMENT OF TRANSPORTATION
DETAILED ESTIMATE
PROJECT STP-034-3(37)
COUNTY BIBB
DATE SH OF

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-034-3(37)	13	116

10-24-03
11-12-03

CPKOF
...\GI113\13309\GI113\C.dgn 11/12/2003 09:17:07 AM