DETAILED ESTIMATE

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-001-3(34)	8	100

REVISION DATES

ITEM NO.	DESCRIPTION	UNITS	QUANTITY
	UD01 STP-001-3(4) LAMAR CO. INTERSECTION IMPROVEMENTS SR 36 AT SR 7/US 3		
	ROADWAY		
150-1000	TRAFFIC CONTROL - STP-001-3(34)	LUMP	LUMP
210-0100	GRADING COMPLETE - STP-001-3(34)	LUMP	LUMP
310-1101	GRADED AGGR BASE CRS, INCL MATL	TN	4460
318-3000	AGGR SURF CRS	TN	500
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM , ATL & H LIME	TN	100
402-3112	RECYCLED ASPH CONC 19 mm SUOERPAVE, GP 1 OR 2, INCL BITUM	TN	550
402-3121	RECYCLED ASPH CONC 25 mm SUPERPAVE, GP 1 OR 2, INCL BITUM	TN	1110
402-3130	RECYCLED ASPH CONC 12.5 mm SUPERPAVE, GP 2 ONLY, INCL	TN	2100
413-1000	BITUM TACK COAT	GL	1040
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	1270
441-0014	DRIVEWAY CONCRETE, 4 IN TK	SY	80
441-0050	CONC SLOPE DRAIN	SY	30
441-0104	CONC SIDEWALK, 4 IN	SY	920
441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	760
441-0303	CONC SPILLWAY, TP 3	EA	2
441-0740	CONCRETE MEDIAN, 4 IN	SY	1200
441-4020	CONC VALLEY GUTTER, 6 IN	SY	85
441-6222	CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	LF	1700
500-3800	CLASS A CONCRETE, INCL REINF STEEL	CY	2
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	1900
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	LF	140
550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10	LF	150
550-2240	SIDE DRAIN PIPE, 24 IN, H 1-10	LF	50
550-4118	FLARED END SECTION 18 IN, SIDE DRAIN	EA	6
550-4124	FLARED END SECTION 24 IN, SIDE DRAIN	EA	2
550-4218	FLARED END SECTION 18 IN, STORM DRAIN	EA	4
550-4224	FLARED END SECTION 24 IN, STORM DRAIN	EA	1
634-1200	RIGHT OF WAY MARKERS	EA	14
668-1100	CATCH BASIN, GP 1	EA	7
668-2100	DROP INLET, GP 1	EA	9
668-4300	STORM SEWER MANHOLE, TP 1	EA	1
668-5000	JUNCTION BOX	EA	1
	EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	4
163-0240	MULCH	TN	47
603-2182	STN DUMPED RIP RAP, TP 3, 24 IN	SY	150
603-7000	PLASTIC FILTER FABRIC	SY	150
700-6910	PERMANENT GRASSING	AC	4
700-7000	AGRICULTURAL LIME	TN	10
700-7010	LIQUID LIME	GL	9
700-8000	FERTILIZER MIXED GRADE	TN	3
700-8100	FERTILIZER NITROGEN CONTENT	LB	2
716-2000	EROSION CONTROL MATS, SLOPES	SY	500
	TEMPORARY EROSION CONTROL		
163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	10
163-0521	CONSTRUCT AND REMOVE TEMPORARY DITCH CHECKS	EA	33
163-0530	CONSTRUCT AND REMOVE BALED STRAW EROSION CHECK	LF	925
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	9

ITEM NO.	DESCRIPTION	UNITS	QUANTITY
165-0040	MAINTENENCE OF EROSION CONTROL CHECKDAMS/DITCH CHECKS	EA	33
165-0070	MAINTENENCE OF BALED STRAW EROSION CHECK	LF	925
165-0087	MAINTENENCE OF SILT CONTROL GATE, TP 3	EA	10
165-0105	MAINTENENCE OF INLET SEDIMENT TRAP	EA	9
	TRAFFIC SIGNS		
636-1020	HIGHWAY SIGNS, TYPE 1 MATL, REFL SHEETING, TP 3	SF	90
636-1022	HIGHWAY SIGNS, TYPE 1 MATL, REFL SHEETING, TP 4	SF	140
636-1030	HIGHWAY SIGNS, TYPE 2 MATL, REFL SHEETING, TP 4	SF	6
636-2070	GALV STEEL POSTS, TP 7	LF	330
639-4004	STRAIN POLE, TP IV	EA	7
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 1	LUMP	LUMP
653-0100	THERMOPLASTIC PVMT MARKING, RR/HWY CROSSING SYMBOL	EA	6
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	14
653-0210	THERMOPLASTIC PVMT MARKING, WORD, TP 1	EA	10
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	6000
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	3600
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	170
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	1500
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	890
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	890
653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	520
654-1001	RAISED PVMT MARKERS TP 1	EA	18
654-1003	RAISED PVMT MARKERS TP 3	EA	33

GENERAL NOTES

THE FOLLOWING UTILITY OWNERS HAVE FACILITIES WHICH CONFLICT WITH CONSTRUCTION ON THIS PROJECT: (SEE PLAN AND PROFILE SHEETS FOR DETAILS)

NAME OF UTILITY	TYPE OF FACILITY
ATLANTA GAS LIGHT ATLANTA, GEORGIA	NATURAL GAS
BELLSOUTH TELECOMMUNICATIONS, INC. GRIFFIN, GEORGIA	TELEPHONE
CITY OF BARNESVILLE BARNSVILLE, GA	POWER, WATER, SEWER
CHARTER COMMUNICATIONS MCDONOUGH, GEORGIA	CABLE TV
LAMAR EMC BARNESVILLE, GEORGIA	ELECTRICITY
LAMAR COUNTY BARNESVILLE, GEORGIA	WATER
NORFOLK SOUTHERN	RAILROAD

THIS PROJECT REQUIRES A NOI

AND MARKING IS 1-800-282-7411

THE ONE CALL CENTER FOR UTILITY COORDINATION

THIS PROJECT IS LOCATED 100% WITHIN CONGRESSIONAL DISTRICT NO. 8

THIS PROJECT IS LOCATED 100% WITHIN LAMAR COUNTY

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO FURNISH ALL MATERIAL PITS ON THIS PROJECT

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
DISTRICT 3 ROAD DESIGN

DRAWING No.

•DATE•
•DGN•
•PRF•

Wed Aug 13 12:04:55 2003 \\GDOT_TM_SV20\OCF\8830mular.qcf swalerskile C:\Work\333220\RDDGN\detailedestimate.prf

6/4/2008 1:58:41 PM \\GDOT-DSN1\GOPLOT\QCF\Road_Design_Tiff-18x12_to_Tiff-36x24.qcf asanford Y:\333220-\Construction\333220_0008.tif GO-RD14