STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	STP00-8060-00(002)	29	623

VOID

STATION	INSTL. NO.	SIGN CODE	HIGHWAY SIGNS: TP 1 MATL, REFL SHEETING TP 3 SIZE	QUANTITY	SQUARE FEET	TP 2 MATL, REFL SHEETING TP 3 SIZE	QUANTITY	SQUARE FEET	TP 1 MATL, REFL SHEETING TP 9 SIZE	QUANTITY	SQUARE FEET	TP 2 MATL, REFL SHEETING TP 9 SIZE	QUANTITY	SQUARE FEET	SQUARE TUBE POST: TYPE 7 LENGTH (LIN FEET)	QUANTITY	TOTAL LENGTH	TYPE 8 LENGTH (LIN FEET)	QUANTITY	TOTAL LENGTH	TYPE 9 LENGTH (LIN FEET)	QUANTITY	TOTAL LENGTH	BREAKAWAY SIGN SUPPORT (EACH)
WHITTLESEY RD SURVEY																								
16+00	1	R1-1(36)							36" OCT	1	7.46				13	1	13							
17+25	2	R1-2(36)							36" TRI	1	3.90				13	1	13							
17+62	3	R1-1(36)							36" OCT	1	7.46				13	1	13							
19+52	4	R5-1(36)							36" X 36"	1	9.00				13	1	13							
20+00	5	W3-3(36)	36" X 36"	1	9.00										15	1	15							
		W16-8(2)(48)	48" X 24"	1	8.00																			
21+17	6	R6-2(24)	24" X 30"	1	5.00										13	1	13							
22+08	7	R6-2(24)	24" X 30"	1	5.00										13	1	13							
22+40	8	R5-1(30)							30" X 30"	1	6.25				13	1	13							
23+00	9	R2-1(24)(45)	24" X 30"	1	5.00										13	1	13							
28+00	10	R2-1(24)(45)	24" X 30"	1	5.00										13	1	13							
29+25	11	W3-3(36)	36" X 36"	1	9.00										14	1	14							
		W16-8(2)(48)	48" X 24"	1	8.00																			
29+61	12	R1-1(36)							36" OCT	1	7.46				15	1	15							
		R3-2(24)							24" X 24"	1	4.00													
29+67	13	R6-2(24)	24" X 30"	1	5.00										13	1	13							
30+24	14	R5-1(30)							30" X 30"	1	6.25				13	1	13							
32+23	15	R1-1(36)							36" OCT	1	7.46				15	1	15							
		R3-2(24)							24" X 24"	1	4.00													
32+35	16	R6-2(24)	24" X 30"	1	5.00										13	1	13							
32+50	17	W2-2R(36)	36" X 36"	1	9.00										14	1	14							
		W16-8(2)(48)	48" X 24"	1	8.00																			
32+55	18	R5-1(30)							30" X 30"	1	6.25				13	1	13							
34+00	19	R1-1(36)							36" OCT	1	7.46				15	1	15							
		R3-2(24)							24" X 24"	1	4.00													
34+09	20	R6-2(24)	24" X 30"	1	5.00										13	1	13							
34+55	21	R5-1(30)							30" X 30"	1	6.25				13	1	13							
35+75	22	W2-2R(36)	36" X 36"	1	9.00										15	1	15							
		W16-8(2)(54)	54" X 24"	1	9.00																			
36+02	23	R5-1(30)							30" X 30"	1	6.25				13	1	13							
36+12	24	R6-2(24)	24" X 30"	1	5.00										13	1	13							
36+15	25	R1-1(36)							36" OCT	1	7.46				13	1	13							
		R3-2(24)							24" X 24"	1	4.00				14	1	14							
36+53	26	R5-1(30)							30" X 30"	1	6.25				13	1	13							
36+58	27	R6-2(24)	24" X 30"	1	5.00										13	1	13							
36+65	28	R1-1(36)							36" OCT	1	7.46				14	1	14							
		R3-2(24)							24" X 24"	1	4.00													
40+34	29	R560-5	18" X 24"	1	3.00										12	1	12							
40+64	30	R1-2(36)							36" TRI	1	3.90				13	1	13							
SUBTOTAL #1					117.00						126.52						416							

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN

SUMMARY QUANTITIES

STANDARD HIGHWAY SIGNS
SHEET 1 OF 3

DRAWING No. 6-10

1/5/2009 GPLN