STATE	PROJECT NUMBER	SHEET NUMBER	TOTAL SHEETS
GEORGIA	BRZLB-77 (37)	7	7

(1) WILELLA McDONALD
SEE RW-03

****
PARCEL 1 REQ'D R/W
****

PNT	OFFSET/ DIST	STATION/ BEARING	ALIGNMENT
RW4048	60.00 L	10+43.48	HWY 16
	273.48	S 88°35'37" E	
RW4015	75.00 L	13+04.48	HWY 16
	79.50	S 76°12'38" E	
RW4052	71.63 L	13+80.00	HWY 16
	48.38	N 12°53'17" E	
RW4050	120.00 L	13+80.00	HWY 16
	22.40	S 76°12'00" E	
RW4054	119.81 L	14+00.65	HWY 16
	65.77	S 12°51'26" W	
PAR1504	54.05 L	14+01.61	HWY 16

ARC LENGTH = 371.68
CHORD BEAR = N 84°51'31" W
LNTH CHORD = 370.74
RADIUS = 1501.99

PAR1106	45.27 L	10+42.59	HWY 16
	14.76	N 2°49'13" E	
RW4048	60.00 L	10+43.48	HWY 16

REQD R/W = 7184.68 SF
REQD R/W = 0.165 ACRES
REMAINDER LT = +/- 2.4 ACRES

EASEMENT FOR THE CONSTRUCTION & MAINTAINENCE OF SLOPES = 508.41 SF

(2) WILELLA McDONALD
SEE RW-01 & 03

****
PARCEL 2 REQ'D R/W
****

PNT	OFFSET/ DIST	STATION/ BEARING	ALIGNMENT
RW4023	51.207 R	12+00.000	HWY 16

ARC LENGTH = 300.905
CHORD BEAR = S 79°41'19" E
LNTH CHORD = 300.328
RADIUS = 1402.000
DEGREE = 4° 5' 12''

PAR1124	42.839 R	15+11.171	HWY 16
	433.630	S 65°17'45" E	
RW4022	52.659 R	19+50.000	HWY 16
	7.341	S 24°42'15" W	
RW4020	60.000 R	19+50.000	HWY 16
	539.022	N 67°00'22" W	
RW4018	50.000 R	14+00.000	HWY 16
	192.683	N 80°42'46" W	
RW4023	51.207 R	12+00.000	HWY 16

REQD R/W = 8155.87 SF
REQD R/W = 0.187 ACRES
REMAINDER RT = +/- 36 ACRES

EASEMENT FOR CONSTRUCTION OF ONE (1) DRIVEWAY

(3) BLACKWATER CELLULAR CORP
SEE RW-01 & 03

****
PARCEL 3 REQ'D R/W TRACT 1
****

PNT	OFFSET/ DIST	STATION/ BEARING	ALIGNMENT
PAR1504	54.05 L	14+01.61	HWY 16
	65.77	N 12°51'26" E	
RW4054	119.81 L	14+00.65	HWY 16
	26.42	S 76°12'00" E	
RW4051	120.00 L	14+25.00	HWY 16
	48.37	S 14°42'43" W	
RW4053	71.63 L	14+25.00	HWY 16
	78.95	S 76°12'38" E	
RW4038	75.00 L	15+00.00	HWY 16
	117.06	S 71°40'57" E	
RW4024	50.00 L	10+70.37	MCINTOSH TRAIL
	109.76	N 81°01'59" W	
PAR1100	57.11 L	15+08.24	HWY 16

ARC LENGTH = 110.87
CHORD BEAR = N 75°39'17" W
LNTH CHORD = 110.85
RADIUS = 1501.99

PAR1504	54.05 L	14+01.61	HWY 16

TRACT 1 = 4130.19 SF
TRACT 1 = 0.095 ACRES

****
PARCEL 3 REQ'D R/W TRACT 2
****

PNT	OFFSET/ DIST	STATION/ BEARING	ALIGNMENT
RW4024	50.00 L	10+70.37	MCINTOSH TRAIL
	125.99	N 33°40'25" E	
RW4031	85.75 L	11+51.12	MCINTOSH TRAIL
	204.06	S 55°03'30" E	
PAR1103	45.41 R	12+87.86	MCINTOSH TRAIL
	102.80	S 85°51'42" W	
PAR1102	51.43 R	11+80.66	MCINTOSH TRAIL
	136.00	N 81°46'51" W	
RW4024	50.00 L	10+70.37	MCINTOSH TRAIL

TRACT 2 = 14347.54 SF
TRACT 2 = 0.329 ACRES

TOTAL REQD R/W TRACTS 1 & 2 = 18477.73 SF
TOTAL REQD R/W TRACTS 1 & 2 = 0.424 ACRES

REMAINDER LT = +/- 0.88 ACRES

EASEMENT FOR THE CONSTRUCTION & MAINTAINENCE OF SLOPES = 635.46 SF

DEPARTMENT OF TRANSPORTATION
RIGHT OF WAY MAP
PROJECT BRZLB-77 (37) COWETA CO.
DATE MAY 2, 2001 SHEET NO. 7

REVISIONS

DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION

Moreland Altobelli Associates, Inc.
2211 Beaver Ruin Road
Suite 190
Norcross, Georgia 30071
Telephone (770)-263-5945

	NAME	DATE		NAME	DATE
DESIGNED BY	RCR	4-11-01	DRAWN BY	MH	4-11-01
CHECKED BY	RCR	4-11-01	CHECKED BY	MH	4-11-01

SUPERVISED BY: RCR

COWETA COUNTY BRIDGE REPLACEMENT
RIGHT-OF-WAY TABLE

DRAWING NUMBER RW-03A

\hwy\98906\49906h\906h_sh3.dgn Jul 19, 2001 13:23:22