STATE	PROJECT NUMBER	SHEET NUMBER	TOTAL SHEETS
GEORGIA	BRZLB-77 (34) BRZLB-77 (38)	2	113

REVISED 4-28-03

INDEX

COVER	1
INDEX / GENERAL NOTES	2
REVISION SUMMARY SHEET	3
TYPICAL SECTIONS	4-5
SUMMARY OF QUANTITIES	6-8
DETAILED ESTIMATE	9
ROADWAY PLANS	10-13
PROFILES (ROADWAY & DRIVEWAY)	14-19
DRAINAGE MAP & PROFILES	20-22
UTILITY PLANS	23-26
GA DOT STANDARDS	27-50
CONSTRUCTION DETAILS	51-70
SIGNING & MARKING PLANS	71-74
EARTHWORK CROSS SECTIONS	75-82
BRIDGE PLANS	83-109
EROSION CONTROL PLANS	110-113
TOTAL SHEETS 114	
QUANTITIES BY AMENDMENT	9A

GEORGIA STANDARDS

SHEET NO.		DESCRIPTION	DATE
27-29	1030D	PIPE CULVERTS (3 SHEETS)	09-01
30	1030P	CORRUGATED SMOOTH LINED POLYETHYLENE PIPE CULVERT	10-98
31	1120	FLARED END SECTIONS	09-99
32	3054	END POST GUARDRAIL ATTACHMENT DETAIL	05-89
33	3901	BAR BENDING DETAILS	08-69
34	4010	"W" BEAM GUARDRAIL	07-97
35	4011-A	POST & O/S BLOCKS "W" & "T" BEAM GUARDRAIL	12-00
36	4012-C	GUARDRAIL CONNECTION AT BRIDGE END OR AT CONCRETE BARRIER END	11-99
37	4012-D	GUARDRAIL ANCH TP 1	11-99
38	4022-A	LOCATION OF GUARDRAIL	11-97
39	4040	GUARDRAIL ANCH TP 12	07-97
40	4052	G-RAIL LOCATION DETAILS FOR UNDIVIDED HIGHWAYS AND ROADS	10-97
41	4270	STD T-BEAM GUARDRAIL	11-99
42	4360	REFLECTORIZED GUARDRAIL WASHERS	02-01
43	9003	RIGHT OF WAY MARKERS	06-98
44	9017J	CONCRETE SPILLWAYS (ADJ. TO APPROACH SLABS)	02-95
45	9017R	REINFORCED CONCRETE APPROACH SLAB WITH ASPHALT INLAY	09-01
46	9028-C	SUPERELEVATION	11-97
47	9031-H	DETAIL OF TURNOUTS RURAL	10-87
48	9031-T	ISOMETRIC VIEW OF DRIVE FLARE DETAILS AT BRIDGE ENDS	08-95
49	9037	TYPICAL FILL DETAIL @ END OF BRIDGE	10-97
50	9100	TRAFFIC CONTROL GENERAL NOTES, STANDARD LEGEND, MISC. DETAILS	04-01

CONSTRUCTION DETAILS

SHEET NO.	DESCRIPTION	DATE
51	TEMP PIPE SLOPE DRAIN	02-00
52	TEMP SILT FENCE, BALED STRAW EROSION CHECK	02-01
53	BERM DITCHES, SIDE DITCHES, SURFACE DITCHES	07-80
54	TYPICAL LOCATION DETAILS FOR SILT FENCE/BALED STRAW	05-93
55	PERMANENT SOIL REINFORCING MAT	08-88
56	DETAIL OF PAVEMENT MARKING HATCHING	01-00
57	DETAILS OF PAVEMENT MARKINGS PLACEMENT (ARROWS)	01-00
58	DETAIL OF PAVEMENT MARKING ARROWS	01-00
59	SIGN PLATE DETAILS	01-00
60	SIGN ASSEMBLY-TYPICAL FRAMING DETAILS	01-00
61	SUBBASES FOR APPROACH SLAB	06-88
62-63	UNIFORM CODE SYSTEM FOR SOIL EROSION & SEDIMENT CONTROL - PERMANENT	02-98, 02-95
64-65	UNIFORM CODE SYSTEM FOR SOIL EROSION & SEDIMENT CONTROL - TEMPORARY	02-98, 3-98
66	SERRATED SLOPE/BENCHING DETAIL	01-82
67	TYPE "V" INLETS "V" GUTTER DETAILS	06-90
68	SILT CONTROL GATES FOR STRUCTURES TYPE 1,2,3,& 4	12-00
69	CONSTRUCTION EXIT	02-01
70	TYPICAL SKEWED CULVERT ENDS	12-83

GENERAL NOTES

1. THE CONTRACTOR SHALL BE REQUIRED TO USE THE ONE-CALL CENTER TELEPHONE NUMBER 1-800-282-7411 FOR THE PURPOSE OF COORDINATING THE MARKING OF UNDERGROUND UTILITIES.

   UTILITES:

   ELECTRIC: COWETA-FAYETTE EMC
   WATER: COWETA COUNTY
   TELEPHONE: BELL SOUTH TELECOMMUNICATIONS
   CABLE TV: CHARTER CABLE TV

2. THESE ENTIRE PROJECTS ARE CONSIDERED TO BE WITHIN THE LIMITS OF AN INSECT INFESTED AREA, THE CONTRACTORS ATTENTION IS CALLED TO SECTION 155 - INSECT CONTROL.

3. NO NOI ARE REQUIRED ON THESE PROJECTS.

REVISIONS					
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION

Moreland, Altobelli Associates, Inc.
2211 Beaver Ruin Road
Suite 190
Norcross, Georgia 30071
Telephone (770)-263-5945

	NAME	DATE		NAME	DATE
DESIGNED BY			DRAWN BY		
CHECKED BY			CHECKED BY		
SUPERVISED BY:					

COWETA COUNTY BRIDGE REPLACEMENT
INDEX / GENERAL NOTES
HAPPY VALLEY CIRCLE OVER BROWNS CREEK / JIM STARR ROAD OVER CEDAR CREEK

DRAWING NUMBER 1A

Mon May 08 15:50:48 2003 \\GDOT_TM_SV20\OCF\8830mular.qcf h:\workmsa\371306\rddgn\906andx.prf