SUMMARY OF QUANTITIES

TRAFFIC CONTROL	BRS00-1615-00(003)
TOTAL	LUMP SUM
GRADING COMPLETE	BRS00-1615-00(003)
TOTAL	LUMP SUM

AGGREGATE SURFACE COURSE	
AS DIRECTED BY ENGINEER	50 TON
RIGHT OF WAY MARKERS	
TOTAL	7 EACH

SIDE DRAIN PIPE, 24 INCH	
TOTAL	46 FT
SAFETY END SECTIONS, 24 INCH	
TOTAL	2 EA

TEMPORARY BARRIER, METHOD NO. 1	
TOTAL	1700 LF
PORTABLE IMPACT ATTENUATOR	
TOTAL	4 EA

W-BEAM GUARDRAIL

STATION RANGE	SIDE	FT
117+59.00 TO 118+34.00	LT	75.00
117+04.50 TO 118+17.00	RT	112.50
123+09.00 TO 128+34.00	RT	525.00
123+27.00 TO 126+14.50	LT	287.50
TOTAL		**1000.00**

GUARDRAIL ANCHORAGE, TYPE 1	
TOTAL	2 EACH

T-BEAM GUARDRAIL

STATION RANGE	SIDE	FT
118+34.00 TO 118+55.00	LT	21.00
118+17.00 TO 118+38.00	RT	21.00
122+88.00 TO 123+09.00	RT	21.00
123+06.00 TO 123+27.00	LT	21.00
TOTAL		**84.00**

GUARDRAIL ANCHORAGE, TYPE 12	
TOTAL	2 EACH

SURFACING QUANTITIES

ITEM	UNIT	MAINLINE	PAVED SHOULDER	DETOUR	FLARE	DRIVEWAY	GUARDRAIL PAVING	APPROACH SLAB	AS DIRECTED BY ENGINEER	TOTAL
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	305.0	152.8		38.2				99.2	**595.2**
RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE 1, BLEND 1, INCL BITUM MATL & H LIME	TN	262.5	37.5	438.7	9.4	7.0	25.1	18.2	159.7	**958.1**
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	122.0	61.1	540.9	15.3	11.4	40.9	33.1	164.9	**989.6**
GR AGGR BASE CRS, 6 INCH, INCL MATL	SY			2458.6					491.7	**2950.3**
GR AGGR BASE CRS, 8 INCH, INCL MATL	SY	1108.9	555.6		139.0				360.7	**2164.2**
RECYCLED ASPH CONC LEVELING INCL BITUM MATL & H LIME	TN	153.2		741.6					179.0	**1073.8**
BITUM TACK COAT	GL	311.1	66.7	420.5	16.7	4.1	14.9	21.6	171.1	**1026.7**

REINFORCED CONCRETE APPROACH SLAB, GA. STD. 9017R

STATION RANGE	REINF. CONC. APPROACH SLAB (SY)	GA. STD. 9017J CONCRETE SPILLWAY TYPE 1 (EA)		18" SLOPE DRAIN PIPE (LF)	CLASS "A" CONCRETE FOR APRON (CY)
		LEFT	RIGHT		
118+17 TO 118+47	135	1	1	170	0.34
122+97 TO 123+27	135	1	1	100	0.34
TOTAL	**270**	**2**	**2**	**270**	**0.64**

METAL DRAIN INLET

STATION	GA. DETAIL D-26				18" SLOPE DRAIN PIPE (LF)	CLASS "A" CONCRETE FOR APRON (CY)
	TYPE 1		TYPE 2			
	LEFT	RIGHT	LEFT	RIGHT		
125+50.00	1				30	0.17
125+50.00		1			40	0.17
127+49.41				1	50	0.17
TOTAL	**2**		**1**		**120**	**0.51**

MILL ASPH. CONC. VARIBLE DEPTH	
TOTAL	1760 SY

RUMBLE STRIPS	
TOTAL	6 EA

ASPHALTIC CONCRETE CURB	
TOTAL	800 FT

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 4
SUMMARY OF QUANTITIES
SR 256/ SCOOTERVILLE HWY.
@ WARRIOR CREEK

DRAWING No. 6-1