VOID

14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING AND FURNISHING ALL BORROW/WASTE PITS FOR THIS PROJECT AT NO ADDITIONAL COST TO THE DEPARTMENT. FURTHERMORE, THE CONTRACTOR WILL NOTIFY THE DISTRICT MATERIALS ENGINEER A MINIMUM OF 6 WEEKS PRIOR TO ANY LAND DISTURBING ACTIVITIES ON THE BORROW/WASTE PIT SITE TO ALLOW AMPLE TIME FOR A MATERIALS INVESTIGATION AND AN ENVIRONMENTAL EVALUATION. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ENVIRONMENTAL APPROVAL FOR BORROW/WASTE PITS, STOCK PILE SITES, BURIAL SITES, ETC. PRIOR TO USE.

15. REMOVAL OF ALL EXISTING WINGWALLS, PARAPETS, AND PORTIONS OF BOX CULVERTS SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR GRADING COMPLETE. IN ADDITION, ANY SHORING REQUIRED TO BUILD ANY DRAINAGE STRUCTURE OR ROADWAY SECTION WILL BE INCLUDED IN THE OVERALL BID PRICE FOR GRADING COMPLETE.

16. ANY CONTAMINATED SOIL EXCAVATED DURING CONSTRUCTION ACTIVITES FOR PARCELS 18, 29, 63, 76, 77, & ANDREW B. CLARK LTD. FAMILY PARTERNSHIP PARCEL (NEXT TO PARCEL 34) MUST BE DISPOSED OF AT A PERMITTED LINED MUNICIPAL SOLID WASTE LANDFILL. THE COST FOR THIS WORK WILL PAID FOR UNDER THE BID PRICE FOR OVEREXCAVATION OF CONTAMINATED SOILS.

17. ALL BORROW AND WASTE SITES FOR THIS PROJECT SHALL BE ENVIRONMENTALLY APPROVED PRIOR TO CONSTRUCTION ACTIVITIES OCCURRING IN THEM. ALL COMMON FILL OR EXCESS MATERIAL DISPOSED OUTSIDE THE PROJECT RIGHT OF WAY SHALL BE PLACED IN EITHER A PERMITTED SOLID WASTE FACILITY, A PERMITTED INERT WASTE LANDFILL OR IN AN ENGINEERED FILL. SEE SECTION 201 OF THE STANDARD SPECIFICATION AND SUPPLEMENTS THERETO FOR ADDITIONAL INFORMATION.

18. THERE IS NO SUITABLE PLACE TO BURY EXISTING CONSTRUCTION DEBRIS WITHIN THE PROJECT'S LIMITS. THE CONTRACTOR SHALL PROVIDE AN ENVIRONMENTALLY APPROVED SITE TO DISPOSE OF EXISTING CONSTRUCTION DEBRIS AT NO ADDITIONAL COST TO THE DEPARTMENT.

19. CONTRACTOR SHALL NOTIFY CHRIS HAMPTON WITH THE CITY OF MOULTRIE AT (229)668-6000, 24 HOURS PRIOR TO WORKING OVER AND OR IN CLOSE PROXIMITY TO THE EXISTING 8" GAS MAIN, TO ALLOW A CITY REPRESENTATIVE TO BE ON SITE DURING CONSTRUCTION.

20. REFER TO THE APPROVED SOIL SURVEY COMPLETED FOR THIS PROJECT FOR WELL LOCATIONS.

21. CONTRACTOR SHALL NOT DISTURB THE SWITCH STATION OWNED BY WINDSTREAM LOCATED ON PARCEL 84 AND WITHIN THE REQUIRED ROW.

22. ALL REFERENCES TO COLOR CONCRETE SHALL MEAN AND BE DEEMED TO MEAN INTEGRAL COLORED STAMPED CONCRETE SIDEWALK. THE STAMP PATTERN SHALL BE BRICK, FLEMISH. MEASUREMENT AND PAYMENT - NO SEPARATE MEASUREMENT SHALL BE MADE. PRICE FOR COLOR CONCRETE SHALL BE INCLUDED IN THE UNIT PRICE FOR SIDEWALK 4" OR 6".

THE FOLLOWING UTILITIES HAVE FACILITIES IN THE THE PROJECT AREA :

UTILITY OWNER	SERVICE
WINDSTREAM COMMUNICATIONS	TELECOMMUNICATIONS
CITY OF MOULTRIE (COMU)	CATV/ELEC/GAS/SANITARY/WATER
COLQUITT EMC (CEMC)	ELEC
MEDIACOM CABLE TV	TELECOMMUNICATIONS
MOULTRIE-COLQUITT COUNTY DEVELOPMENT AUTHORITY (MCCDA)	SANITARY SEWER

16" SANITARY SEWER FORCE MAIN OWNER:
MOULTRIE COLQUITT COUNTY DEVELOPMENT AUTHORITY (MCCOA)
CONTACT: DARRELL MOORE
TELO NO: 229-985-2131
P.O. BOX 487
MOULTRIE, GA 31776

BOX CULVERT REQUIREMENTS

MINIMUM FILL HEIGHT FROM TOP OF CULVERT TO BOTTOM OF BASE WITHIN TRAVEL WAY SHALL BE 12 INCHES.

MAXIMUM POUR LENGTH SHALL NOT EXCEED 30 FEET ALONG THE LENGTH OF THE CULVERT.

TRAVERSE CONSTRUCTION JOINTS SHALL BE PLACED IN THE BARREL, NORMAL TO THE CENTERLINE OF CULVERT, AT THE OUTSIDE SHOULDER BREAK POINTS. LONGITUDINAL BARREL REINFORCING STEEL SHALL NOT BE CONTINUOUS THROUGH THESE JOINTS, PROVIDED THAT THE JOINTS ARE MORE THAN 15 FEET FROM THE BARREL ENDS.
WHEN TRANSVERSE CONSTRUCTION JOINTS OCCUR WITHIN 15 FEET OF THE BARREL ENDS OR WITHIN THE LIMITS OF THE PAVEMENT, THE LONGITUDINAL BARREL REINFORCING SHALL THEN BE CONTINUOUS THROUGH SUCH JOINTS. THE MINIMUM LENGTH OF LAP SPLICE FOR LONGITUDINAL REINFORCING SHALL BE 24 INCHES.

TRANSVERSE CONSTRUCTION JOINTS PLACED AT ANY OTHER LOCATION NOT SPECIFIED ABOVE SHALL BE FORMED WITH NO LONGITUDINAL REINFORCING STEEL PASSING THROUGH THE JOINTS.

Columbia Engineering
LAND PLANNERS · CIVIL ENGINEERS · LANDSCAPE ARCHITECTS · SURVEYORS
2763 Meadow Church Road, Suite 100
Duluth, GA 30097-4989
Phone: (770) 925-0357
Fax: (770) 925-0565

GEORGIA811 Utilities Protection Center, Inc
Know what's below. Call before you dig.

REVISION DATES
05/06/14
05/16/14

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

GENERAL NOTES

SR133 FM SPENCE FLD TO SR35
COLQUITT COUNTY

DRAWING No. 4-002

GPLM