STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-026-3(51)	47	98

Metric

PARCEL NO. 64 REQ'D R/W RW564

PNT	OFFSET/ DIST ENGLISH	OFFSET/ DIST METRIC	STATION/ BEARING	ALIGNMENT
RW5302	77.571 R	23.64 R	15+238.344	S.R. 196
	426.068	129.87	N 40°58'17.9" E	
RW5303	77.572 R	23.64 R	15+368.210	S.R. 196
	11.271	3.44	S 61°22'42.1" E	
RW6402	88.583 R	27.00 R	15+368.944	S.R. 196
	426.586	130.02	S 40°58'17.7" W	
RW5893	88.582 R	27.00 R	15+238.921	S.R. 196
	11.172	3.41	N 58°46'37.3" W	
RW5302	77.571 R	23.64 R	15+238.344	S.R. 196

REQD R/W = 4694.25 SF (436.11 m2)
REQD R/W = 0.108 ACRES (0.044 ha)
REMAINDER = +/- 12.204 ACRES (+/- 4.825 ha)

PARCEL NO. 64 REQ'D DRWY. EASM'T. RW664

PNT	OFFSET ENGLISH	OFFSET METRIC	STATION	ALIGNMENT
RW5893	88.582 R	27.00 R	15+238.921	S.R. 196
RW6403	88.582 R	27.00 R	15+245.000	S.R. 196
RW6404	98.425 R	30.00 R	15+245.000	S.R. 196
RW5907	98.425 R	30.00 R	15+239.436	S.R. 196
RW5893	88.582 R	27.00 R	15+238.921	S.R. 196

PARCEL NO. 65 REQ'D R/W RW565

PNT	OFFSET/ DIST ENGLISH	OFFSET/ DIST METRIC	STATION/ BEARING	ALIGNMENT
RW5297	22.438 L	6.84 L	15+362.490	S.R. 196
	72.772	22.18	N 61°27'42.0" W	
RW5883	93.504 L	28.50 L	15+357.715	S.R. 196
	794.898	242.29	N 40°58'17.7" E	
RW5909	93.504 L	28.50 L	15+600.000	S.R. 196
	4.921	1.50	S 49°01'42.3" E	
RW5910	88.583 L	27.00 L	15+600.000	S.R. 196
	1474.321	449.37	N 40°58'17.7" E	
RW5911	88.582 L	27.00 L	16+049.374	S.R. 196

ARC LENGTH = 533.560 FEET(162.629 METERS)
CHORD BEAR = N 48°24'07.8" E
LNTH CHORD = 532.065 FEET(162.174 METERS)
RADIUS = 2057.082 FEET(627.000 METERS)
DEGREE = 2° 47' 7''

RW5912	88.583 L	27.00 L	16+205.000	S.R. 196
	209.949	63.99	N 47°53'02.8" E	
RW5913	127.953 L	39.00 L	16+264.608	S.R. 196
	85.912	26.19	S 11°36'58.6" E	
RW5312	45.887 L	13.99 L	16+257.186	S.R. 196

ARC LENGTH = 616.525 FEET(187.917 METERS)
CHORD BEAR = S 49°59'00.0" W
LNTH CHORD = 613.986 FEET(187.143 METERS)
RADIUS = 1959.858 FEET(597.366 METERS)
DEGREE = 2° 55' 24''

RW5313	23.944 L	7.30 L	16+072.693	S.R. 196
	2330.969	710.48	S 40°58'17.6" W	
RW5297	22.438 L	6.84 L	15+362.490	S.R. 196

REQD R/W = 195622.13 SF (18173.96 m2)
REQD R/W = 4.491 ACRES (1.817 ha)
REMAINDER = +/- 391.979 ACRES (+/- 154.969 ha)

PARCEL NO. 65 REQ'D DRWY. EASM'T. RW665

PNT	OFFSET ENGLISH	OFFSET METRIC	STATION	ALIGNMENT
RW5914	88.583 L	27.00 L	15+623.000	S.R. 196
RW5915	98.425 L	30.00 L	15+623.000	S.R. 196
RW5916	98.425 L	30.00 L	15+633.000	S.R. 196
RW5917	88.583 L	27.00 L	15+633.000	S.R. 196
RW5914	88.583 L	27.00 L	15+623.000	S.R. 196

PARCEL 65 REQ'D DRWY. EASM'T. RW765

PNT	OFFSET ENGLISH	OFFSET METRIC	STATION	ALIGNMENT
KC130061	88.58 L	27.000 L	15+753.999	SR 196
KC130062	98.42 L	30.000 L	15+753.999	SR 196
KC130063	98.42 L	30.000 L	15+766.000	SR 196
KC130064	88.58 L	27.000 L	15+766.000	SR 196
KC130061	88.58 L	27.000 L	15+753.999	SR 196

PARCEL 65A REQ'D R/W RW565A1

PNT	OFFSET/ DIST ENGLISH	OFFSET/ DIST METRIC	STATION/ BEARING	ALIGNMENT
KC128535	77.63 R	23.663 R	15+600.000	SR 196
	262.47	80.000	N 40°57'19.9" E	
KC128536	77.56 R	23.640 R	15+680.000	SR 196
	11.02	3.360	S 49°01'42.2" E	
KC128537	88.58 R	27.000 R	15+680.000	SR 196
	262.46	79.999	S 40°58'17.6" W	
KC128534	88.58 R	27.000 R	15+600.000	SR 196
	10.95	3.337	N 49°01'52.1" W	
KC128535	77.63 R	23.663 R	15+600.000	SR 196

REQD R/W = 2883.54 SF (267.89 m2)
REQD R/W = 0.067 ACRES (0.027 ha)
REMAINDER = +/- 38.963 ACRES (+/- 15.768 ha)

PARCEL 65A REQ'D DRWY. EASM'T. RW665A1

PNT	OFFSET ENGLISH	OFFSET METRIC	STATION	ALIGNMENT
KC130057	98.43 R	30.000 R	15+621.992	SR 196
KC130058	88.58 R	27.000 R	15+621.993	SR 196
KC130059	88.58 R	27.000 R	15+633.993	SR 196
KC130060	98.43 R	30.000 R	15+633.992	SR 196
KC130057	98.43 R	30.000 R	15+621.992	SR 196

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
R/W AND LIMIT OF ACCESS

DATE	REVISIONS	DATE	REVISIONS
9-22-05	ADDED REQD FOR PAR 65A		
1-20-06	ADDED DWESMT FOR PAR 65 & 65A		

LAND LOT NO. NA
LAND DISTRICT NA
GMD 1892

GEORGIA
DEPARTMENT OF TRANSPORTATION
RIGHT-OF-WAY PLAN
PROJECT STP-026-3(51)
COUNTY LIBERTY
DATE MAY 15, 2003 SH 47 OF 98