STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	EDS00-0545-00(014)	22a	627

WATER RELOCATION QUANTITES

VOID

FIRE HYDRANT	
QUANTITY	UNIT
1	EA

CLASS A CONRETE	
QUANTITY	UNIT
6	CY

**TO BE USED FOR CONCRETE THRUST BLOCKS.

WATER MAIN, 12 IN		
DESCRIPTION	UNIT	QUANTITY
C900, DR 18, CLASS 150	LF	548

WATER MAIN, 6 IN		
DESCRIPTION	UNIT	QUANTITY
CLASS 350, DUCTILE IRON	LF	10

GATE VALVE, 12 IN	
QUANTITY	UNIT
2	EA

GATE VALVE, 6 IN	
QUANTITY	UNIT
1	EA

REMOVE EXIST FIRE HYDRANT	
QUANTITY	UNIT
1	EA

TAPPING SLEEVE & VALVE ASSEMBLY, 12 IN x 12 IN	
QUANTITY	UNIT
2	EA

GEORGIA
DEPARTMENT OF TRANSPORTATION

• Engineering
• Architecture
• Planning
• Construction Management
3169 Holcomb Bridge Road
Suite 455
Atlanta, Georgia 30071
(404) 329-5900

REVISION DATES		
6-28-2011		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES

US 1/SR 4 WIDENING
TOOMBS/EMANUEL COUNTIES

DRAWING No. 6-007

1/5/2009 GPLN