

SUMMARY OF SIGNING QUANTITIES												
LOCATION	INSTL. NO.	CODE	POSTS									GROUND—MOUNTED BREAKAWAY SIGN SUPPORT EA
			TYPE 7			TYPE 8			TYPE 9			
			LENGTH	QTY	TOTAL	LENGTH	QTY	TOTAL	LENGTH	QTY	TOTAL	
			LF		LF	LF		LF	LF		LF	
EB ON RAMP												
51+93 RT		R5—10A	16.00	1	16.00							
54+00 RT		W1—11R							17.00	1	17.00	
		W13—1P										
56+00 RT		W1—8L							15.25	1	15.25	
56+80 RT		W1—8L							15.25	1	15.25	
57+60 RT		W1—8L							15.25	1	15.25	
58+40 RT		W1—8L							15.25	1	15.25	
59+20 RT		W1—8L							15.25	1	15.25	
62+50 RT		W4—6				16.00	2	32.00				
EB OFF RAMP												
28+00 RT		W13—7							16.00	2	32.00	
31+00 LT		W1—8R	15.50	1	15.50							
31+80 LT		W1—8R	15.50	1	15.50							
32+60 LT		W1—8R	15.50	1	15.50							
33+40 LT		W1—8R	15.50	1	15.50							
34+20 LT		W1—8R	14.00	1	14.00							
35+00 LT		W1—8R	8.00	1	8.00							
35+80 LT		W1—8R	8.00	1	8.00							
36+60 LT		W1—8R	8.00	1	8.00							
37+40 LT		W1—8R	8.00	1	8.00							
41+00 LT		R5—1A	5.50	1	5.50							
41+00 RT		R5—1A	13.00	1	13.00							
42+58 RT		R560—5	14.75	1	14.75							
43+00 RT		R5—1	13.50	1	13.50							
MARINERS WAY												
11+27 RT		R560—5	13.00	1	13.00							
PROJECT TOTAL:					812			391			461	6

BRIDGE MOUNTED SIGNS				
LOCATION	INSTL. NO.	CODE	HIGHWAY SIGNS TP 1 MATL, REFL SHEETING, TP 3	
			SIZE	SF
KING GEORGE BLVD.				
34+84 RT		R3-5L	30X36	7.50
		M-SPECIAL	36X36	9.00
36+81 LT		R3-5L	30X36	7.50
		M-SPECIAL	36X36	9.00
PROJECT TOTAL:				33

SIGN MODIFICATIONS			
LOCATION	SIGN NO.	REMOVE HIGHWAY SIGN - SPECIAL ROADSIDE	REMOUNT UNMODIFIED HIGHWAY SIGN, SPECIAL ROADSIDE
		EA	EA
SR 204			
443+55 CL		1	1
444+30 RT		1	1
465+88 RT		1	1
477+22 LT		1	1
PROJECT TOTAL:		4	4

SPECIAL ROADSIDE SIGNS												
LOCATION	INSTL. NO.	SIGN NO.	HIGHWAY SIGNS, ALUM EXTRUDED PANELS, REFL SHEETING,TP 3		GALVANIZED STEEL STRUCTURAL SHAPE POSTS				FOOTINGS			
					LENGTH LF	POST SIZE	STUB LENGTH		FOOTING TYPE	FOOTING DEPTH "D"	PILING IN PLACE, SIGNS STEEL H, HP 12 X 53	
			SIZE	SF			LF	LB			LF	CLASS A CONCRETE, SIGNS CY
STA 477+22 RT	1	D2-3	78X48	26.00	15.50	W6 X 9	2	139.5	3	9.00	7.00	1.00
					14.50	W6 X 9	2	130.50	3	9.00	7.00	1.00
PROJECT TOTAL:				26				270			14	2

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR
& MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
REQ'D R/W & LIMIT OF ACCESS

McGee Partners, Inc.
www.mcgeepartners.com

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY
SUMMARY QUANTITIES

DRAWING No.
06-020

SR 204 AT KING GEORGE BLVD.

10/17/2011
CONBOR