STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-4001(7)	52	77

****
PARCEL 96A (CITY OF SAVANNAH) REQ'D R/W RW5096A1
****

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
RW1397	46.433	R	119+58.921	MIDDLEGROUND ROAD
	70.954		S 76°19'46.7" E	
RW1555	45.452	R	120+29.868	MIDDLEGROUND ROAD
	5.904		S 46°40'26.3" W	
RW1399	50.447	R	120+26.721	MIDDLEGROUND ROAD
	5.381		S 46°39'33.5" W	
RW5212	55.000	R	120+23.854	MIDDLEGROUND ROAD
	35.451		S 46°39'33.5" W	
RW5885	85.000	R	120+04.965	MIDDLEGROUND ROAD
	61.112		N 56°26'02.7" W	
RW5211	65.000	R	119+47.218	MIDDLEGROUND ROAD
	21.947		N 46°41'12.5" E	
RW1397	46.433	R	119+58.921	MIDDLEGROUND ROAD

REQD R/W = 2043.79 SF
REQD R/W = 0.047 ACRES
REMAINDER = +/- 4.620 ACRES

****
PARCEL 97 (MARTA CRUZ CAMACHO AND RAFAEL CRUZ ORTIZ)
REQ'D R/W RW5097
****

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
RW1399	50.447	R	120+26.721	MIDDLEGROUND ROAD
	13.000		S 75°29'04.7" E	
RW1400	50.459	R	120+39.721	MIDDLEGROUND ROAD
	4.847		S 6°00'08.9" E	
RW5213	55.000	R	120+41.416	MIDDLEGROUND ROAD
	17.562		N 75°32'13.0" W	
RW5212	55.000	R	120+23.854	MIDDLEGROUND ROAD
	5.381		N 46°39'33.5" E	
RW1399	50.447	R	120+26.721	MIDDLEGROUND ROAD

REQD R/W = 69.49 SF
REQD R/W = 0.002 ACRES
REMAINDER = +/- 0.186 ACRES

****
PARCEL 98 (DEBORAH A. PADILLA) REQ'D R/W RW5098
****

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
RW1400	50.459	R	120+39.721	MIDDLEGROUND ROAD
	92.001		S 75°29'08.2" E	
RW1406	50.541	R	121+31.722	MIDDLEGROUND ROAD
	4.459		S 15°01'24.8" W	
RW5214	55.000	R	121+31.679	MIDDLEGROUND ROAD
	90.263		N 75°32'13.0" W	
RW5213	55.000	R	120+41.416	MIDDLEGROUND ROAD
	4.847		N 6°00'08.9" W	
RW1400	50.459	R	120+39.721	MIDDLEGROUND ROAD

REQD R/W = 410.08 SF
REQD R/W = 0.009 ACRES
REMAINDER = +/- 0.184 ACRES

****
PARCEL 99 (AUDREY SCOTT) REQ'D R/W RW5099
****

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
RW1406	50.541	R	121+31.722	MIDDLEGROUND ROAD
	58.929		S 75°29'04.4" E	
RW1408	50.595	R	121+90.651	MIDDLEGROUND ROAD
	6.036		S 28°39'56.3" E	
RW5215	55.000	R	121+94.777	MIDDLEGROUND ROAD
	63.099		N 75°32'13.0" W	
RW5214	55.000	R	121+31.679	MIDDLEGROUND ROAD
	4.459		N 15°01'24.8" E	
RW1406	50.541	R	121+31.722	MIDDLEGROUND ROAD

REQD R/W = 270.36 SF
REQD R/W = 0.006 ACRES
REMAINDER = +/- 0.209 ACRES

****
PARCEL 100 (JAMES A. BRADFORD AND KATHERINE N. BRADFORD)
REQ'D R/W RW5100
****

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
RW1413	50.704	R	123+10.716	MIDDLEGROUND ROAD
	88.348		S 75°29'05.8" E	
RW1414	50.784	R	123+99.064	MIDDLEGROUND ROAD
	14.245		S 18°08'38.6" W	
RW5217	65.000	R	123+98.150	MIDDLEGROUND ROAD
	102.693		N 75°32'13.0" W	
RW5216	65.000	R	122+95.456	MIDDLEGROUND ROAD
	20.910		N 61°19'49.0" E	
RW1413	50.704	R	123+10.716	MIDDLEGROUND ROAD

REQD R/W = 1362.08 SF
REQD R/W = 0.031 ACRES
REMAINDER = +/- 0.182 ACRES

****
PARCEL 100 (JAMES A. BRADFORD AND KATHERINE N. BRADFORD)
REQ'D DRWY. EASM'T. RW7100
****

PNT	OFFSET		STATION	ALIGNMENT
RW5216	65.000	R	122+95.456	MIDDLEGROUND ROAD
RW5633	98.596	R	122+93.291	MIDDLEGROUND ROAD
RW5632	97.471	R	122+75.811	MIDDLEGROUND ROAD
RW1417	82.501	R	122+76.776	MIDDLEGROUND ROAD
RW5216	65.000	R	122+95.456	MIDDLEGROUND ROAD

****
PARCEL 100 (JAMES A. BRADFORD AND KATHERINE N. BRADFORD)
REQ'D DRWY. EASM'T. RW7100
****

PNT	OFFSET		STATION	ALIGNMENT
RW5218	65.000	R	125+48.160	MIDDLEGROUND ROAD
RW5635	65.000	R	125+93.000	MIDDLEGROUND ROAD
RW5636	85.000	R	125+93.000	MIDDLEGROUND ROAD
RW5634	85.000	R	125+46.873	MIDDLEGROUND ROAD
RW5218	65.000	R	125+48.160	MIDDLEGROUND ROAD

****
PARCEL 102 (CORNERSTONE CHURCH OF SAVANNAH,INC.)
REQ'D DRWY. EASM'T. RW8102
****

PNT	OFFSET		STATION	ALIGNMENT
RW5637	65.000	R	128+70.000	MIDDLEGROUND ROAD
RW5639	65.000	R	129+12.000	MIDDLEGROUND ROAD
RW5640	85.000	R	129+12.000	MIDDLEGROUND ROAD
RW5638	85.000	R	128+70.000	MIDDLEGROUND ROAD
RW5637	65.000	R	128+70.000	MIDDLEGROUND ROAD

****
PARCEL 102 (CORNERSTONE CHURCH OF SAVANNAH,INC.)
REQ'D R/W RW5102
****

PNT	OFFSET/ DIST		STATION/ BEARING	ALIGNMENT
RW1418	45.784	R	123+99.387	MIDDLEGROUND ROAD
	150.000		S 75°28'37.2" E	
RW1419	45.940	R	125+49.387	MIDDLEGROUND ROAD
	376.803		S 75°28'48.4" E	
RW2000	46.314	R	129+26.190	MIDDLEGROUND ROAD
	18.733		S 18°32'47.7" W	
RW2002	65.000	R	129+24.856	MIDDLEGROUND ROAD
	526.707		N 75°32'13.0" W	
RW5217	65.000	R	123+98.150	MIDDLEGROUND ROAD
	14.245		N 18°08'38.6" E	
RW1414	50.784	R	123+99.064	MIDDLEGROUND ROAD
	5.011		N 18°09'26.1" E	
RW1418	45.784	R	123+99.387	MIDDLEGROUND ROAD

REQD R/W = 9981.39 SF
REQD R/W = 0.229 ACRES
REMAINDER = +/- 3.925 ACRES

****
PARCEL 102 (CORNERSTONE CHURCH OF SAVANNAH,INC.)
REQ'D DRWY. EASM'T. RW7102
****

PNT	OFFSET		STATION	ALIGNMENT
RW5218	65.000	R	125+48.160	MIDDLEGROUND ROAD
RW5635	65.000	R	125+93.000	MIDDLEGROUND ROAD
RW5636	85.000	R	125+93.000	MIDDLEGROUND ROAD
RW5634	85.000	R	125+46.873	MIDDLEGROUND ROAD
RW5218	65.000	R	125+48.160	MIDDLEGROUND ROAD

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS —C— —F—
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
R/W AND LIMIT OF ACCESS

DATE	REVISIONS	DATE	REVISIONS
3-6-03	CHANGED OWNERS NAME PARCEL NO.102		

LAND LOT NO.
LAND DISTRICT
GMD 6TH

GEORGIA
DEPARTMENT OF TRANSPORTATION
RIGHT OF WAY PLAN

PROJECT STP-4001(7)
COUNTY CHATHAM COUNTY
DATE MAY. 4, 2001 SH 52 OF 77