DRAINAGE STRUCTURE LOCATION			STRUCTURE NO.	STORM DRAIN PIPE								FLARED END SECTIONS					CONCRETE HEADWALLS					SEE CONSTRUCTION DETAILS	HEIGHT OF FILL ABOVE PIPE	STRUCTURE DEPTH	ADDITIONAL STRUCT. DEPTHN GP1	ADDITIONAL STRUCT. DEPTHN GP2	D. I. STD 1019A W/ HOOD GP1	D. I. STD D4	D. I. STD 1019A TYPE D GP1	D. I. STD 1019A TYPE A GP1	D. I. STD 1019A TYPE A GP2	STORM MANHOLE STD 1011A TYPE 1	STORM MANHOLE STD 1011A TYPE 2	CATCH BASIN GA STD 1033D GP1	CATCH BASIN GA STD 1033D GP2	CATCH BASIN GA STD 1034D GP1	CATCH BASIN GA STD 1034D GP2	TEMPORARY DRAIN STRUCTURES	RIPRAP TYPE 3 12" THICK	PLASTIC FILTER FABRIC	COMMENTS
STATION	SIDE	ROADWAY		18"	24"	30"	36"	42"	48"	54"	60"	18"	24"	30"	36"	42"	18"	24"	30"	36"	54"	SPECIAL	FT	FT	FT	FT	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	SY	SY	SY	
12+48	RT	MAINLINE VETERANS PARKWAY	A-01	9																			1-10	4.80	1									1								
12+48	RT	MAINLINE VETERANS PARKWAY	A-05																					5.47	2								1									MH OVER EXIST. DBL. 24" REMOVE FES
13+20	RT	MAINLINE VETERANS PARKWAY	A-03																					7.55	3								1									REMOVE FES
14+24	MED	MAINLINE VETERANS PARKWAY	A-36																					6.03	3									1								REMOVE OLD & REPLACE
14+44	RT	MAINLINE VETERANS PARKWAY	A-06		12																		1-10	6.87	3								1									MH OVER EXIST. DBL 42". REMOVE FES
14+52	RT	MAINLINE VETERANS PARKWAY	A-02																					6.48	3									1								CB OVER EXIST PIPE
14+60	MED	MAINLINE VETERANS PARKWAY	A-35																					7.88	4							1										REPLACE EXIST. MH OVER PIPE
16+28	MED	MAINLINE VETERANS PARKWAY	A-10	50																			1-10	7.14	4									1								
16+28	RT	MAINLINE VETERANS PARKWAY	A-09																					6.39	3									1								
17+57	MED	MAINLINE VETERANS PARKWAY	A-13	43																			1-10	3.3										1								
17+57	RT	MAINLINE VETERANS PARKWAY	A-12																					5.7	2									1								
17+57	RT	MAINLINE VETERANS PARKWAY	A-11	10																			1-10	4.0					1													
18+70	RT	MAINLINE VETERANS PARKWAY	A-14	10																			1-10	5.09	2							1										
18+70	RT	MAINLINE VETERANS PARKWAY	A-32																					3.66					1													
19+77	MED	MAINLINE VETERANS PARKWAY	A-16	32																			1-10	4.4	1									1								
19+77	RT	MAINLINE VETERANS PARKWAY	A-17																					4.68	1									1								
19+77	RT	MAINLINE VETERANS PARKWAY	A-33	10																			1-10	1.9					1													
21+00	LT	MAINLINE VETERANS PARKWAY	A-19	32																			1-10	3.5												1						
21+00	RT	MAINLINE VETERANS PARKWAY	A-20																					3.83												1						
21+00	RT	MAINLINE VETERANS PARKWAY	A-34	10																			1-10	2.07					1													
25+91	LT	MAINLINE VETERANS PARKWAY	A-24	90																			1-10	3.5										1								
25+91	RT	MAINLINE VETERANS PARKWAY	A-23																					4.12	1									1								
27+53	RT	MAINLINE VETERANS PARKWAY	A-26																					3.5										1								
27+85	RT	MAINLINE VETERANS PARKWAY	A-30																					2.87			1															
28+02	LT	MAINLINE VETERANS PARKWAY	A-27																					3.5										1								
28+08	LT	MAINLINE VETERANS PARKWAY	A-28																					3.22							1											
28+21	RT	MAINLINE VETERANS PARKWAY	A-3A																					5.32	2		1															
29+33	LT	MAINLINE VETERANS PARKWAY	B-01																					3.18						1												
		SUBTOTAL #1		296	12	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				35	0	2	4	1	1	0	2	3	13	0	2	0	0	0	0	

P.C. Simonton & Associates, Inc.
Consulting Engineers

HINESVILLE OFFICE
309 N. MAIN STREET
P.O. BOX 649
HINESVILLE, GA 31313
912-368-5212

GREENSBORO OFFICE
1050 PARKSIDE COMMONS
SUITE 101
GREENSBORO, GA 30642
706-454-0870

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES

VETERANS PARKWAY

DRAWING No. 6-003