STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	PLH 149-1 (34)	13	227

SUMMARY OF PAVING QUANTITIES

STATION RANGE	SURFACING AND BASE						RECONSTRUCT EXISTING ASPHALT DRIVEWAYS			
	12.5mm SUPERPAVE	19mm SUPERPAVE	25mm SUPERPAVE	200mm GRADED AGGREGATE BASE COURSE, INCLUDING MATERIAL	RECYCLED ASPHALTIC CONCRETE LEVELING INCLUDING BITUMINOUS MATERIAL AND HYDRATED LIME	BITUMINOUS TACK COAT	12.5mm SUPERPAVE	19mm SUPERPAVE	150mm GRADED AGGREGATE BASE COURSE, INCLUDING MATERIAL	BITUMINOUS TACK COAT
	Mg	Mg	Mg	m^2	Mg	l	Mg	Mg	m^2	l
SUBTOTAL	10 290	13 125	13 625	52 600	3155	58 500	26.3	35	292	29
TOTAL	10 500	13 500	14 000	53 000	3300	60 000	30	50	350	35

NOTE:
AGGREGATE BASE COURSE FOR DRIVEWAYS INCLUDED IN TOTAL FOR AGGREGATE SURFACE COURSE.

PAVEMENT REINFORCING FABRIC STRIPS, TYPE 2, INCLUDING BITUMINOUS BINDER	
10.000	m

STONE DUMPED RIP-RAP, TYPE 3 300mm THICKNESS	
m^2	25

AGGREGATE SURFACE COURSE INCLUDING MATERIAL AND HAUL		
FOR USE IN INCLEMENT WEATHER TO FACILITATE THE MOVEMENT OF LOCAL TRAFFIC ALONG ROADWAY CONSTRUCTION AND TO PERMIT INGRESS / EGRESS AT DRIVES.		
GRADED AGGREGATE		ART.815.01
DESCRIPTION	UNIT	TOTAL
AS DIRECTED BY ENGINEER	MEGAGRAM	2000

CLASS B CONCRETE FOR CULVERT PLUGS	
m^3	10

PERMANENT TIMBER TYPE BARRICADE GA STD 9039	
M	8

UTILITY ADJUSTMENTS		
ADJUST WATER VALVE BOX TO GRADE	EA	18
ADJUST MANHOLE TO GRADE	EA	9

DRAINAGE ADJUSTMENTS		
ADJUST MINOR STRUCTURE TO GRADE	EA	8
RECONSTRUCT CATCH BASIN, GROUP 1	EA	17

GRADING COMPLETE PLH 149-1(34)	
TOTAL	LUMP SUM

MILL ASPHALTIC CONCRETE PAVEMENT, 40mm	
m^2	580

150mm UNDERDRAIN PIPE GA STD 9029B INCLUDING DRAINAGE AGGREGATE	
m	100

DATE	REVISIONS	DATE	REVISIONS

GEORGIA
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
PROJECT PLH 149-1 (34)
COUNTY LIBERTY
DATE: JANUARY, 1999

PLNCON

PRF SSPENTABLESS

9/5/2008 9:16:44 AM \\GDOT-DSN1\GOPLOT\QCF\Road_Design_Tiff-18x12_to_Tiff-36x24.qcf asanford Y:\562160-\Construction\562160_0013.tif GO-RD14