5/7/2013 8:12:51 AM \\GDOT-DSN1\GOPLOT\QCF\OGC.qcf mhandley K:\610750\2.08 DGN\PRF's\06_Summary of Quantities\610750GN01_02.prf

PAVING QUANTITES

LOCATION	PLAIN PC CONC PVMT, CL 3 CONC, 12 INCH THK, WITH 1½IN DOWEL BARS	ASPH CONC 12.5 MM PEM, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	RECYC. ASPH CONC 12.5 MM, SMA, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	RECYC. ASPH. CONCRETE 12.5 MM SUPERPAVE, GP 2 ONLY, INCL. BITUM MATL & H. LI	RECYC. ASPH. CONCRETE 19 MM SUPERPAVE, GP 1 OR 2, INCL. BITUM MATL & H. LIME	RECYCLED ASPH CONC 25MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	GR AGGR BASE CRS, 6 INCH, INCL MATL	GR AGGR BASE CRS, 8 INCH, INCL MATL	GR AGGR BASE CRS, 12 INCH, INCL MATL	GR AGGR BASE CRS, 14 INCH, INCL MATL	GR AGGR BASE CRS, 16 INCH, INCL MATL	MILL ASP CONC PVMT, VARIABLE DEPTH	RECYLCED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	BITUM TACK COAT
	SY	TN	TN	TN	TN	TN	TN	TN	TN	TN	TN	SY	TN	GL
S.R. 156 - FULL DEPTH				1280	1706	3412				12662				1552
S.R. 156 - OVERLAY				1584	2112							19195		960
175 - FULL DEPTH		2379	3001	1825	6402	41608					54301			8728
175 - OVERLAY		1933	2363									28635	1721	1432
175 - GUARDRAIL PAVING				301	402			1702						183
RAMPS - FULL DEPTH	26012				4292				18205					
RAMPS - GUARDRAIL PAVING	418			78	69				585					
SIDEROADS - FULL DEPTH				1293	1724	2585		7309						1568
SIDEROADS - OVERLAY				54	72							646		33
SIDEROADS - GUARDRAIL PAVING				74	99			416						45
STAGING - TEMP PAVEMENT	103				103				73					
STAGING - TEMP MEDIAN		1500		1834	2445	7333			15555					4447
STAGING - TEMP SHOULDER				436	582	3779					4931			1322
PAVING TOTAL	26533	5812	5364	8759	20008	58717		9427	34418	12662	59232	48476	1721	20270
DRIVEWAY TOTAL				231	421		977							179
PAVING TOTAL	26533	5812	5364	8990	20429	58717	977	9427	34418	12662	59232	48476	1721	20449

VOID

CLASS B CONCRETE BASE OR PVMT WIDENING

	UNIT	QUANTITY
TOTAL	CY	37

FOR USE IN AREAS OF NARROW PAVING WIDENING NEXT TO CURB AND GUTER AS DIRECTED BY THE ENGINEER.

PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH

SECTION 446

TOTAL	21972 LF

GRADING COMPLETE IM000-0075-03(189)

TOTAL	LS

SHORING IM000-0075-03(189)

TOTAL	LS

TRAFFIC CONTROL IM000-0075-03(189)

	UNIT	QUANTITY
TOTAL	LS	1

TRAFFIC CONTROL WORK ZONE LAW ENFORCEMENT

	UNIT	QUANTITY
TOTAL	HR	2000

RUMBLE STRIPS GROUND-IN-PLACE (CONTINUOUS)

	GLM
411+19.20 to 471+38.69 RT	1.14
411+19.20 to 471+38.69 LT	1.14
TOTAL	2.28

AGG SURF CRS

	UNIT	QUANTITY
TOTAL	TN	1000

TO BE USED AS DIRECTED BY THE ENGINEER

1/5/2009 GQUANT

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES
04/29/13

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROAD DESIGN

SUMMARY OF QUANTITIES

PROJECT IM000-0075-03(189)
GORDON COUNTY

DRAWING No. 06-002

5/7/2013 8:12:51 AM \\GDOT-DSN1\GOPLOT\QCF\OGC.qcf mhandley K:\610750\2.08 DGN\PRF's\06_Summary of Quantities\610750GN01_02.prf