COUNTY	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
	NH000-0018-01(59)	31	778

VOID

STATION	INSTL. NO.	SIGN CODE	HIGHWAY SIGNS: TP 1 MATL. REFL SHEETING TP 3 SIZE	QUANTITY	SQUARE FEET	TP 2 MATL. REFL SHEETING TP 3 SIZE	QUANTITY	SQUARE FEET	TP 1 MATL. REFL SHEETING TP 9 SIZE	QUANTITY	SQUARE FEET	TP 2 MATL. REFL SHEETING TP 9 SIZE	QUANTITY	SQUARE FEET	SQUARE TUBE POST: TYPE 7 LENGTH (FEET)	QUANTITY	TOTAL LENGTH	TYPE 8 LENGTH (FEET)	QUANTITY	TOTAL LENGTH	TYPE 9 LENGTH (FEET)	QUANTITY	TOTAL LENGTH	BREAKAWAY SIGN SUPPORT (EACH)
I-75 SB OFF RAMP																								
12+80	77	R5-1A							30X30	1	6.25				13	1	13							
12+80	78	R5-1A							30X30	1	6.25				13	1	13							
11+34	79	M3-2	24X12	1	2.00													15	2	30				2
		M3-4	24X12	1	2.00																			
		M1-5	24X24	1	4.00																			
		M1-5	24X24	1	4.00																			
		M6-1L	24X12	1	2.00																			
		M6-1R	24X12	1	2.00																			
10+94	80	R560-5	18X24	1	3.00										13	1	13							
10+90	81	R5-1A							30X30	1	6.25				13	1	13							
10+90	82	R5-1A							30X30	1	6.25				13	1	13							
10+70	83	R1-2							36 TRI	1	3.90				13	1	13							
I-75 NB OFF RAMP																								
28+14	84	R5-1A							30X30	1	6.25				13	1	13							
28+14	85	R5-1A							30X30	1	6.25				13	1	13							
																		15	2	30				
29+25	86	M3-4	24X12	1	2.00																			2
		M3-2	24X12	1	2.00																			
		M1-5	24X24	1	4.00																			
		M1-5	24X24	1	4.00																			
		M6-1R	24X12	1	2.00																			
		M6-1L	24X12	1	2.00																			
29+89	87	R560-5	18X24	1	3.00										13	1	13							
30+08	88	R1-2							36 TRI	1	3.90				13	1	13							
30+10	89	R5-1							30X30	1	6.25				13	1	13							
30+10	90	R5-1							30X30	1	6.25				13	1	13							
30+34	91	R6-2R	24X30	1	5.00																13	1	13	
30+34	92	R6-2R	24X30	1	5.00																13	1	13	
I-75 NB ON RAMP																								
11+22	93	R1-2							36 TRI	1	3.90				13	1	13							
12+18	94	R5-10A	30X36	1	7.50																13	1	13	
19+84	95	W4-5							36X36	1	9.00										14	1	14	
I-75 SB ON RAMP																					14	1	14	
36+53	96	R5-10A	30X36	1	7.50										13	1	13							
37+51	97	R1-2							36 TRI	1	3.90				13	1	13							
COLUMBUS CIR																								
19+34	98	R1-1							36 OCT	1	7.46				13	1	13							
19+34	99	R1-2							36 TRI	1	3.90				13	1	13							
COLUMBUS DR																								
19+14	100	R1-2							36 TRI	1	3.90				13	1	13							
19+22	101	R560-5	12X24	1	5.00										13	1	13							
19+61	102	R1-1							36 OCT	1	7.46				13	1	13							
WARRIOR PATH																								
19+08	103	R560-5	18X24	1	5.00										13	1	13							
19+38	104	R560-5	18X24	1	5.00										13	1	13							
19+56	105	R1-2							36 TRI	1	3.90				13	1	13							
PAGE TOTAL	29			21	78.00					18	101.22		0	0		23	299		2	60		5	67	4
PROJECT TOTAL	105			78	301.02					57	368.56		10	127.50		78	1022		36	574		11	134	36

GPLN

GEORGIA
DEPARTMENT OF TRANSPORTATION

- NO SCALE -

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN

SUMMARY OF QUANTITIES

PROJECT IM000-0075-03(189)
GORDON COUNTY

DRAWING No. 06-011