LIGHTING QUANTITIES

ITEM DESCRIPTION	UNITS	ITEM TOTALS
CLASS A CONCRETE	CY	244
BAR REINF STEEL	LB	35,246
DIRECTIONAL BORE, 2 IN	LF	1,600
PULL BOX, PB-3	EA	9
PULL BOX, PB-4	EA	4
LIGHTING STD, 35 FT MH, POST TOP	EA	12
LIGHTING STD, 40 FT MH, POST TOP	EA	8
LUMINAIRE, TP 3, 150 W, HP SODIUM	EA	20
LUMINAIRE, TP A, 250W, HP SODIUM	EA	4
CABLE,TP RHH/RHW, AWG NO 10	LF	11,940
CABLE, TP RHH/RHW, AWG NO 8	LF	8,410
CABLE, TP RHH/RHW, AWG NO 6	LF	9,188
CABLE, TP RHH/RHW, AWG NO 4	LF	6,871
CABLE, TP RHH/RHW, AWG NO 2	LF	19,135
CABLE, TP RHH/RHW, AWG NO 1/0	LF	247
CABLE, TP RHH/RHW, AWG NO 2/0	LF	7,370
CABLE, TP RHH/RHW, AWG NO 4/0	LF	7,582
CONDUIT, RIGID, 1 IN	LF	300
CONDUIT, NONMETL, TP 2, 2 IN	LF	16,811
CONDUIT, NONMETL, TP 3, 2 IN	LF	1,940
ELECTRICAL JUNCTION BOX, CONC, GROUND MOUNTED, SIZE - 24" x 24" x 24"	EA	10
ELECTRICAL JUNCTION BOX, GALVANIZED, SIZE - 12" X 12" X 6" DEEP	EA	4
LIGHTING TOWER, STEEL, 100 FT MH, INCL LOWERING EQUIP	EA	2
LIGHTING TOWER, STEEL, 110 FT MH, INCL LOWERING EQUIP	EA	21
HIGH LEVEL LUMINAIRE, TP 5, 1000 W, HP SODIUM	EA	81
LOWERING DEVICE POWER SUPPLY UNIT	EA	1
ELECTRICAL POWER SERVICE ASSEMBLY, AERIAL SERVICE POINT	EA	3
ELECTRICAL POWER SERVICE ASSEMBLY, UNDERGROUND SERVICE POINT	EA	1

Heath & Lineback Engineers
INCORPORATED
2390 CANTON ROAD, BUILDING 200
MARIETTA, GEORGIA 30066-5393
(770)424-1668

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: CONSULTANT DESIGN

SUMMARY QUANTITIES

NHSTP-0075-03(203)
UNION GROVE ROAD INTERCHANGE

DRAWING No. 06-012