VOID

SUMMARY OF SIGNING QUANTITIES

				HIGHWAY SIGNS									POSTS										
				TYPE 3 SHEETING			TYPE 9 SHEETING															STRAIN POLE	GROUND MOUNTED BREAKAWAY SIGN
				TYPE 1 (0.080+.005 IN.)			TYPE 1 (0.080+.005 IN.)			TYPE 2 (0.100+.006 IN.)			TYPE 7 (2" 14GA)			TYPE 8 (2-1/2" 12GA)			TYPE 9 (2-1/4" 14GA)				
		INSTL.											LENGTH			LENGTH			LENGTH			TYPE III	SUPPORT
Drawing No.	SIDE	NO.	CODE	SIZE	QTY	SQ. FT.	SIZE	QTY	SQ. FT.	SIZE	QTY	SQ. FT.	LIN. FT.	QTY	LIN. FT	LIN. FT.	QTY	LIN. FT.	LIN. FT.	QTY	LIN. FT.	EACH	EACH
SHEET 26-29																							
S.R. 411																							
305+60	RT	133	R5-1 (30)				30 X 30	1	6.25				12.50	1	12.50								
306+00	C	134	R4-7 (24)	24 X 30	1	5.00							12.50	1	12.50								
310+25	LT	135	W 6-1 (36)				36 X 36	1	9.00				13.00	1	13.00								
CONNECTOR ROAD																							
70+52	LT	136	R1-1 (36)				36 OCT	1	9.00				13.00	1	13.00								
SHEET 26-30																							
CONNECTOR ROAD																							
75+34	RT	137	R1-1 (36)				36 OCT	1	9.00				13.00	1	13.00								
SHEET 26-31																							
MARKETPLACE BLVD																							
54+02	RT	138	W 14-1aL				36 X 8	1	2.00							14.25	1	14.25					
			W 14-1aR				36 X 8	1	2.00														
			R1-1 (36)				36 OCT	1	9.00														
			R1-3P				19 X 6	1	0.79														
54+16	LT	139	R1-2 (36)				36 OCT	1	9.00				13.00	1	13.00								
54+80	RT	140	R1-2 (36)				36 OCT	1	9.00				13.00	1	13.00								
54+98	LT	141	R1-2 (36)				36 X 36 X 36	1	3.90				13.00	1	13.00								
54+98	LT	142	W 14-1aL				36 X 8	1	2.00							14.25	1	14.25					
			W 14-1aR				36 X 8	1	2.00														
			R1-1 (36)				36 OCT	1	9.00														
57+55	RT	143	R3-7R (30)	30 X 30	1	6.25							12.50	1	12.50								
SHEET 26-34																							
CLINESMITH ROAD																							
165+37	RT	144	R1-2 (36)				36 X 36 X 36	1	3.90				13.00	1	13.00								
FROM SIGNALS									67.50			232.50											
TOTAL:						258.0			866.0			233.0			1662.0			142.0			124.0	4.0	

JORDAN JONES & GOULDING

REVISION DATES		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 6

SUMMARY QUANTITIES

S.R. 20 WIDENING

DRAWING No.
6-17