VOID

TRAFFIC CONTROL NH000-0017-01(022)	
TOTAL	1 LUMP SUM

GRADING COMPLETE NH000-0017-01(022)	
TOTAL	1 LUMP SUM

CONCRETE SLOPE PAVING, 4 IN	
TOTAL	700 SY

CONC. SIDEWALK, 4 IN.			
LOCATION		SIDE	SY
US 27	STA 13+38 TO 14+14	LT	60
US 27	STA 13+38 TO 14+41	RT	82
US 27	STA 22+33 TO 23+39	RT	103
US 27	STA 22+40 TO 23+39	LT	100
TOTAL			345

FIELD ENGINEERS OFFICE TP3	
TOTAL	1 EA

REINFORCED CONC. APPROACH SLAB GA. STD. 9017P	
TOTAL	920 SY

SUMMARY OF ROADWAY QUANTITIES

	STATIONS		PERMANENT PAVEMENT					TEMP. PAVEMENT									
			GRADED AGGREGATE BASE CRS, 14 INCH, INCL MAT'L	GRADED AGGREGATE BASE CRS, 6 INCH, INCL MAT'L	1½" RECYC ASPH CONC 12.5MM SUPERPAVE, GP2 ONLY, INLC BITUM. MAT'L & H. LIME	3" RECYC ASPH CONC 19MM SUPERPAVE, GP1 OR 2 ONLY, INLC BITUM. MAT'L & H. LIME	6" RECYC ASPH CONC 25MM SUPERPAVE, GP1 OR 2 ONLY, INLC BITUM. MAT'L & H. LIME	GRADED AGGREGATE BASE CRS, 10 INCH, INCL MAT'L	1½" RECYC ASPH CONC 12.5MM SUPERPAVE, GP2 ONLY, INLC BITUM. MAT'L & H. LIME	3" RECYC ASPH CONC 25MM SUPERPAVE, GP1 OR 2 ONLY, INLC BITUM. MAT'L & H. LIME	CLASS "B" CONCRETE BASE	CONCRETE MEDIAN, 6 IN	BITUMINOUS TACK COAT	CONCRETE CURB AND GUTTER 8 INCH X 30 INCH GDOT STD 9032B		PVMT. REINF. FABRIC STRIPS, TP2, 18 INCH WIDE	INDENTATION RUMBLE STRIPES - GROUND-IN-PLACE (SKIP)
	FROM	TO	TON	TON	TON	TON	TON	TON	TON	TON	CY	SY	GAL	TYPE 2 LF	TYPE 7 LF	LF	GLM
US 27	13+38.00	15+50.00	2,165		232	464	931	1,027	155	310	4	101	282	337	100	80	
	15+50.00	20+50.00	1,739	21	190	380	749	370	56	112	9	342	232		299		
	20+50.00	23+39.00	3,153	12	339	678	1,353	890	134	268	15	310	413	216	255	84	
RAMP A	29+35.00	37+43.00	2,508		253	506	1,063	64	10	19			314			26	0.26
RAMP B	40+15.00	43+50.00	917		93	185	395						116			22	0.10
	43+50.00	49+48.00	2,065		210	420	884						261				0.22
RAMP C	60+71.00	69+32.00	2,787	105	311	622	1,195	71	11	22			375			25	0.29
RAMP D	80+73.00	86+50.00	1,892		194	388	815						241				0.20
	86+50.00	90+00.00	968		98	196	417	56	8	17			123			29	0.12
SUB-TOTAL			18,194	138	1,920	3,839	7,802	2,478	374	748	28	753	2,357	553	654	266	1.19
AS DIRECTED BY ENGINEER			1,806	12	180	361	798	222	36	72	7	77	243	47	46	34	0.11
TOTAL			20,000	150	2,100	4,200	8,600	2,700	410	820	35	830	2,600	600	700	300	1.3

PLAIN CONCRETE DITCH PAVING, 4"						
LOCATION	SIDE	SLOPE	BOTTOM FEET	DEPTH FEET	LENGTH LIN FT	QUANITY SQ YD
32+50 TO 34+50, RAMP A	RT		2	1	200	273
43+37 TO 46+17, RAMP B	LT		2	1	280	362
AS DIRECTED BY ENGINEER						55
TOTAL						690

CONCRETE SPILLWAY			
LOCATION	SIDE	GA. STD 9013 TYPE 3	GA. STD 9017J TYPE 3
		EA	EA
US 27 20+15	LT		1
US 27 20+25	RT		1
RAMP A 36+45	LT	1	
TOTAL		1	2

SAWED JOINTS IN EXIST PAVEMENTS - PCC	
TOTAL	400 LF

REMOVE CONC APPROACH SLAB	
TOTAL	511 SY

REMOVE CONC DITCH PAVING		
LOCATION	SIDE	SY
RAMP A 32+50 TO 34+25	RT	238
RAMP B 44+05 TO 46+50	LT	332
TOTAL		570

AECOM

REVISION DATES
4/30/12

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES

SR1/US 27 @ SR166
INTERCHANGE RECONSTRUCTION
PI NO: 621990

DRAWING No. 6-01