TRAFFIC CONTROL
NH000-0017-01(022)

TOTAL 1 LUMP SUM

GRADING COMPLETE
NH000-0017-01(022)

TOTAL 1 LUMP SUM

CONCRETE SLOPE PAVING, 4 IN

TOTAL 700 SY

CONC. SIDEWALK, 4 IN.

LOCATION	SIDE	SY
US 27 STA 13+38 TO 14+14	LT	60
US 27 STA 13+38 TO 14+41	RT	82
US 27 STA 22+33 TO 23+39	RT	103
US 27 STA 22+40 TO 23+39	LT	100
TOTAL		345

FIELD ENGINEERS OFFICE TP3

TOTAL 1 EA

REINFORCED CONC. APPROACH SLAB
GA. STD. 9017P

TOTAL 920 SY

SUMMARY OF ROADWAY QUANTITIES

	STATIONS		PERMANENT PAVEMENT					TEMP. PAVEMENT									
			GRADED AGGREGATE BASE CRS, 14 INCH, INCL MAT'L	GRADED AGGREGATE BASE CRS, 6 INCH, INCL MAT'L	1½" RECYC ASPH CONC 12.5MM SUPERPAVE, GP2 ONLY, INLC BITUM. MAT'L & H.LIME	3" RECYC ASPH CONC 19MM SUPERPAVE, GP1 OR 2 ONLY, INLC BITUM. MAT'L & H.LIME	6" RECYC ASPH CONC 25MM SUPERPAVE, GP1 OR 2 ONLY, INLC BITUM. MAT'L & H.LIME	GRADED AGGREGATE BASE CRS, 10 INCH, INCL MAT'L	1½" RECYC ASPH CONC 12.5MM SUPERPAVE, GP2 ONLY, INLC BITUM. MAT'L & H.LIME	3" RECYC ASPH CONC 25MM SUPERPAVE, GP1 OR 2 ONLY, INLC BITUM. MAT'L & H.LIME	CLASS "B" CONCRETE BASE	CONCRETE MEDIAN, 6 IN	BITUMINOUS TACK COAT	CONCRETE CURB AND GUTTER 8 INCH X 30 INCH GDOT STD 9032B		PVMT. REINF. FABRIC STRIPS. TP2, 18 INCH WIDE	INDENTATION RUMBLE STRIPES - GROUND-IN-PLACE (SKIP)
	FROM	TO	TON	TON	TON	TON	TON	TON	TON	TON	CY	SY	GAL	LF TYPE 2	LF TYPE 7	LF	GLM
US 27	13+38.00	15+50.00	2,165		232	464	931	1,027	155	310	4	101	282	337	100	80	
	15+50.00	20+50.00	1,739	21	270	480	749	370	56	112	9	342	232		299		
	20+50.00	23+39.00	3,153	12	339	678	1,353	890	134	268	15	310	413	216	255	84	
RAMP A	29+35.00	37+43.00	2,508		253	506	1,063	64	10	19			314			26	0.26
RAMP B	40+15.00	43+50.00	1,660		120	238	502						116			22	0.10
	43+50.00	49+48.00	2,065		210	420	884						261				0.22
RAMP C	60+71.00	69+32.00	2,787	105	311	622	1,195	71	11	22			375			25	0.29
RAMP D	80+73.00	86+50.00	1,892		194	388	815						241				0.20
	86+50.00	90+00.00	1,611		121	242	509	56	8	17			123			29	0.12
SUB-TOTAL			19580	138	2,050	4,038	8,001	2,478	374	748	28	753	2,357	553	654	266	1.19
AS DIRECTED BY ENGINEER			1,920	12	250	462	799	222	36	72	7	77	243	47	46	34	0.11
TOTAL			21,500	150	2,300	4,500	8,800	2,700	410	820	35	830	2,600	600	700	300	1.3

PLAIN CONCRETE DITCH PAVING, 4"

LOCATION	SIDE	SLOPE	BOTTOM FEET	DEPTH FEET	LENGTH LIN FT	QUANITY SQ YD
32+50 TO 34+50, RAMP A	RT		2	1	200	273
43+37 TO 46+17, RAMP B	LT		2	1	280	362
AS DIRECTED BY ENGINEER						55
TOTAL						690

CONCRETE SPILLWAY

LOCATION	SIDE	GA. STD 9013 TYPE 3	GA. STD 9017J TYPE 3
		EA	EA
US 27 20+15	LT		1
US 27 20+25	RT		1
RAMP A 36+45	LT	1	
TOTAL		1	2

SAWED JOINTS IN EXIST PAVEMENTS - PCC

TOTAL 400 LF

REMOVE CONC APPROACH SLAB

TOTAL 511 SY

REMOVE CONC DITCH PAVING

LOCATION	SIDE	SY
RAMP A 32+50 TO 34+25	RT	238
RAMP B 44+05 TO 46+50	LT	332
TOTAL		570

AECOM

REVISION DATES
4/30/12
6/8/12
6/14/12

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES

SR1/US 27 @ SR166
INTERCHANGE RECONSTRUCTION
PI NO: 621990

DRAWING No. 6-01