STATION	SIDE	SIGN CODE	HIGHWAY SIGNS												
			TYPE I MATL. REFL SHEETING TYPE 3		TYPE I MATL. REFL SHEETING TYPE 9		TYPE 2 MATL. REFL SHEETING TYPE 3		TYPE 7			TYPE 8			BREAKAWAY SIGN SUPPORT
			SIZE	SF	SIZE	SF	SIZE	SF	LENGTH (FT)	QUANTITY	TOTAL LENGTH (FT)	LENGTH (FT)	QUANTITY	TOTAL LENGTH (FT)	EACH
SR225															
SEE PLANS	RT	D7-1 SPCL *2					42"x60"	17.5				13.5	2	27	2
SEE PLANS	RT	D7-1 SPCL *1					54"x72"	27.0				17.3	3	51.9	3
102+75	RT	R1-1			36"x36"	9.0			13	1	13				
112+30	LT	D7-1 SPCL *1					54"x72"	27.0				17.3	3	51.9	3
112+40	RT	W8-13			36"x36"	9.0			13	1	13				
113+35	RT	I-3	18"x36"	4.5					11.5	1	11.5				
115+74	LT	I-3	18"x36"	4.5					11.5	1	11.5				
116+62.50	LT	W8-13			36"x36"	9.0			13	1	13				
118+00	RT	R1-1			36"x36"	9.0			13	1	13				
118+57	RT	W3-1			36"x36"	9.0			13	1	13				
118+82.30	RT	W8-13			36"x36"	9.0			13	1	13				
119+50	LT	D7-1 SPCL *2					42"x60"	17.5				13.5	2	27	2
119+79	RT	I-3	18"x36"	4.5					11.5	1	11.5				
127+20	LT	I-3	18"x36"	4.5					11.5	1	11.5				
128+02.30	LT	W8-13			36"x36"	9.0			13	1	13				
141+83	RT	W3-1			36"x36"	9.0			13	1	13				
142+14	RT	R1-1			36"x36"	9.0			13	1	13				
TOTAL				18		81		89			163			157.8	10

NEW ECHOTA HISTORIC SITE SIGN	
CLASS A CONCRETE, SIGNS	5.0 CY

*SEE NOTE *4 ON SHEET 38-01.

6" PERFORATED PIPE UNDERDRAIN INCLUDING DRAINAGE AGGREGATE	
AS REQUIRED	2100 LIN. FT.

SPRING BOX (GA. STD. 9031-L)
AS DIRECTED BY ENGINEER: 1 EA

GRANULAR EMBANKMENT INCL MATL & HAUL	
AS REQUIRED	465 CY

PLANTING SCHEDULE

QTY	BOTANICAL NAME	COMMON NAME	PAY-ITEM	SIZE
0.4	RIPARIAN SEEDING		700-9400	AC
21	ACER RUBRUM "OCTOBER GLORY"	"OCTOBER GLORY" RED MAPLE	702-0030	3"-B&B
17	AMELANCHIER ARBOREA	SERVICEBERRY TREE	702-0049	8' HT-B&B
3	ILEX X "NELLIE R. STEVENS"	NELLIE STEVENS HOLLY	702-0474	10' HT-B&B
23	JUNIPERUS VIRGINIANA	EASTERN RED CEDAR	702-0520	8' HT-B&B
9	MAGNOLIA GRANDIFLORA "ALTA"	ALTA SOUTHERN MAGNOLIA	702-0630	8' HT-B&B
32	PINUS VIRGINIANA	VIRGINIA PINE	702-0790	1"-15 GAL
33	HYPERICUM CALYCINUM	ST. JOHNS WORT	702-0350	3 GAL
35	ILEX VOMITORIA "STOKE'S DWARF"	STOKE'S DWARF YAUPON HOLLY	702-0470	1 GAL
30	HEMEROCALIS "STELLA D'ORO"	STELLA D'ORO DAYLILY	702-0330	1 GAL
10	PLANTING SOIL MIX		708-1000	CY

CDM Smith
listen. think. deliver.

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY OF QUANTITIES

STATE ROUTE 225
PROJECT: BHF00-0151-01(006)
COUNTY: GORDON

DRAWING No. 6-002