DETAILED ESTIMATE

ITEM NO.	DESCRIPTION	UNIT	QTY
	ROADWAY		
150-1000	TRAFFIC CONTROL - STP-187-1(26)	Lump Sum	LS
208-0200	ROCK EMBANKMENT	CY	450
210-0100	GRADING COMPLETE - STP-187-1(26)	Lump Sum	LS
310-1101	GR AGGR BASE CRS, INCL MATL	TN	6850
318-3000	AGGR SURF CRS	TN	500
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	110
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	2680
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1310
402-4510	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	1650
413-1000	BITUM TACK COAT	GL	1060
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	3400
441-3999	CONCRETE V GUTTER	LF	150
441-5002	CONCRETE HEADER CURB, 6 IN, TP 2	LF	100
441-6222	CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	LF	400
446-1100	PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH	LF	1700
456-2015	INDENTATION RUMBLE STRIPS - GROUND-IN-PLACE (SKIP)	GLM	1
500-3900	CLASS B CONCRETE, INCL REINF STEEL	CY	1
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	128
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	LF	120
550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10	LF	540
550-3618	SAFETY END SECTION 18 IN, SIDE DRAIN, 6:1 SLOPE	EA	22
550-4218	FLARED END SECTION 18 IN, STORM DRAIN	EA	3
550-4224	FLARED END SECTION 24 IN, STORM DRAIN	EA	2
573-2006	UNDDR PIPE INCL DRAINAGE AGGR, 6 IN	LF	10000
600-0001	FLOWABLE FILL	CY	5
615-1000	JACK OR BORE PIPE - STEEL - 5/8 IN - 36 IN	LF	120
620-0100	TEMPORARY BARRIER, METHOD NO. 1	LF	630
634-1200	RIGHT OF WAY MARKER	EA	64
641-1200	GUARDRAIL, TP W	LF	1213
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	5
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	3
643-0155	FIELD FENCE SPCL DESIGN	LF	786
643-1132	CH LK FENCE, ZC COAT, 4 FT, 9 GA	LF	142
643-8010	GATE, CHAIN LINK ZC COAT - 14 FT	EA	1
668-2100	DROP INLET, GP 1	EA	1
	TEMPORARY EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	6
163-0240	MULCH	TN	18
163-0300	CONSTRUCTION EXIT	EA	3
163-0520	CONSTRUCT & REMOVE TEMPORARY PIPE SLOPE DRAIN	LF	400
163-0530	CONSTRUCT & REMOVE BALED STRAW EROSION CHECK	LF	170
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	2050
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	400
165-0070	MAINTENANCE OF BALED STRAW EROSION CHECK	LF	85
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	6
167-1000	WATER QUALITY MONITORING & SAMPLING	EA	2
167-1500	WATER QUALITY INSPECTIONS	MO	12
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	4100
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	800
603-2182	STN DUMPED RIP RAP, TP 3, 24 IN	SY	500
603-7000	PLASTIC FILTER FABRIC	SY	500
716-1000	EROSION CONTROL MATS, WATERWAYS	SY	2600
716-2000	EROSION CONTROL MATS, SLOPES	SY	29000
	PERMANENT EROSION CONTROL		
700-6910	PERMANENT GRASSING	AC	12
700-7000	AGRICULTURAL LIME	TN	36
700-7010	LIQUID LIME	GL	30
700-8000	FERTILIZER MIXED GRADE	TN	11
700-8100	FERTILIZER NITROGEN CONTENT	LB	600
	SIGNING & MARKING		
635-1000	BARRICADES	LF	50
636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING TP 9	SF	125
636-2070	GALV STEEL POSTS, TP 7	LF	221
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	10
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	62
653-2501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LM	2
653-2502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LM	3
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	800
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	56
653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	580
654-1001	RAISED PVMT MARKERS TP 1	EA	300
654-1003	RAISED PVMT MARKERS TP 3	EA	150
654-1010	RAISED PVMT MARKERS TP 10	EA	40

GENERAL NOTES

THE FOLLOWING UTILITY OWNERS HAVE FACILITIES WHICH CONFLICT WITH CONSTRUCTION ON THIS PROJECT. SEE SHEET NUMBERS INDICATED FOR DETAILS.

NAME OF UTILITY & CONTACT INFO	TYPE OF SERVICE	SHEET NUMBER
SAWNEE EMC Kevin Lassister 770-866-8119	POWER	SEE UTILITY PLANS
BELLSOUTH Mike Jobe 770-427-7103	TELEPHONE	SEE UTILITY PLANS
COMCAST Perry Kitchell 706-291-4942	CABLE TV	SEE UTILITY PLANS
ATLANTA GAS LIGHT Rob Hembree 770-584-3363	NATURAL GAS	SEE UTILITY PLANS
CHEROKEE COUNTY Bill Graham 770-479-6554	WATER & SANITARY SEWER	SEE UTILITY PLANS

A NOTICE OF INTENT (N.O.I.) WILL BE REQUIRED FOR THIS PROJECT

Georgia Department of Transportation

Dig Safely.

1-800-282-7411
770-623-4344

ALL DRIVEWAYS SHALL BE PAVED BACK TO TIE-IN POINT OR REQUIRED RIGHT-OF-WAY

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	STP-187-1(26)	009	195

REV. 05-03-06

09-01

5/11/2006 9:05:31 AM \\600T-DSN1\GDPLOT\GCF\d6_8830_mvlgt.cof drav C:\DGN\632845\08mlgs\632845detest.prf D6-Cartersville

5/11/2006 9:05:31 AM \\600T-DSN1\GDPLOT\GCF\d6_8830_mvlgt.cof drav C:\DGN\632845\08mlgs\632845detest.prf