FORM EF3

S U M M A R Y O F Q U A N T I T I E S

FIELD ENGINEERS OFFICE, TYPE 2	
TOTAL	1 EACH

CLEARING AND GRUBBING	
CLEARING AND GRUBBING (LUMP SUM)	23.99 Acres

"THE TOTAL ACREAGE SHOWN FOR CLEARING AND GRUBBING (LUMP SUM) IS FOR ESTIMATING PURPOSES ONLY.

IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE TOTAL ACREAGE SHOWN IN CASE HE ELECTS TO USE THE PLAN QUANTITY IN ESTABLISHING HIS BID PRICE. NO CLAIMS WILL BE CONSIDERED FOR EXTRA COMPENSATION IN CASE THE ACREAGE SHOWN IS LESS THAN THE ACTUAL ACREAGE, NOR WILL THE DEPARTMENT CLAIM ANY REDUCTION IN PAYMENT IN CASE THE ACREAGE SHOWN EXCEEDS THE ACTUAL ACREAGE."

REMOVE CULVERT - LUMP SUM

STATION	SIDE	DESCRIPTION
174+75	℄	7-5'x5' RUBBLE MASONARY CULVERT.
180+29	℄	24.5'-13'x6' CONC. CULVERT.
327+35	℄	21'-24.8'x7' CONC. & RUBBLE MASONARY CULVERT.

All Obstructions Within The Proposed Right-Of-Way Will Be Removed As Clearing And Grubbing Unless Covered As A Pay Item. The Listing May Not Be All Inclusive Of The Items Which May Be Encountered.

ITEMS TO BE REMOVED AS CLEARING AND GRUBBING (CONTINUED)

STATION	SIDE	DESCRIPTION
363+28	Rt.	4'-12" T.C. S.D. PIPE
364+12	Lt.	16'-10" T.C. S.D. PIPE
364+34	Rt.	28'-15" CONC. S.D. PIPE
364+84	Rt.	22'-8" S.D. PIPE
364+84	Lt.	20'-15" CONC. S.D. PIPE
365+12	Lt.	9'-18" T.C. S.D. PIPE
366+04	Lt.	42'-15" CONC. S.D. PIPE
367+25	Lt.	20'-15" CONC. S.D. PIPE
367+70	Lt.	20'-15" CONC. S.D. PIPE
369+10	Rt.	3' CONC. SIDEWALK

ITEMS TO BE REMOVED AS CLEARING AND GRUBBING

STATION	SIDE	DESCRIPTION
158+65	℄	88.5'-24" CONC. C.D. PIPE
159+90	Rt.	75'-18" T.C.S.D. PIPE
160+71	Lt.	20.3'-15" CONC. S.D. PIPE
163+63	Lt.	24.2'-15" CONC. S.D. PIPE
165+49	Rt.	JUNCTION BOX
165+49	Rt.	REMOVE 20 FT. OF C.M. STORM DRAIN PIPE
165+53	℄	25'-18" T.C.C.D. PIPE
165+47-166+04	Rt.	57'-15" C.M.S.D. PIPE
167+39	Lt.	42'-9" CONC. S.D. PIPE
171+39	Rt.	21'-18" CONC. S.D. PIPE
171+76	Rt.	42'-18" C.M.S.D. PIPE
173+35	Rt.	21'-15" C.M.S.D. PIPE
170+36	Lt.	28'-10" CONC. S.D. PIPE
174+50	Rt.	38'-20" T.C.S.D. PIPE
174+75	Rt.	RUBBLE MASONARY WALL
		10'-60" C.M.C.D. PIPE
174+86	Lt.	16'-18" C.M.S.D. PIPE
175+31	Lt.	19'-18" CONC. S.D. PIPE
187+28	Rt.	43'-24" C.M.S.D. PIPE
188+56	Lt.	20'-15" CONC. S.D. PIPE
189+86	Lt.	18'-12" CONC. S.D. PIPE
200+67	℄	49'-24" T.C.C.D. PIPE
218+22	℄	37'-24" T.C.C.D. PIPE
231+94	℄	37'-4.0'x3.5' RUBBLE MASONARY & 60"C.M. PIPE
234+46	Lt.	33'-18" CONC. S.D. PIPE
243+90	℄	37.5'-15"&18" T.C.C.D. PIPE
253+09	℄	46.0'-72" C.M.C.D. PIPE
264+28	℄	36.8'-60" C.M.C.D PIPE
266+43	Lt.	43'-15" C.M.S.D. PIPE
272+25	Rt.	25'-15" CONC. S.D. PIPE
273+50	Rt.	20'-15" CONC. S.D. PIPE
276+02	℄	36.3'-24" T.C.C.D. PIPE
280+25	Rt.	29'-15" CONC. S.D. PIPE
285+43	Rt.	20.5'-15" CONC. C.D. PIPE
289+29	℄	30.4'-15" T.C.C.D. PIPE
298+40	℄	30.7'-70" C.M.C.D. PIPE
298+50-299+38	Lt.	88'-15" C.M.S.D. PIPE
301+45	Rt.	20'-15" CONC. S.D. PIPE
305+98	℄	31.1'-24" T.C.C.D. PIPE
307+05	Lt.	26'-18" CONC. S.D. PIPE
307+77	Rt.	15'-15" CONC. S.D. PIPE
308+38	Lt.	14'-24" C.M.S.D. PIPE
315+72	℄	38.8'-15" T.C.C.D. PIPE
324+28	Rt.	77'-15" T.C. & CONC. S.R.C.D. PIPE
325+07	Rt.	9'-12" CONC. S.D. PIPE
325+63	Lt.	20'-15" CONC. S.D. PIPE
326+94	Lt.	30'-18" CONC. S.D. PIPE
334+92	℄	38'-18" T.C.C.D. PIPE
335+15	Lt.	22'-18" T.C.S.D. PIPE
336+20	Lt.	20'-12" CONC. S.D. PIPE
341+96	Rt.	20'-15" CONC. S.D. PIPE
342+27	Lt.	20'-15" CONC. S.D. PIPE
345+45	℄	43.5'-24" T.C.C.D. PIPE
349+37	Lt.	13'-1.0'x1.0' ROCK WALL
349+50	Lt.	33'-12" CONC. S.D. PIPE
349+59	Lt.	19'-1.0'x1.0' ROCK WALL
349+95	℄	25.5'-12" T.C. & C.M. PIPE
351+75	℄	24'-12" CONC. & T.C. PIPE
357+24	Lt.	5.0'-15" S.D. PIPE
357+71	Lt.	20'-15" CONC. S.D. PIPE
358+44	Rt.	20'-15 CONC. S.D. PIPE
358+82	Lt.	19'-12" CONC. S.D. PIPE
360+95	℄	27'-24" T.C.C.D. PIPE
361+00	℄	27'-36" CONC. & T.C. PIPE
361+06	℄	27'-15" T.C.C.D. PIPE
361+55	Rt.	15'-12" T.C.S.D. PIPE
362+50	Lt.	3x15 CONC. STEPS
362+62	Lt.	4.0'-15" CONC. S.D. PIPE

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	7318P 193 (9)	6	135