STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	TSAP 193(9)	9	135

Rev. 9-8-82
Rev. 1-24-83

S U M M A R Y O F Q U A N T I T I E S

(C O N T.)

*FENCING REQUIRED				
STATION TO STATION	SIDE	WOVEN WIRE W/ 1 STRAND BARBED WIRE	BARBED WIRE 4 STRAND	
		LIN. FT.	LIN. FT.	
179+00 - 182+00	RT.		352	
271+00 - 277+00	RT.	591		
TOTAL		591	352	

*TEMPORARY FENCING WITHIN TEMPORARY CONSTRUCTION EASEMENT.

UNDERDRAIN PIPE INCLUDING DRAINAGE AGGREGATE, 6" STD 9029B	
TOTAL	2000 LIN. FT.

TO BE USED AS DIRECTED BY THE ENGINEER. ALTERNATE MATERIALS WILL CONSIST OF THE FOLLOWING: ASBESTOS CEMENT, BITUMINOUS FIBER, CLAY, CONCRETE, CORRUGATED ALUMINUM, POLYETHYLENE (P.E.) PLASTIC CORRUGATED, AND CORRUGATED STEEL.

CONCRETE VALLEY GUTTER STD. 6050		
STATION	SIDE	SQ. YDS.
165+74	RT.	27.33
353+04	RT.	24.67
TOTAL		52.00

CONCRETE SIDEWALK, 4" STD. 9031J		
Station	Side	Sq. Yd.
357+30	Lt.	6.67
368+96	Rt.	8.33
Total		15.00

CLASS B CONCRETE		
Station	Side	Cu. Yds
158+10	Rt.	0.2
159+55	℄	0.2
263+70	℄	0.7
Total		*1.10

*Used To Plug End Of Existing Pipe.

SURFACING QUANTITIES - ALT. "A" & ALT. "B"															
ITEM		AGGREGATE SURFACE COURSE		ASPHALTIC CONCRETE LEVELING		4" ASPHALTIC CONCRETE BASE INCLUDING BITUMINOUS MATERIAL GROUP 1 OR 2		BITUMINOUS TACK COAT		GRADED AGGR. BASE		ASPH. CONCRETE "F", INCLUDING BITUMINOUS MATERIAL; BLEND 1		ASPH. CONCRETE "B", GP. 1 OR 2	
		TON		TON		TON		GALLON		TON		TON		TON	
		ALT. "A"	ALT. "B"	ALT. "A"	ALT. "B"	ALT. "A"	ALT. "B"	ALT. "A"	ALT. "B"	ALT. "A"	ALT. "B"	ALT. "A"	ALT. "B"	ALT. "A"	ALT. "B"
COUNTY ROADS				24	24		32	61	66	83		63	63	16	16
DETOURS		409	409									62	62		
DRIVEWAYS										719	719	76	76		
ROADWAY				986	986		2794	3164	3596	15681	6318	3868	3868	2798	2798
TOTAL		409	409	1010	1010		2826	3225	3662	16483	7037	4069	4069	2814	2814

CONCRETE DITCH PAVING, 4 IN.		
STATION	SIDE	SQ. YDS.
324+50 - 327+00	RT.	120
TOTAL		120

STONE PLAIN RIP RAP FOR DITCH CHECKS		
STONE PLAIN RIP RAP	2511	SQ. YDS.
LOOSE SOD	289	CU. YDS.

REMOVE FENCING	
DESCRIPTION	LIN. FT.
WOVEN WIRE W/1 STRAND BARBED WIRE	591
BARBED WIRE 4 STRAND	352

NOTE: AFTER COMPLETION OF CONSTRUCTION TEMPORARY FENCING TO BE REMOVED AND STOCKPILED. TO BE PICKED UP BY THE D.O.T. MAINTENANCE FORCES.

GUARDRAIL AND GUARDRAIL ANCHORAGES. STD. 4010, 4011, 4022-A AND 4052				
LOCATION	GUARDRAIL		GUARDRAIL ANCHORAGES	
	TYPE "W"		TYPE 1*	TYPE 9**
	LIN. FT.		EACH	EACH
179+61.25 - 181+63.00 LT.	201.75		1	1
179+37.00 - 181+38.75 RT.	201.75		1	1
231+04.75 - 233+06.00 LT.	201.75		1	1
230+81.00 - 232+82.75 RT.	201.75		1	1
252+99.25 - 255+01.00 LT.	201.75		1	1
252+68.00 - 254+57.25 RT.	189.25		1	1
263+38.25 - 265+40.00 LT.	201.75		1	1
263+15.00 - 265+16.75 RT.	201.75		1	1
297+42.00 - 298+96.00 LT.	114.00		1	1
299+16.00 - 299+55.25 LT.	39.25		1	1
297+27.00 - 299+28.75 RT.	201.75		1	1
326+21.50 - 326+88.00 LT.	26.50		1	1
327+00.00 - 328+51.75 LT.	151.75		1	1
360+12.00 - 362+13.75 LT.	201.75		1	1
359+84.75 - 361+49.00 RT.	164.25		1	1
TOTAL	2500.75		15	15

*SEE GA. STD. 4012-B
**SEE GA. STD. 4050

FORM EF3