SUMMARY OF QUANTITIES

TEMPORARY EROSION CONTROL

ITEM	QTY.	UNIT
TEMPORARY GRASSING	27	AC.
MULCH	770	TON
CONSTRUCTION EXIT	4	EA
CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	2	EA
CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	119	EA
CONSTRUCT AND REMOVE ROCK FILTER DAM	8	EA
CONSTRUCT AND REMOVE STONE FILTER RING	2	EA
MAINTENANCE OF INLET SEDIMENT TRAP	119	EA
MAINTENANCE OF ROCK FILTER DAM	8	EA
MAINTENANCE OF STONE FILTER RING	2	EA
MAINTENANCE OF TEMPORARY SILT FENCE, TP C	14500	LF
MAINTENANCE OF SILT CONTROL GATE, TP 3	2	EA.
MAINTENANCE OF CONSTRUCTION EXIT	4	EA.
WATER QUAL. MONITOR & SAMP.	2	EA.
WATER QUALITY INSPECT.	32	MO
TEMPORARY SILT FENCE TYPE C	29000	LF
CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER OR BALED STRAW CHECK DAM	1000	LF
CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP / SAND BAGS	53	EA
MAINTENANCE OF CHECK DAMS - ALL TYPES	530	LF
CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN	1000	LF
CONSTRUCT AND REMOVE STONE FILTER BERM (AS DIRECTED)	200	LF
MAINTENANCE OF STONE FILTER BERM	200	LF
MAINTENANCE OF SEDIMENT BARRIER - BALED STRAW	500	LF

PERMANENT EROSION CONTROL

ITEM	QTY.	UNIT
STN. DUMP RIP RAP TP. 1 24''	252	SY
PLASTIC FILTER FABRIC	252	SY
PERMANENT GRASSING	53	AC
AGRICULTURAL LIME	159	TN
FERTILIZER MIXED GRADE	101	TN
FERTILIZER NITROGEN CONTENT	5300	LB
EROSION CONTROL MATS SLOPES	90776	SY

ORANGE BARRIER FENCE

TOTAL	3000 LF

9/15/2007 GOUANT

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES
06/09/2014

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN
SUMMARY OF QUANTITIES
I-285 AT FLAT SHOALS RD
INTERCHANGE RECONSTRUCTION

DRAWING No. 6-008