

2025 RELEASE UNDER E.O. 14176

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CM-285-1(361)	3	234

REVISED: 02/18/05

## GENERAL NOTES

1. AT ALL EXPOSED CONDUIT LOCATIONS, FIBERGLASS OR RIGID STEEL CONDUIT SHALL BE USED AS SHOWN ON PLANS.

2. THE CONTRACTOR SHALL LOCATE ALL UTILITIES BEFORE DIGGING TO ELIMINATE ANY CONFLICTS WITH EXISTING UNDERGROUND UTILITIES. FOR HIGHWAY LIGHTING PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT AT (404) 656-5396.

3. THE CONTRACTOR SHALL REPLACE IN LIKE KIND AND SIZE, AT NO SEPARATE EXPENSE TO THE DEPARTMENT, ANY BARRIER WALL, FENCE, DITCH PAVING, CURBING, SIDEWALK, GUTTER, SLOPE PAVEMENT, SIGNS, GUARDRAIL, LANDSCAPING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 702), GRASSING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 700), UTILITY SERVICE LINES, STORM DRAIN PIPES, RUMBLE STRIPS, ROADWAY AND ANY RETAINING WALLS THAT ARE REMOVED, DAMAGED, OR DESTROYED DUE TO THE INSTALLATION OF CONDUIT, FIBER OPTIC CABLE, STRAIN POLES, OR PROPOSED DEVICES. THE CONTRACTOR WILL NOT BE REQUIRED TO MAINTAIN LANDSCAPING AS SPECIFIED IN SECTION 702.3.07 OF THE GEORGIA SPECIFICATIONS.

4. THE CONTRACTOR SHALL REMOVE THE PAVEMENT IN A MANNER TO PROVIDE A NEAT LINE. WHERE CONDUIT IS INSTALLED, THE CONTRACTOR SHALL INLAY TO MATCH EXISTING SURFACE AFTER CONDUIT IS INSTALLED. THE COST FOR PAVEMENT REMOVAL AND ASPHALT INLAY SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR CONDUIT DUCTBANK.

5. ANY REQUIRED EROSION CONTROL DEVICES WILL NOT BE MEASURED SEPARATELY AND SHALL BE INCLUDED IN THE COST OF THE OVERALL BID PRICE.

6. WITHIN 24 HOURS, THE CONTRACTOR SHALL REPAIR ALL EXISTING CONDUIT, CABLE, OR PIPE THAT IS DAMAGED BY THE INSTALLATION OF CONDUIT, FIBER OPTIC CABLE, STRAIN POLES, OR PROPOSED DEVICES. THERE IS NO SEPARATE PAYMENT FOR THIS WORK.

7. PAVEMENT MARKING AND RE-STRIPING ITEMS SHALL BE REPLACED IN LIKE KIND AND SIZE. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.

8. THE CONTRACTOR SHALL CONTACT THE DEPARTMENT'S FILE PLANS ROOM (404) 656-5408 FOR DRAINAGE PLANS AS NEEDED FOR THIS PROJECT.

9. CONDUIT UNDER RAMPS SHALL BE INSTALLED BY DIRECTIONAL BORING, UNLESS NOTED OTHERWISE ON THE PLANS.

10. THE ELECTRICAL POWER SERVICE ASSEMBLY POINTS SHOWN ON PLANS ARE FOR THE CONTRACTOR'S USE IN DETERMINING POWER ROUTING TO EACH DEVICE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL ELECTRICAL UTILITY COMPANIES TO PROVIDE POWER TO THE SERVICE RISER POINTS. ALL SERVICE RISER POINTS SHALL BE LOCATED WITHIN THE EXISTING RIGHT OF WAY, AT THE RIGHT OF WAY LINE. THE CONTRACTOR MAY OBTAIN ALTERNATE SERVICE POINT LOCATIONS THROUGH COORDINATION WITH THE UTILITY COMPANIES. ALTERNATE SERVICE POINT LOCATIONS SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW. THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A DETAILED POWER ROUTING PLAN FOR THE 2" TYPE 2 CONDUIT FROM THE ELECTRICAL POWER SERVICE ASSEMBLY POINT TO EACH DEVICE FOR REVIEW AND APPROVAL BY THE ENGINEER. PAYMENT FOR COPPER WIRE, ELECTRICAL JUNCTION BOXES, TRANSFORMERS, AND DIRECTIONAL BORES ASSOCIATED WITH THE INSTALLATION OF HORIZONTAL RUNS OF POWER CONDUIT SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR 2" TYPE 2 CONDUIT.

11. UNLESS SPECIFIED OTHERWISE ON THE PLANS, ALL PROPOSED STRAIN POLES SHALL BE INSTALLED A MINIMUM OF 6' BEHIND EXISTING OR REQUIRED GUARDRAIL WHERE SHOWN ON THE PLANS.

12. UNLESS SHOWN OTHERWISE ON THE PLANS, THE CONTRACTOR SHALL REMOVE ALL EXISTING SHOWCASE RADAR SYSTEMS, ELECTRONICS, AND THEIR ASSOCIATED CONTROLLER CABINETS AFTER ALL DEVICES INSTALLED BY THIS PROJECT ARE IN PLACE AND FULLY OPERATIONAL. ALL EXISTING RADAR SYSTEMS, CONTROLLER CABINETS, AND ELECTRONICS TO BE REMOVED SHALL BE DELIVERED TO BUILDING 5 LOCATED AT 935 EAST CONFEDERATE AVENUE, ATLANTA GEORGIA, 30316. THE CONTRACTOR SHALL CONTACT THE STATE SIGNAL ENGINEER AT (404) 624-7124 ONE WEEK PRIOR TO DELIVERY. THE POLE, ALL VERTICAL AND HORIZONTAL CONDUIT, AND CABLE FROM THE ELECTRICAL POWER SERVICE ASSEMBLY POINT SHALL REMAIN IN PLACE. THE CONTRACTOR SHALL TURN OFF MAIN SOURCE CIRCUIT BREAKER AND LOCK THE BREAKER CABINET WITH A PADLOCK. THE CONTRACTOR SHALL SUPPLY PADLOCKS AND KEYS. ALL PADLOCKS USED FOR LOCKING CIRCUIT BREAKERS SHALL BE KEYED THE SAME. ALL PAD PADLOCK KEYS SHALL BE GIVEN TO THE ENGINEER. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT. THE CONTRACTOR SHALL NOT DISTURB ANY OTHER ATMS DEVICES EXCEPT WHERE SPECIFIED IN THE PLANS. THE CONTRACTOR SHALL GRASS AND STABILIZE ANY DISTURBED AREA ON A DAILY BASIS.

13. EXISTING LOOP DETECTORS THAT ARE CUT, DAMAGED, OR DESTROYED SHALL NOT BE REPAIRED BY SPlicing THE LOOPS CABLES TOGETHER. ALL LOOP LINES THAT ARE CUT, DAMAGED, OR DESTROYED SHALL BE REPLACED ENTIRELY WITHIN TWO WEEKS AT NO SEPARATE EXPENSE TO THE DEPARTMENT. THE EXISTING LOOP DETECTORS ARE SHOWN ON THE PLANS FOR INFORMATION ONLY. THE CONTRACTOR SHALL CONTACT THE OFFICE OF INFORMATION SERVICES AT (770) 986-1356 ONE WEEK PRIOR TO DOING ANY WORK AT THESE LOCATIONS.

14. NO NOTICE OF INTENT IS REQUIRED FOR THIS PROJECT.

15. UNLESS SHOWN OTHERWISE ON THE PLANS, THE CONTRACTOR SHALL INSTALL DUCT BANK UNDER SHOULDER LANES THAT AT SOME LOCATIONS MAY BE AS NARROW AS SIX (6) FEET.

16. MINOR TREE TRIMMING AND REMOVAL MAY BE REQUIRED AS DIRECTED BY THE ENGINEER. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.

17. BEFORE WORKING AROUND EXISTING HUB BUILDINGS, THE CONTRACTOR SHALL CONTACT THE ITS MANAGER AT (404) 624-7811 48 HOURS IN ADVANCE TO LOCATE GDOT ITS INFRASTRUCTURE.

## UTILITIES CONTACT INFORMATION

CITY OF ATLANTA BUREAU OF WATER  
651 - 14TH STREET, N.W.  
ATLANTA, GEORGIA 30318  
MR. PETER TINUBU PHONE: 404-235-2029

ATLANTA GAS LIGHT COMPANY  
LOCATION 2010  
1219 CAROLINE STREET  
ATLANTA, GEORGIA 30307  
MR. EDDIE CONDER PHONE: 404 584-4569

BELLSOUTH TELECOMMUNICATIONS  
ROOM 118  
2310 PARKLAKE DRIVE  
ATLANTA, GEORGIA 30345  
MR. PHIL KEMPTON PHONE: 404 761-3212

GEORGIA POWER COMPANY  
BIN 20020  
241 RALPH MCGILL BLVD. NE  
ATLANTA, GEORGIA 30308-3374  
MR. TOM JACKSON PHONE: 404 506-2428

GEORGIA POWER UNDERGROUND  
829 JEFFERSON STREET, N. W.  
ATLANTA, GEORGIA 30318  
MR. KEN ROMANO PHONE: 404 506-4470

PLANTATION PIPE LINE COMPANY  
945 E. PACES FERRY ROAD, N. E.  
ATLANTA, GEORGIA 30326-1125  
MR. WAYNE HAMILTON PHONE: 404 364-5955

COLONIAL PIPELINE COMPANY  
3925 ANDERSON FARM ROAD  
AUSTELL, GA 30106-1001  
MR. MICKEY ELLIOTT PHONE: 404 794-3027

CITY OF ATLANTA DEPT OF PUBLIC WORKS  
360 ENGLEWOOD AVENUE, SE  
ATLANTA, GA 30316  
MR. LANCELOT CLARK, P.E. PHONE: 404-330-6249

THE CONTRACTOR SHALL ADHERE TO  
THE CALL BEFORE YOU DIG LAW  
BY CALLING THE UTILITIES  
PROTECTION CENTER

DIG SAFELY.  
1-800-282-7411  
770-623-4344

STATE OF GEORGIA  
DEPARTMENT OF TRANSPORTATION  
OFFICE OF TRAFFIC OPERATIONS

ATMS DESIGN PLAN SHEET  
I-285 NORTHWEST FROM I-20 TO I-75  
GENERAL NOTES

DRAWING No.

GN