

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CM-285-I(378)	4	110

GENERAL NOTES

1. THE CONTRACTOR SHALL LOCATE ALL UTILITIES BEFORE DIGGING TO ELIMINATE ANY CONFLICTS. TO OBTAIN HIGHWAY LIGHTING PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT AT (404) 656-5396. TO OBTAIN DRAINAGE PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT'S FILE PLANS ROOM AT (404) 656-5408. FOR GDOT ATMS FACILITIES THAT MAY BE IMPACTED, THE CONTRACTOR SHALL CONTACT THE GDOT PROJECT ENGINEER.

2. EXISTING INDUCTIVE LOOPS OR LEAD-IN WIRES THAT ARE CUT, DAMAGED, OR DESTROYED SHALL NOT BE REPAIRED BY SPLICING. ALL LOOPS OR LEAD-IN WIRES THAT ARE CUT, DAMAGED, OR DESTROYED SHALL BE REPLACED ENTIRELY WITHIN TWO WEEKS AT NO ADDITIONAL COST TO THE DEPARTMENT. ANY EXISTING INDUCTIVE LOOPS SHOWN ON THE PLANS ARE FOR INFORMATION ONLY. THE CONTRACTOR SHALL CONTACT THE OFFICE OF TRANSPORTATION DATA AT (770) 986-1435 ONE WEEK PRIOR TO DOING ANY WORK AT THESE LOCATIONS.

3. THE CONTRACTOR SHALL CONTACT THE GDOT PROJECT ENGINEER TO LOCATE GDOT ITS INFRASTRUCTURE AT LEAST 72 HOURS IN ADVANCE OF ALL WORK AROUND EXISTING HUB BUILDINGS.

4. THE CONTRACTOR SHALL REPAIR ANY EXISTING CONDUIT, PIPE, OR FIBER/CABLE THAT IS DAMAGED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE DEPARTMENT. ANY DAMAGED FIBER/CABLE SHALL BE REPAIRED WITHIN 24 HOURS OR LIQUIDATED DAMAGES SHALL INCUR. SEE GEORGIA SPECIFICATIONS SECTION 108.

5. THE CONTRACTOR SHALL REPLACE IN LIKE KIND AND SIZE, AT NO ADDITIONAL COST TO THE DEPARTMENT, ANY PAVEMENT MARKINGS, BARRIER WALL, FENCE, DITCH PAVING, CURBING, SIDEWALK, GUTTER, SLOPE PAVEMENT, SIGNS, GUARDRAIL, LANDSCAPING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 702), GRASSING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 700), UTILITY SERVICE LINES, STORM DRAIN PIPES, RUMBLE STRIPS, ROADWAY, AND ANY RETAINING WALLS THAT ARE DAMAGED OR DESTROYED BY ANY WORK PERFORMED AS PART OF THIS PROJECT. THE CONTRACTOR WILL NOT BE REQUIRED TO MAINTAIN LANDSCAPING AS SPECIFIED IN SECTION 702.3.07 OF THE GEORGIA SPECIFICATIONS.

6. THE CONTRACTOR SHALL REMOVE ALL EXISTING PAVEMENT MARKINGS THAT ARE IN CONFLICT BY A METHOD OTHER THAN GRINDING. REMOVAL METHOD MUST BE APPROVED BY PROJECT ENGINEER. PAYMENT SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR TRAFFIC CONTROL.

7. FIBERGLASS OR RIGID STEEL CONDUIT SHALL BE USED (AS SHOWN ON PLANS) AT ALL EXPOSED CONDUIT LOCATIONS.

8. THE CONTRACTOR SHALL REMOVE PAVEMENT BY SAW CUT TO PROVIDE A NEAT LINE. WHERE CONDUIT IS INSTALLED, THE CONTRACTOR SHALL INLAY TO MATCH EXISTING SURFACE TYPE AFTER CONDUIT IS INSTALLED. PAVEMENT REMOVAL AND PAVEMENT INLAY SHALL BE INCLUDED IN THE BID PRICE FOR CONDUIT DUCT BANK OR CONDUIT.

9. ANY REQUIRED EROSION CONTROL DEVICES WILL NOT BE MEASURED SEPARATELY AND SHALL BE INCLUDED IN THE COST OF THE OVERALL BID.

10. THE ELECTRIC POWER SERVICE ASSEMBLY POINTS SHOWN ON THE PLANS ARE FOR THE CONTRACTOR'S USE IN DETERMINING POWER ROUTING TO EACH DEVICE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL ELECTRICAL UTILITY COMPANIES TO PROVIDE POWER TO THE SERVICE RISER POINTS. PAYMENT FOR TYPE 2 CONDUIT FOR ELECTRIC POWER SERVICE INCLUDES ALL MATERIALS AND LABOR TO PROVIDE A CONNECTION BETWEEN THE SERVICE POINTS AND THE EQUIPMENT CABINETS.

11. ALL PROPOSED STRAIN POLES SHALL BE INSTALLED A MINIMUM OF 6 FEET BEHIND EXISTING OR PROPOSED GUARDRAIL WHERE SHOWN ON THE PLANS.

12. NO NOTICE OF INTENT IS REQUIRED FOR THIS PROJECT.

13. MINOR TREE TRIMMING AND REMOVAL MAY BE REQUIRED AS DIRECTED BY THE ENGINEER.

14. CABINETS, CAMERAS, CONTROLLERS AND OTHER ELECTRONIC DEVICES THAT ARE REMOVED AS PART OF THIS PROJECT SHALL BE RETURNED TO THE GDOT TRAFFIC SIGNALS AND ELECTRICAL FACILITIES BUILDING AT 935 EAST CONFEDERATE AVENUE, BUILDING 5, ATLANTA, GA 30316 AT NO ADDITIONAL COST TO THE DEPARTMENT. THE CONTRACTOR SHALL CALL THE TRAFFIC SIGNAL MAINTENANCE ENGINEER AT (404) 635-8900 AT LEAST 72 HOURS IN ADVANCE TO ARRANGE DELIVERY OF THESE COMPONENTS.

15. CONDUIT UNDER RAMPS SHALL BE INSTALLED BY DIRECTIONAL BORING, UNLESS NOTED OTHERWISE ON THE PLANS.

16. THE REMOVAL OF ALL GUARDRAIL AND GUARDRAIL ANCHORS SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.

UTILITIES CONTACT INFORMATION

MR. JON CLARK JR.  
 GEORGIA POWER COMPANY  
 BIN 39066  
 829 JEFFERSON ST.  
 ATLANTA, GA 30318  
 PHONE:

MR DAN EVERITT  
 GEORGIA POWER COMPANY  
 BIN 20033  
 241 RALPH MCGILL BLVD., N.E.  
 ATLANTA GA 30308-3374  
 PHONE: (404) 506-2889

CONTRACTOR SHALL CALL BEFORE ANY WORK IN RUNWAY TUNNEL.

FAA  
 MR. KIM ANDERSON  
 404-209-4080 EXT. 255



THE CONTRACTOR SHALL ADHERE TO THE "CALL BEFORE YOU DIG" LAW BY CALLING THE UNDERGROUND PROTECTION CENTER AT 1-800-282-7411 OR 770-623-4344 BEFORE BEGINNING CONSTRUCTION.



G R E S H A M  
 S M I T H A N D  
 P A R T N E R S



OFFICE OF TRAFFIC SAFETY & DESIGN

DATE	REVISIONS

GEORGIA DEPARTMENT OF TRANSPORTATION  
 1-285 SOUTH ATMS  
 GENERAL NOTES  
 PROJECT - PI713372  
 COUNTY - FULTON & CLAYTON  
 DATE - \_\_/\_\_/\_\_ SHEET 4-01

\$FILE\$  
 \$DATE\$