

GENERAL NOTES

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CM-575-I(34)	4	113

1. THE CONTRACTOR SHALL LOCATE ALL UTILITIES BEFORE DIGGING TO ELIMINATE ANY CONFLICTS. TO OBTAIN HIGHWAY LIGHTING PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT AT (404) 656-5396. TO OBTAIN DRAINAGE PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT'S FILE PLANS ROOM AT (404) 656-5408. FOR GDOT ATMS FACILITIES THAT MAY BE IMPACTED, THE CONTRACTOR SHALL CONTACT THE GDOT ITS MANAGER AT (404) 624-7811.

2. EXISTING INDUCTIVE LOOPS OR LEAD-IN WIRES THAT ARE CUT, DAMAGED, OR DESTROYED SHALL NOT BE REPAIRED BY SPLICING. ALL LOOPS OR LEAD-IN WIRES THAT ARE CUT, DAMAGED, OR DESTROYED SHALL BE REPLACED ENTIRELY WITHIN TWO WEEKS AT NO ADDITIONAL COST TO THE DEPARTMENT. ANY EXISTING INDUCTIVE LOOPS SHOWN ON THE PLANS ARE FOR INFORMATION ONLY. THE CONTRACTOR SHALL CONTACT THE OFFICE OF TRANSPORTATION DATA AT (770) 986-1435 ONE WEEK PRIOR TO DOING ANY WORK AT THESE LOCATIONS.

3. THE CONTRACTOR SHALL CONTACT THE ITS MANAGER AT (404) 624-7811 TO LOCATE GDOT ITS INFRASTRUCTURE AT LEAST 48 HOURS IN ADVANCE OF ALL WORK AROUND EXISTING HUB BUILDINGS.

4. WITHIN 24 HOURS, THE CONTRACTOR SHALL REPAIR ANY EXISTING CONDUIT, CABLE, OR PIPE THAT IS DAMAGED BY ANY WORK PERFORMED AS PART OF THIS PROJECT AT NO ADDITIONAL COST TO THE DEPARTMENT.

5. THE CONTRACTOR SHALL REPLACE IN LIKE KIND AND SIZE, AT NO ADDITIONAL COST TO THE DEPARTMENT, ANY PAVEMENT MARKINGS, BARRIER WALL, FENCE, DITCH PAVING, CURBING, SIDEWALK, GUTTER, SLOPE PAVEMENT, SIGNS, GUARDRAIL, LANDSCAPING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 702), GRASSING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 700), UTILITY SERVICE LINES, STORM DRAIN PIPES, RUMBLE STRIPS, ROADWAY, AND ANY RETAINING WALLS THAT ARE DAMAGED OR DESTROYED BY ANY WORK PERFORMED AS PART OF THIS PROJECT. THE CONTRACTOR WILL NOT BE REQUIRED TO MAINTAIN LANDSCAPING AS SPECIFIED IN SECTION 702.3.07 OF THE GEORGIA SPECIFICATIONS.

6. THE CONTRACTOR SHALL REMOVE ALL EXISTING PAVEMENT MARKINGS THAT ARE IN CONFLICT BY A METHOD OTHER THAN GRINDING. REMOVAL METHOD MUST BE APPROVED BY PROJECT ENGINEER. PAYMENT SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR TRAFFIC CONTROL.

7. FIBERGLASS OR RIGID STEEL CONDUIT SHALL BE USED (AS SHOWN ON PLANS) AT ALL EXPOSED CONDUIT LOCATIONS.

8. THE CONTRACTOR SHALL REMOVE PAVEMENT BY SAW CUT TO PROVIDE A NEAT LINE. WHERE CONDUIT IS INSTALLED, THE CONTRACTOR SHALL INLAY TO MATCH EXISTING SURFACE TYPE AFTER CONDUIT IS INSTALLED. PAVEMENT REMOVAL AND PAVEMENT INLAY SHALL BE INCLUDED IN THE BID PRICE FOR CONDUIT DUCT BANK OR CONDUIT.

9. ANY REQUIRED EROSION CONTROL DEVICES WILL NOT BE MEASURED SEPARATELY AND SHALL BE INCLUDED IN THE COST OF THE OVERALL BID.

10. THE ELECTRIC POWER SERVICE ASSEMBLY POINTS SHOWN ON THE PLANS ARE FOR THE CONTRACTOR'S USE IN DETERMINING POWER ROUTING TO EACH DEVICE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL ELECTRICAL UTILITY COMPANIES TO PROVIDE POWER TO THE SERVICE RISER POINTS. PAYMENT FOR TYPE 2 CONDUIT FOR ELECTRIC POWER SERVICE INCLUDES ALL MATERIALS AND LABOR TO PROVIDE A CONNECTION BETWEEN THE SERVICE POINTS AND THE EQUIPMENT CABINETS.

11. ALL PROPOSED STRAIN POLES SHALL BE INSTALLED A MINIMUM OF 6 FEET BEHIND EXISTING OR PROPOSED GUARDRAIL WHERE SHOWN ON THE PLANS.

12. NO NOTICE OF INTENT IS REQUIRED FOR THIS PROJECT.

13. MINOR TREE TRIMMING AND REMOVAL LOCATIONS ARE SHOWN ON THE PLANS. HOWEVER, ADDITIONAL LOCATIONS MAY BE REQUIRED AS DIRECTED BY THE ENGINEER. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.

14. CABINETS, CAMERAS, CONTROLLERS AND OTHER ELECTRONIC DEVICES THAT ARE REMOVED AS PART OF THIS PROJECT SHALL BE RETURNED TO THE GDOT TRAFFIC SIGNALS AND ELECTRICAL FACILITIES BUILDING AT 935 EAST CONFEDERATE AVENUE, BUILDING 5, ATLANTA, GA 30316 AT NO ADDITIONAL COST TO THE DEPARTMENT. THE CONTRACTOR SHALL CALL THE TRAFFIC SIGNAL MAINTENANCE ENGINEER AT (404) 635-8900 AT LEAST 72 HOURS IN ADVANCE TO ARRANGE DELIVERY OF THESE COMPONENTS.

15. CONDUIT UNDER RAMPS SHALL BE INSTALLED BY DIRECTIONAL BORING, UNLESS NOTED OTHERWISE ON THE PLANS.

16. THE REMOVAL OF ALL GUARDRAIL AND GUARDRAIL ANCHORS SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.

UTILITY CONTACTS:

GEORGIA POWER COMPANY  
MR. JOHN CLARK  
BIN 20020  
241 RALPH MCGILL BLVD. NE  
ATLANTA, GA. 30308-3374  
404-506-6597

MARIETTA POWER  
MR. KERRY RICHARDSON  
675 NORTH MARIETTA PKWY  
MARIETTA, GA. 30060-1528  
770-794-5124

COBB EMC  
MR. TERRY BRYANT  
P.O. BOX 369  
MARIETTA, GA. 30061  
770-429-2200

COBB COUNTY WATER SYSTEM  
MR. RUSSELL COOKE  
660 SOUTH COBB DRIVE  
MARIETTA, GA. 30060-3113  
770-419-6330

MARIETTA WATER AUTHORITY  
MR. KEN JANNEY  
1660 BARNES MILL ROAD  
MARIETTA, GA. 30062  
770-426-8936 EXT. -241

COLONIAL PIPELINE COMPANY  
MR. MICKEY ELLIOTT  
3925 ANDERSON FARM ROAD  
AUSTELL, GA. 30106-1001  
770-819-3557

GEORGIA POWER COMPANY  
MR. DAN EVERIT  
TRANSMISSION AND RESOURCE SERVICES  
241 RALPH MCGILL BLVD  
BIN 20025  
ATLANTA, GA. 30308-3374  
404-506-2889

ATLANTA GAS LIGHT RESOURCES  
MR. BRIAN LEAVELL  
10 PEACHTREE PLACE  
ATLANTA, GA. 30309  
404-584-4702

COMCAST, INC.  
MR. JOEY BROWN  
2925 COURTYARDS DRIVE  
NORCROSS, GA. 30071  
770-559-2215

LEVEL 3 COMMUNICATIONS  
MR. MIKE PALLESCHI  
SR. OUTSIDE PLANT MANGER  
180 PEACHTREE ST.  
ATLANTA, GA. 30303  
404-253-1925

AT&T COMMUNICATIONS  
MR. GENE GEREN  
360 GEES MILL BUSINESS PARKWAY  
CONYERS, GA. 30013  
770-602-2121

BELLSOUTH  
MR. JOE DeGROM  
400 CHASTAIN CENTER BLVD.  
SUITE 121  
KENNESAW, GA. 30144  
404-626-9643



**Dig | Safely.**  
1-800-282-7411  
770-623-4344

THE CONTRACTOR SHALL ADHERE TO THE "CALL BEFORE YOU DIG" LAW BY CALLING THE UNDERGROUND PROTECTION CENTER AT 1-800-282-7411 OR 770-623-4344 BEFORE BEGINNING CONSTRUCTION.



G R E S H A M  
S M I T H   A N D  
P A R T N E R S



OFFICE OF TRAFFIC SAFETY & DESIGN

DATE	REVISIONS

I-575 ATMS  
GENERAL NOTES  
PROJECT - CM-575-I(34)  
COUNTY - COBB/CHEROKEE  
DATE - 05/02/06    SHEET 4-1