

GENERAL NOTES

1. THE CONTRACTOR SHALL LOCATE ALL UTILITIES BEFORE DIGGING TO ELIMINATE ANY CONFLICTS. TO OBTAIN HIGHWAY LIGHTING PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT AT (404) 631-1642. TO OBTAIN DRAINAGE PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT'S FILE PLANS ROOM AT (404) 631-1531. FOR GDOT ATMS FACILITIES THAT MAY BE IMPACTED, THE CONTRACTOR SHALL CONTACT THE GDOT ITS MANAGER AT (404) 694-6613.

2. EXISTING INDUCTIVE LOOPS OR LEAD-IN WIRES THAT ARE CUT, DAMAGED, OR DESTROYED SHALL NOT BE REPAIRED BY SPlicing. ALL LOOPS OR LEAD-IN WIRES THAT ARE CUT, DAMAGED, OR DESTROYED SHALL BE REPLACED ENTIRELY WITHIN TWO WEEKS AT NO ADDITIONAL COST TO THE DEPARTMENT. ANY EXISTING INDUCTIVE LOOPS SHOWN ON THE PLANS ARE FOR INFORMATION ONLY. THE CONTRACTOR SHALL CONTACT THE OFFICE OF TRANSPORTATION DATA AT (770) 986-1448 ONE WEEK PRIOR TO DOING ANY WORK AT THESE LOCATIONS.

3. THE CONTRACTOR SHALL CONTACT THE ITS MANAGER AT (404) 624-7811 TO LOCATE GDOT ITS INFRASTRUCTURE AT LEAST 48 HOURS IN ADVANCE OF ALL WORK AROUND EXISTING HUB BUILDINGS.

4. WITHIN 24 HOURS, THE CONTRACTOR SHALL REPAIR ANY EXISTING CONDUIT, CABLE, OR PIPE, THAT IS DAMAGED BY ANY WORK PERFORMED AS PART OF THIS PROJECT AT NO ADDITIONAL COST TO THE DEPARTMENT.

5. THE CONTRACTOR SHALL REPLACE IN LIKE KIND AND SIZE, AT NO ADDITIONAL COST TO THE DEPARTMENT, ANY PAVEMENT MARKINGS, BARRIER WALL, FENCE, DITCH PAVING, CURBING, SIDEWALK, GUTTER, SLOPE PAVEMENT, SIGNS, GUARDRAIL, LANDSCAPING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 702), GRASSING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 700), UTILITY SERVICE LINES, STORM DRAIN PIPES, RUMBLE STRIPS, ROADWAY, AND ANY RETAINING WALLS THAT ARE DAMAGED OR DESTROYED BY ANY WORK PERFORMED AS PART OF THIS PROJECT. THE CONTRACTOR WILL NOT BE REQUIRED TO MAINTAIN LANDSCAPING AS SPECIFIED IN SECTION 702.3.07 OF THE GEORGIA SPECIFICATIONS.

6. THE CONTRACTOR SHALL REMOVE ALL EXISTING PAVEMENT MARKINGS THAT ARE IN CONFLICT BY A METHOD OTHER THAN GRINDING. REMOVAL METHOD MUST BE APPROVED BY PROJECT ENGINEER. PAYMENT SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR TRAFFIC CONTROL.

7. FIBERGLASS OR RIGID STEEL CONDUIT SHALL BE USED (AS SHOWN ON PLANS) AT ALL EXPOSED CONDUIT LOCATIONS.

8. THE CONTRACTOR SHALL REMOVE PAVEMENT BY SAW CUT TO PROVIDE A NEAT LINE. WHERE CONDUIT IS INSTALLED, THE CONTRACTOR SHALL INLAY TO MATCH EXISTING SURFACE TYPE AFTER CONDUIT IS INSTALLED. PAVEMENT REMOVAL AND PAVEMENT INLAY SHALL BE INCLUDED IN THE BID PRICE FOR CONDUIT DUCT BANK OR CONDUIT.

9. THE ELECTRIC POWER SERVICE ASSEMBLY POINTS SHOWN ON PLANS ARE FOR THE CONTRACTOR'S USE IN DETERMINING POWER ROUTING TO EACH DEVICE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL ELECTRICAL UTILITY COMPANIES TO PROVIDE POWER TO THE SERVICE RISER POINTS. PAYMENT FOR TYPE 2 CONDUIT FOR ELECTRIC POWER SERVICE INCLUDES ALL MATERIALS AND LABOR TO PROVIDE A CONNECTION BETWEEN THE SERVICE POINTS AND THE EQUIPMENT CABINETS.

10. UNLESS OTHERWISE NOTED ON THE PLANS, ALL PROPOSED STRAIN POLES SHALL BE INSTALLED A MINIMUM OF 38 FEET FROM THE EDGE OF THE NEAREST TRAVEL LANE OR 6 FEET BEHIND EXISTING OR PROPOSED GUARDRAIL.

11. A NOTICE OF INTENT IS REQUIRED FOR THIS PROJECT

12. CABINETS, CAMERAS, CONTROLLERS AND OTHER ELECTRONIC DEVICES THAT ARE REMOVED AS PART OF THIS PROJECT SHALL BE RETURNED TO THE GDOT TRAFFIC SIGNALS AND ELECTRICAL FACILITIES BUILDING AT 935 EAST CONFEDERATE AVENUE, BUILDING 5, ATLANTA, GA 30316 AT NO ADDITIONAL COST TO THE DEPARTMENT. THE CONTRACTOR SHALL CALL THE TRAFFIC SIGNAL MAINTENANCE ENGINEER AT (404) 635-8900 AT LEAST 72 HOURS IN ADVANCE TO ARRANGE DELIVERY OF THESE COMPONENTS.

13. CONDUIT UNDER RAMPS SHALL BE INSTALLED BY DIRECTIONAL BORING, UNLESS NOTED OTHERWISE ON THE PLANS.

14. THE REMOVAL OF ALL GUARDRAIL AND GUARDRAIL ANCHORS SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.

15. CONDUIT DUCT BANK SHALL BE INSTALLED AT LEAST 15 FEET FROM MAINLINE EDGE OF PAVEMENT UNLESS OTHERWISE NOTED ON PLANS.

16. UPON COMPLETION OF CONSTRUCTION ACTIVITIES THE CONTRACTOR WILL PROVIDE AS-BUILT PLANS THAT INCLUDE THE LOCATION OF INSTALLED FIBER, ELECTRICAL COMMUNICATION BOXES (ECBS), PULL BOXES, CONDUIT LOCATION AND DEPTH, AND POWER SERVICE FEEDS.

<u>UTILITY OWNER</u>	<u>SERVICE</u>	<u>CONTACT</u>
GREYSTONE POWER	ELECTRICAL	770-370-2032
GEORGIA POWER COMPANY	ELECTRICAL	678-432-2069
ATLANTA GAS LIGHT COMPANY	GAS	404-584-3238
CLAYTON COUNTY WATER & SEWER	WATER	770-961-2130
AT&T GEORGIA	TELEPHONE	770-493-3753
DEKALB COUNTY WATER & SEWER	WATER	770-621-7200
COMCAST COMMUNICATIONS	CABLE TV	706-232-0997
COLONIAL PIPELINE	GAS	678-762-2200
PLANTATION PIPELINE COMPANY	GAS	770-751-4000
SOUTHERN NATURAL GAS	GAS	205-320-0919
HENRY COUNTY		770-288-6000



**Know what's below
Call before you dig**

**GEORGIA
DEPARTMENT
OF
TRANSPORTATION**

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF TRAFFIC OPERATIONS
I-675 ATMS
GENERAL NOTES

DRAWING No.
4-01