SUMMARY OF QUANTITIES
ROADWAY

LOCATION (SEE SOUND BARRIER PLAN FOR SPECIFIC LOCATION OF EACH ITEM)	SOUND BARRIER			PAVING							EROSION CONTROL										
	SOUND BARRIER TYPE 'B' H = 0'-10'	SOUND BARRIER TYPE 'B' H = 10'-20'	SOUND BARRIER TYPE 'B' H = 20'-30'	6" CLASS B CONC BASE OR PVMT WIDENING	12.5 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	GR AGGR BASE CRS. INCL MATL	BITUM TACK COAT	CONC SLOPE PAVING, 4 IN	CONCRETE "V" GUTTER	CLASS B CONCRETE, RETAINING WALL	TEMP SILT FENCE TYPE "A"	TEMP SILT FENCE TYPE "C"	CONSTRUCT & REMOVE BALED STRAW EROSION CHECK	CONSTRUCT & REMOVE TEMP PIPE SLOPE DRAIN	PLAIN CONC. DITCH PAVING 4 IN.	EROSION CONTROL MATS, SLOPES	MAINT TEMP SILT FENCE TYPE "A"	MAINT TEMP SILT FENCE TYPE "C"	MAINT OF BALED STRAW EROSION CHECK	MAINT OF CHECKDAM/ DITCH CHECKS	MAINT OF SEDIMENT TRAPS
	SQ. FT.	SQ. FT.	SQ. FT.	C.Y.	TON	TON	GAL	SQ. YD.	LIN.FT.	C.Y.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	SQ. YD.	SQ. YD.	LIN.FT.	LIN.FT.	LIN.FT.	EACH	EACH
SOUND BARRIER 1	470	18858	5431	58	-	229	-	12	21	104	500	2360	370	-	807	575	250	1180	185	55	2
SOUND BARRIER 2	5856	31023	1277	44	-	171	-	12	21	191	485	960	1080	-	2182	448	243	480	540	70	15
SOUND BARRIER 3	742	10724	-	47	6	175	1	-	-	147	-	-	500	-	670	275	-	-	250	17	5
SOUND BARRIER 4	-	62450	2166	170	-	732	-	383	690	117	2295	1525	4505	-	880	1458	1148	763	2253	104	17
SOUND BARRIER 5	-	6040	6473	-	-	-	-	-	-	-	-	-	340	-	-	-	-	-	170	-	-
SOUND BARRIER 6	-	13902	3504	-	-	-	-	-	-	-	-	-	1890	-	446	-	-	-	945	12	1
SOUND BARRIER 7	6440	42070	-	84	-	327	-	127	190	178	2970	1300	2265	-	754	815	1485	650	1133	95	18
SOUND BARRIER 8	-	28270	7878	60	-	320	-	592	1065	-	1230	-	1780	-	328	1365	615	-	890	31	6
SOUND BARRIER 9	-	35375	6628	63	21	315	3	59	107	101	2410	-	1950	-	1248	1918	1205	-	975	76	10
SOUND BARRIER 10	-	17654	2977	40	44	165	7	-	-	-	2300	-	70	-	807	69	1150	-	35	23	3
AS DIRECTED BY ENGINEER														1000							
TOTAL	13508	266366	36334	566	71	2434	11	1185	2094	838	12190	6145	14750	1000	8122	6923	6096	3073	7376	483	77

LOCATION (SEE SOUND BARRIER PLAN FOR SPECIFIC LOCATION OF EACH ITEM)	ROADWAY ITEMS								
	GUARDRAIL ANCHORAGE TYPE 1	GUARDRAIL ANCHORAGE TYPE 12	GUARDRAIL TYPE "T"	GUARDRAIL TYPE "W"	CONC SIDE BARRIER, TYPE 2-S	CONC SIDE BARRIER, TYPE 7-RS	CONC SIDE BARRIER, TYPE 7-TS	PRECAST CONCRETE MEDIAN BARRIER, METHOD 3	GUARDRAIL IMPACT ATTENUATORS - TYPE T-3-S-30
	EACH	EACH	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	EACH
SOUND BARRIER 1	1	-	77	-	558	450	45		
SOUND BARRIER 2	1	1	42	60	500	100	30		
SOUND BARRIER 3	1	-	42	-	348	-	30		
SOUND BARRIER 4	2	3	160	592	1485	500	120		
SOUND BARRIER 5	1	1	560	-	-	-	-		
SOUND BARRIER 6	-	-	-	-	-	-	-		
SOUND BARRIER 7	-	2	84	106	650	-	60		
SOUND BARRIER 8	-	1	-	1077	-	-	-		
SOUND BARRIER 9	1	-	84	100	878	1150	60		
SOUND BARRIER 10	1	1	21	-	-	235	30		
AS DIRECTED BY ENGINEER								8000	4
TOTAL	8	9	1070	1935	4419	2435	375		

GRADING (COMPLETE)	TOTAL
NH-7141-00(100)	LUMP SUM

LIQUID LIME	GAL
	28 GAL

FERTILIZER MIXED GRADE	TONS
	2 TONS

FERTILIZER NITROGEN CONTENT	LBS
	862 LBS

PERMANENT GRASSING	TOTAL
	11 AC

TEMPORARY GRASSING	AC
	6 AC

TEMPORARY MULCH	TONS
	50 TONS

AGRICULTURAL LIME	TONS
	52 TONS

TRAFFIC CONTROL	TOTAL
NH-7141-00(100)	LUMP SUM

FIELD ENGINEER'S OFFICE, TYPE 3	TOTAL
NH-7141-00(100)	1 EACH

WATER QUALITY MONITORING AND SAMPLING	TOTAL
NH-7141-00(100)	2 EA

GREENHORNE & O'MARA
2211 NEWMARKET PARKWAY
SUITE 104
MARIETTA, GEORGIA 30067
PHONE: (770) 988-9555
G&O PROJECT NO. 0094/WO 010

DATE	REVISIONS	DATE	REVISIONS
12-08-03	COMBINED WATER MONITORING AND SAMPLING		

GEORGIA
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
PROJECT: NH-7141-00(100)
COUNTY: DEKALB
DATE: 06-21-02
DRAWING 4-01