STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NH -7141-00(100)	106	334

SUMMARY OF QUANTITIES-OVERHEAD WIRE SPAN

STATION	SPAN WIDTH	LANE	SIGNS-TYPE 1 MAT'L (0.08)				SIGNS-TYPE 2 MAT'L (0.10)				GALV. SEIMANS-MARTIN GUY STRAND MESSENGER CABLE (lin. ft.)-(including 3-bolt 1" galv. clamps with 5/8" galv. bolts.)	STRAIN POLES (CONCRETE OR STEEL) EACH			TREATED TIMBER POLES, CLASS 2, 30 FT.
			CODE	SIZE	QUAN.	SQ. FT.	CODE	SIZE	QUAN.	SQ. FT.	3/8" DIA. CABLE LIN. FT.	TYPE I	TYPE II	TYPE III	EACH
I-20															
RAMP FS2-4															
16+40	70'	RAMP		EXISTING	1	EXST					140'			1	
16+40		RAMP	R3-5L	EXISTING	1	EXST									
16+40		RAMP	R3-5T	EXISTING	1	EXST									
16+40		RAMP					M SPEC # 14	EXISTING	1	EXST					
16+40		RAMP	R3-5R	EXISTING	1	EXST									
TOTALS					3				1		140			1	

NOTE: 1. FOR CABLE AND STRAIN POLES REFER TO SECTION 639 GA.STD. SPECIFICATIONS.
2. LANE NUMBERS ASSIGNED FROM CENTER LINE OUT IN DIRECTION OF SURVEY.
3. WHEN TWO OR MORE SIGN FACING THE SAME DIRECTION ARE TO BE MOUNTED OVER THE SAME LANE(S), THE SIGNS SHALL BE CENTERED OVER THE LANE(S) WITH A 2" SPACE BETWEEN SIGNS.
4. FOR ERECTION DETAILS SEE "TYPICAL ERECTION DETAILS-OVERHEAD LANE MARKERS".

SM-20

PCBDTB

12/8/2003 7:52:39 AM \\ATLFS1\JOBS\CIVIL\CADNET\OCF\BATCHset dt-plotter jt\Trans\0094\W0010\plot\SIGN\71410sum01.prf