DATE$$$	TIME$$$	PRF	DGN	STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
$USER$		$$PENTABLE$$		GA	CSSTP-0006-00(901), CSSTP-0006-00(900)	1048	1415

STP00-0186-01(011)

TIE INTO EXISTING
12" WATER LINE

20" STEEL CASING
12" DIP WATER LINE

6" DIP
WATER LINE

20" STEEL CASING
12" DIP WATER LINE

SEWER LINE ON
WSA EASEMENT
TO REMAIN

NEW RIM ELEV 1143.4
INV IN 1135.3
INV OUT 1128.1
OUTSIDE DROP DETAIL FIG 9

REPLACE EXISTING 8"
SEWER WITH 8" DIP

20" STEEL CASING
12" DIP WATER LINE

TIE INTO EXISTING
12" WATER LINE

MATCH LINE
SEE DRAWING 44+009

SEWER LINE ON
WSA EASEMENT

REPLACE EXISTING 8"
SEWER LINE WITH
8" DIP PIPE

NEW RIM ELEV 1137.8
INV IN 1118.7
INV OUT 1118.5

NEW MANHOLE
RIM ELEV. - 1096.0
INV IN 1084.9
INV OUT 1084.7

ABANDON SEWER
MAIN

ABANDON WATER
MAIN

MATCH LINE
SEE DRAWING 44+011

ADJUST MANHOLE
TO GRADE

16" STEEL CASING
8" DIP WATER LINE

8" DIP
WATER LINE

NEW MANHOLE
RIM ELEV. - 1105.0
INV IN 1096.6
INV OUT 1096.4

ABANDON SEWER
MAIN

ABANDON SEWER
MAIN

NEW MANHOLE
RIM ELEV. - 1110
INV1 IN 1095.8
INV2 IN 1089.6
INV OUT 1089.3
OUTSIDE DROP DETAIL FIG 9

INSTALL NEW 10" DIP
SEWER LINE

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR
& MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
REQ'D R/W & LIMIT OF ACCESS

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

DOUGLASVILLE-DOUGLAS COUNTY
WATER AND SEWER AUTHORITY

SCALE IN FEET
0 40 80 160

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY
WATER AND SEWER RELOCATION PLANS

SR 92 RELOCATION AND WIDENING

DRAWING No.
44-010

1/5/2009 GPLN