

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CM-056-1 (56)	3	157

REVISED AND REDRAWN: 1-07-05

GENERAL NOTES

- AT ALL EXPOSED CONDUIT LOCATIONS, FIBERGLASS OR GALVANIZED RIGID METAL CONDUIT SHALL BE USED AS SHOWN ON PLANS.
- THE CONTRACTOR SHALL LOCATE ALL UTILITIES BEFORE DIGGING TO ELIMINATE ANY CONFLICTS WITH EXISTING UNDERGROUND UTILITIES. THE CONTRACTOR SHALL USE THE ONE-CALL CENTER TELEPHONE NUMBER (800) 282-7411 FOR THE MARKING OF UNDERGROUND UTILITIES. FOR HIGHWAY LIGHTING PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT AT (404) 656-5396.
- THE CONTRACTOR SHALL REPLACE IN LIKE KIND AND SIZE, AT NO SEPARATE EXPENSE TO THE DEPARTMENT, ANY BARRIER WALL, SOUND BARRIER, FENCE, DITCH PAVING, CURBING, SIDEWALK, GUTTER, SLOPE PAVEMENT, SIGNS, GUARDRAIL, LANDSCAPING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 702), GRASSING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 700), UTILITY SERVICE LINES, STORM DRAIN PIPES, AND ANY RETAINING WALLS THAT ARE REMOVED, DAMAGED, OR DESTROYED DUE TO THE INSTALLATION OF CONDUIT, FIBER OPTIC CABLE, STRAIN POLES, OR PROPOSED DEVICES. THE CONTRACTOR WILL NOT BE REQUIRED TO MAINTAIN LANDSCAPING AS SPECIFIED IN SECTION 702.3.07 OF THE GEORGIA SPECIFICATIONS.
- THE CONTRACTOR SHALL CONTACT THE PROJECT ENGINEER TO COORDINATE ALL CONSTRUCTION ACTIVITIES WITH THE GEORGIA STATE TOLL AUTHORITY. CONTACT TOLL PLAZA MANAGER (404) 266-3040.
- THE CONTRACTOR SHALL REMOVE THE ASPHALT IN A MANNER TO PROVIDE A NEAT LINE. WHERE CONDUIT IS INSTALLED, THE CONTRACTOR SHALL INLAY TO MATCH EXISTING SURFACE AFTER CONDUIT IS INSTALLED. THE COST FOR ASPHALT REMOVAL AND ASPHALT INLAY SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR CONDUIT DUCT BANK.
- ANY REQUIRED EROSION CONTROL DEVICES WILL NOT BE MEASURED SEPARATELY AND SHALL BE INCLUDED IN THE COST OF THE OVERALL BID PRICE.
- WITHIN 24 HOURS, THE CONTRACTOR SHALL REPAIR ALL EXISTING CONDUIT, CABLE, OR PIPE THAT IS DAMAGED BY THE INSTALLATION OF CONDUIT, FIBER OPTIC CABLE, STRAIN POLES, OR PROPOSED DEVICES. THERE IS NO SEPARATE PAYMENT FOR THIS WORK.
- PAVEMENT MARKING AND RE-STRIPING ITEMS SHALL BE REPLACED IN LIKE KIND AND SIZE. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.
- THE CONTRACTOR SHALL CONTACT THE DEPARTMENT'S FILE PLANS ROOM (404) 656-5408 FOR DRAINAGE PLANS AS NEEDED FOR THIS PROJECT.
- CONDUIT UNDER RAMPS SHALL BE INSTALLED BY DIRECTIONAL BORING, UNLESS NOTED OTHERWISE ON THE PLANS.
- THE ELECTRICAL POWER SERVICE ASSEMBLY POINTS SHOWN ON PLANS ARE FOR THE CONTRACTOR'S USE IN DETERMINING POWER ROUTING TO EACH DEVICE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL ELECTRICAL UTILITY COMPANIES TO PROVIDE POWER TO THE SERVICE RISER POINTS. ALL SERVICE RISER POINTS SHALL BE LOCATED AT THE MOST PRACTICAL LOCATION AT THE BACK OF THE EXISTING RIGHT OF WAY AND OUTSIDE OF CLEAR ZONE. THE CONTRACTOR MAY OBTAIN ALTERNATE SERVICE POINT LOCATIONS THROUGH COORDINATION WITH THE UTILITY COMPANIES. ALTERNATE SERVICE POINT LOCATIONS SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW. THE CLEAR ZONE SHALL NOT BE VIOLATED WHEN THE CONTRACTOR RELOCATES THE EXISTING SERVICE RISER. THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A DETAILED POWER ROUTING PLAN FOR THE NONMETAL 2" TYPE 2 CONDUIT FROM THE ELECTRICAL POWER SERVICE ASSEMBLY POINT TO EACH DEVICE FOR REVIEW AND APPROVAL BY THE ENGINEER. PAYMENT FOR COPPER WIRE, PULLBOXES, TRANSFORMERS, AND DIRECTIONAL BORES ASSOCIATED WITH THE INSTALLATION OF HORIZONTAL RUNS OF POWER CONDUIT SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR NONMETAL 2" TYPE 2 CONDUIT.
- UNLESS SPECIFIED OTHERWISE ON THE PLANS, ALL PROPOSED STRAIN POLES AND SERVICE POLES SHALL BE INSTALLED A MINIMUM OF 6' BEHIND EXISTING OR REQUIRED GUARDRAIL WHERE SHOWN ON THE PLANS.
- UNLESS SHOWN OTHERWISE ON THE PLANS, THE CONTRACTOR SHALL REMOVE ALL EXISTING SHOWCASE RADAR SYSTEMS, ELECTRONICS, AND THEIR ASSOCIATED CONTROLLER CABINETS AFTER ALL DEVICES INSTALLED BY THIS PROJECT ARE IN PLACE AND FULLY OPERATIONAL. ALL EXISTING RADAR SYSTEMS, CONTROLLER CABINETS, AND ELECTRONICS TO BE REMOVED SHALL BE DELIVERED TO BUILDING 5 LOCATED AT 935 EAST CONFEDERATE AVENUE, ATLANTA GEORGIA, 30316. THE CONTRACTOR SHALL CONTACT THE STATE SIGNAL ENGINEER AT (404) 624 - 7124 ONE WEEK PRIOR TO DELIVERY. THE POLE, ALL VERTICAL AND HORIZONTAL CONDUIT, AND CABLE FROM THE ELECTRICAL POWER SERVICE ASSEMBLY POINT SHALL REMAIN IN PLACE. THE CONTRACTOR SHALL TURN OFF MAIN SOURCE CIRCUIT BREAKER AND LOCK THE BREAKER CABINET WITH A PADLOCK. THE CONTRACTOR SHALL SUPPLY PADLOCKS AND KEYS. ALL PADLOCKS USED FOR LOCKING CIRCUIT BREAKERS SHALL BE KEYED THE SAME. ALL PADLOCK KEYS SHALL BE GIVEN TO THE ENGINEER. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT. THE CONTRACTOR SHALL NOT DISTURB ANY OTHER ATMS DEVICES EXCEPT WHERE SPECIFIED IN THE PLAN.

14. EXISTING LOOP DETECTORS THAT ARE CUT, DAMAGED, OR DESTROYED SHALL NOT BE REPAIRED BY SPlicing THE LOOP CABLES TOGETHER. ALL LOOP LINES THAT ARE CUT, DAMAGED, OR DESTROYED SHALL BE REPLACED ENTIRELY WITHIN TWO WEEKS AT NO SEPARATE EXPENSE TO THE DEPARTMENT. THE EXISTING LOOP DETECTORS ARE SHOWN ON THE PLANS FOR INFORMATION ONLY. THE CONTRACTOR SHALL CONTACT THE OFFICE OF INFORMATION SERVICES AT (770) 986-1356 ONE WEEK PRIOR TO DOING ANY WORK AT THESE LOCATIONS.

15. NO NOTICE OF INTENT IS REQUIRED FOR THIS PROJECT.

16. UNLESS SHOWN OTHERWISE ON THE PLANS, THE CONTRACTOR SHALL INSTALL DUCT BANK UNDER SHOULDER LANES.

17. MINOR TREE TRIMMING AND REMOVAL MAY BE REQUIRED AS DIRECTED BY THE ENGINEER. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.

18. BEFORE WORKING AROUND EXISTING HUB BUILDINGS OR ITS DEVICES, THE CONTRACTOR SHALL CONTACT THE ITS MANAGER AT (404) 624-7811 72 HOURS IN ADVANCE OF ANY EXCAVATION IN THE AREA TO ALLOW GDOT STAFF TO LOCATE GDOT ITS INFRASTRUCTURE.

UTILITIES CONTACT INFORMATION

MCI TELECOMMUNICATIONS
2250 Lakeside Blvd.
Richardson, Texas 75082
R & U Investigations 2855-642 Phone: 404 525-4870

GEORGIA POWER Underground
829 Jefferson Street, N. W.
Atlanta, Georgia 30318
Mr. Ken Romano Phone: 404 506-4470

ATLANTA GAS LIGHT COMPANY
Location 2010
1219 Caroline Street
Atlanta, Georgia 30307
Mr. Brian Leavell Phone: 404 584-4569

AT&T Broadband.
2925 Courtyards Drive
Norcross, Georgia 30071
Ms. Cathy Campbell Phone: 770 559-2166

BELLSOUTH TELECOMMUNICATIONS
Room 118
2310 Parklake Drive
Atlanta, Georgia 30345
Mr. Phil Kempton Phone: 404 761-3212

SAWNEE E.M.C.
543 Atlanta Road
P.O. Box 266
Cumming, Georgia 30130
Mr. Kevin Laseter Phone: 770 887-2363

UNITED WATER SERVICES ATLANTA
651 - 14th Street, N. W.
Atlanta, Georgia 30318
Mr. Peter Tinubu Phone: 404 235-2029

PLANTATION PIPE LINE COMPANY
945 E. Paces Ferry Road, N. E.
Atlanta, Georgia 30326-1125
Mr. Wayne Hamilton Phone: 404 364-5955

GEORGIA POWER COMPANY
Bin 20020
241 Ralph McGill Blvd. NE
Atlanta, Georgia 30308-3374
Mr. Tom Jackson Phone: 404 506-2428

COLONIAL PIPELINE COMPANY
3925 Anderson Farm Road
Austell, GA 30106-1001*
Mr. Mickey Elliott Phone: 404 794-3027

DESIGNED BY	NAME	DATE	FIRST DRAWN	NAME	DATE	GEORGIA DEPARTMENT OF TRANSPORTATION	SUBMITTED BY	DATE
CHECKED BY			LAST DRAWN					
SUPERVISED BY								

ATMS DESIGN
S.R. - 400 FROM I-85 TO I-285
GENERAL NOTES SHEET

ACCOUNT NO.

DRAWING NO.