COST ESTIMATE

ITEM CODE NO.	DESCRIPTION	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - CM-056-1 (56)	LS	LUMP
153-1300	FIELD ENGINEERS OFFICE TYP3	EA	1
610-1075	REM GUARDRAIL ANCH, ALL TYPES	EA	3
615-1200	DIRECTIONAL BORE - 9 IN	LF	3620
631-2343	LED PIXEL CMS, NON-WALK IN, 3 X 15, 18 IN, TYPE B	EA	1
631-8000	TESTING (631-8000)	LS	LUMP
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4
638-1003	STR SUPPORT FOR OVERHEAD SIGN, TP III, STA. 190+25 SR 400 NB	LS	LUMP
639-2002	STEEL WIRE STRAND CABLE, 3/8 IN	LF	335
639-4004	STRAIN POLE, TP IV	EA	34
641-1200	GUARDRAIL, TP W	LF	2650
641-5001	GUARDRAIL ANCHORAGE TP 1	EA	19
641-5012	GUARDRAIL ANCHORAGE TP 12	EA	18
647-2150	PULL BOX, PB-5	EA	43
682-6120	CONDUIT, RIGID, 2 IN	LF	604
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	24375
682-6224	CONDUIT, NONMETL, TP 2, 4 IN	LF	40
682-6231	CONDUIT, NONMETL, TP 3, 1 1/4 IN	LF	25630
682-6233	CONDUIT, NONMETL, TP 3, 2 IN	LF	13710
682-6520	CONDUIT, FIBERGLASS, 2 IN	LF	14590
682-7040	MULTI-CELL CONDUIT SYS, 4 WAY, SCH 40 PVC	LF	120
682-7042	MULTI-CELL CONDUIT SYS, 4 WAY, RIGID METAL	LF	40
682-7043	MULTI-CELL CONDUIT SYS, 4 WAY, FIBERGLASS	LF	8460
682-7060	CONDUIT DUCT BANK, TYPE 1	LF	22094
682-7061	CONDUIT DUCT BANK, TYPE 2	LF	30408
682-9028	ELECTRICAL COMMUNICATION BOX, TP 5	EA	95
682-9029	ELECTRICAL COMMUNICATION BOX, REHABILITATION	EA	2
935-1113	OUTSIDE PLANT FIBER OPTIC CABLE, LOOSE TUBE, SINGLE MODE, 24 FIBER	LF	14968
935-1114	OUTSIDE PLANT FIBER OPTIC CABLE, LOOSE TUBE, SINGLE MODE, 36 FIBER	LF	25314
935-1118	OUTSIDE PLANT FIBER OPTIC CABLE, LOOSE TUBE, SINGLE MODE, 144 FIBER	LF	84960
935-1511	OUTSIDE PLANT FIBER OPTIC CABLE, DROP, SINGLE MODE, 6 FIBER	LF	7040
935-1512	OUTSIDE PLANT FIBER OPTIC CABLE, DROP, SINGLE MODE, 12 FIBER	LF	220
935-1513	OUTSIDE PLANT FIBER OPTIC CABLE, DROP, SINGLE MODE, 24 FIBER	LF	6820
935-3101	FIBER OPTIC CLOSURE, UNDERGROUND, 6 FIBER	EA	36
935-3103	FIBER OPTIC CLOSURE, UNDERGROUND, 24 FIBER	EA	37
935-3104	FIBER OPTIC CLOSURE, UNDERGROUND, 36 FIBER	EA	3
935-3105	FIBER OPTIC CLOSURE, UNDERGROUND, 48 FIBER	EA	3
935-3108	FIBER OPTIC CLOSURE, UNDERGROUND, 144 FIBER	EA	10
935-3403	FIBER OPTIC CLOSURE, FDC (RACK MOUNTED), 24 FIBER	EA	39
935-3404	FIBER OPTIC CLOSURE, FDC (RACK MOUNTED), 36 FIBER	EA	1
935-3408	FIBER OPTIC CLOSURE, FDC (RACK MOUNTED), 144 FIBER	EA	4
935-4010	FIBER OPTIC SPLICE, FUSION	EA	3004
935-8000	TESTING (935-8000)	LS	LUMP
936-1001	CCTV SYSTEM, TYPE B	EA	19
936-8000	TESTING (936-8000)	LS	LUMP
936-8500	TRAINING (936-8500)	LS	LUMP
937-1000	VIDEO CAMERA SENSOR ASSEMBLY	EA	46
937-3010	VDS SYSTEM PROCESSOR, TYPE A	EA	36
937-8000	TESTING (937-8000)	LS	LUMP
937-8500	TRAINING (937-8500)	LS	LUMP
939-1190	VIDEO ENCODER, TYPE A	EA	19
939-1195	VIDEO DECODER, TYPE A	EA	16
939-2025	SERIAL DATA TERMINAL SERVER, TYPE B	EA	3
939-2221	GBIC ENTERPRISE ROUTING SWITCH MODULE, 8 PORT	EA	3
939-2232	GBIC, TYPE B	EA	16
939-2300	FIELD SWITCH, TYPE A	EA	30
939-2301	FIELD SWITCH, TYPE B	EA	12
939-3020	EQUIPMENT FRAME	EA	1
939-4040	TYPE D CABINET	EA	39
939-5010	ELECTICAL POWER SERVICE ASSEMBLY, AERIAL SERVICE POINT	EA	25
939-8000	TESTING (939-8000)	LS	LUMP
939-8500	TRAINING (939-8500)	LS	LUMP

REVISED: 05-22-02
REVISED AND REDRAWN: 1-07-05
REVISED: 02/18/05
REVISED: 04/29/05
REVISED: 10/26/05
REVISED: 5/30/06

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CM-056-1 (56)	8	157

DESIGNED
CHECKED
SUPERVISED BY
NAME
DATE
FINAL
LAST
DRAWN
NAME
DATE

GEORGIA DEPARTMENT OF TRANSPORTATION

SUBMITTED BY
DATE

ATMS DESIGN
S.R. 400 FROM I-85 TO I-285
DETAILED ESTIMATE

ACCOUNT NO.
DRAWING NO.

...\CAD Files\detailedestimat 5/30/2006 2:31:20 PM