STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	NH000-0056-01(061)	82	115

UTILITY LINECODES

	EXISTING	TO BE REMOVED	PROPOSED	TYPE OF UTILITY
OVERHEAD	E	E	E	ELECTRIC
	E-T	E-T	E-T	ELECTRIC/TELECOMMUNICATIONS
	E-TV	E-TV	E-TV	ELECTRIC/CABLE TV
	E-TC	E-TC	E-TC	ELECTRIC/TRAFFIC CONTROL
	E-T-TV	E-T-TV	E-T-TV	ELECTRIC/TELECOMMUNICATIONS/CABLE TV
	E-T-TV-TC	E-T-TV-TC	E-T-TV-TC	ELECTRIC/TELECOMMUNICATIONS/CABLE TV/TRAFFIC CONTROL
	E-TV-TC	E-TV-TC	E-TV-TC	ELECTRIC/CABLE TV/TRAFFIC CONTROL
	E-T-TC	E-T-TC	T-TV-TC	ELECTRIC/TELECOMMUNICATIONS/TRAFFIC CONTROL
	GW	GW	GW	GUY WIRE
	T	T	T	TELECOMMUNICATIONS
	T-TC	T-TC	T-TC	TELECOMMUNICATIONS/TRAFFIC CONTROL
	T-TV-TC	T-TV-TC	T-TV-TC	TELECOMMUNICATIONS/CABLE TV/TRAFFIC CONTROL
	T-TV	T-TV	T-TV	TELECOMUNICATIONS/CABLE TV
	TV	TV	TV	CABLE TV
	TV-TC	TV-TC	TV-TC	CABLE TV/TRAFFIC CONTROL
	TC	TC	TC	TRAFFIC CONTROL
UNDERGROUND	E	E	E	ELECTRIC (QL-D)
	E(C)	E(C)		ELECTRIC (QL-C)
	E(B)	E(B)		ELECTRIC (QL-B)
	T	T	T	TELECOMMUNICATIONS (QL-D)
	T(C)	T(C)		TELECOMMUNICATIONS (QL-C)
	T(B)	T(B)		TELECOMMUNICATIONS (QL-B)
	TV	TV	TV	CABLE TV (QL-D)
	TV(C)	TV(C)		CABLE TV (QL-C)
	TV(B)	TV(B)		CABLE TV (QL-B)
	W	W	W	WATER (QL-D)
	W(C)	W(C)		WATER (QL-C)
	W(B)	W(B)		WATER (QL-B)
	**W	**W	**W	WATER FOR LABELED PIPE SIZES (QL-D)
	**W(C)	**W(C)		WATER FOR LABELED PIPE SIZES (QL-C)
	**W(B)	**W(B)		WATER FOR LABELED PIPE SIZES (QL-B)
	NW	NW	NW	NON-POTABLE WATER (QL-D)
	NW(C)	NW(C)		NON-POTABLE WATER (QL-C)
	NW(B)	NW(B)		NON-POTABLE WATER (QL-B)
	**NW	**NW	**NW	NON-POTABLE WATER FOR LABELED PIPE SIZES (QL-D)
	**NW(C)	**NW(C)		NON-POTABLE WATER FOR LABELED PIPE SIZES (QL-C)
	**NW(B)	**NW(B)		NON-POTABLE WATER FOR LABELED PIPE SIZES (QL-B)
	STM	STM	STM	STEAM (QL-D)
	STM(C)	STM(C)		STEAM (QL-C)
	STM(B)	STM(B)		STEAM (QL-B)
	**STM	**STM	**STM	STEAM FOR LABELED PIPE SIZES (QL-D)
	**STM(C)	**STM(C)		STEAM FOR LABELED PIPE SIZES (QL-C)
	**STM(B)	**STM(B)		STEAM FOR LABELED PIPE SIZES (QL-B)
	SS	SS	SS	SANITARY SEWER WITH FLOW DIRECTION (QL-D)
	SS(C)	SS(C)		SANITARY SEWER WITH FLOW DIRECTION (QL-C)
	SS(B)	SS(B)		SANITARY SEWER WITH FLOW DIRECTION (QL-B)
	Σ**SS	Σ**SS	Σ**SS	SANITARY SEWER WITH FLOW DIRECTION FOR LABELED PIPE SIZES (QL-D)
	Σ**SS(C)	Σ**SS(C)		SANITARY SEWER WITH FLOW DIRECTION FOR LABELED PIPE SIZES (QL-C)
	Σ**SS(B)	Σ**SS(B)		SANITARY SEWER WITH FLOW DIRECTION FOR LABELED PIPE SIZES (QL-B)
	SFM	SFM	SFM	SANITARY SEWER FORCE MAIN WITH FLOW DIRECTION (QL-D)
	SFM(C)	SFM(C)		SANITARY SEWER FORCE MAIN WITH FLOW DIRECTION (QL-C)
	SFM(B)	SFM(B)		SANITARY SEWER FORCE MAIN WITH FLOW DIRECTION (QL-B)
	G	G	G	GAS (QL-D)
	G(C)	G(C)		GAS (QL-C)
	G(B)	G(B)		GAS (QL-B)
	**G	**G	**G	GAS FOR LABELED PIPE SIZES (QL-D)
	**G(C)	**G(C)		GAS FOR LABELED PIPE SIZES (QL-C)
	**G(B)	**G(B)		GAS FOR LABELED PIPE SIZES (QL-B)
	P	P	P	PETROLEUM (QL-D)
	P(C)	P(C)		PETROLEUM (QL-C)
	P(B)	P(B)		PETROLEUM (QL-B)
	**P	**P	**P	PETROLEUM FOR LABELED PIPE SIZES (QL-D)
	**P(C)	**P(C)		PETROLEUM FOR LABELED PIPE SIZES (QL-C)
	**P(B)	**P(B)		PETROLEUM FOR LABELED PIPE SIZES (QL-B)
	TC	FOR PROPOSED/TEMPORARY TRAFFIC CONTROL INFORMATION REFER TO TRAFFIC SIGNAL PLANS		TRAFFIC CONTROL (QL-D)
	TC(C)			TRAFFIC CONTROL (QL-C)
	TC(B)			TRAFFIC CONTROL (QL-B)
	UNK(B)	UNK(B)		UNKNOWN UTILITY FOUND IN SUE INVESTIGATION (QL-B)

UTILITY SYMBOLS

EXISTING	PROPOSED	TEMPORARY	
			UTILITY POLE/GUY POLE
			LIGHT POLE
			GUY ANCHOR
M	M	M	MARKER
X	X	X	SPLICE BOX
			CABINET
			VENT
E	E	E	ELECTRIC MANHOLE
H	H	H	HAND HOLE
E	E	E	TRANSFORMER
E	E	E	ELECTRIC METER
E	E	E	ELECTRIC BOX
T	T	T	TELECOMMUNICATIONS MANHOLE
T	T	T	TELECOMMUNICATIONS PEDESTAL
SLC	SLC	SLC	SUBSCRIBER LOOP CARRIER (aka "SLICK")
			PHONE BOOTH
			CABLE TV PEDESTAL
TV	TV	TV	CABLE TV MANHOLE
W	W	W	WATER VALVE
W	W	W	WATER METER
W	W	W	WATER MANHOLE
			FIRE HYDRANT ASSEMBLY (INCLUDES ASSOCIATED VALVE)
BFP	BFP	BFP	BACKFLOW PREVENTER
PIV	PIV	PIV	PRESSURE INDICATOR VALVE
ARV	ARV	ARV	AIR RELEASE VALVE
W	W	W	WELL
W	W	W	WATER VAULT
W	W	W	WATER VALVE MARKER
			STAND PIPE

EXISTING	PROPOSED	TEMPORARY	
			CLEANOUT
SS	SS	SS	SANITARY SEWER MANHOLE
ARV	ARV	ARV	AIR RELEASE VALVE
GT	GT	GT	GREASE TRAP
S	S	S	SANITARY SEWER FORCE MAIN VALVE
G	G	G	GAS VALVE
G	G	G	GAS METER
G	G	G	GAS MANHOLE
GPR	GPR	GPR	GAS PRESSURE REGULATOR
G	G	G	GAS VAULT
GTS	GTS	GTS	GAS TEST STATION
P	P	P	PETROLEUM VALVE
TC	FOR PROPOSED/TEMPORARY TRAFFIC CONTROL INFORMATION REFER TO TRAFFIC SIGNAL PLANS		TRAFFIC CONTROL MANHOLE/ ELECTRIC COMMUNICATIONS BOX
			TRAFFIC CONTROL PEDESTRIAN SIGNAL/BUTTON POST

MISCELLANEOUS

LOS	LIMITS OF OVERHEAD AND SUBSURFACE UTILITY INVESTIGATION
TH	TEST HOLE (QL-A ONLY)
EOI	END OF INFORMATION
	QUALITY LEVEL (QL) DELINEATION
123	POLE ID
A01	SANITARY SEWER MANHOLE (SSMH) ID
C123	CONFLICT LOCATION (UTILITY IMPACT ANALYSIS (UIA) ONLY)
	ELEVATION POINT

QUALITY LEVELS AND DEFINITIONS

QL-D DEPICTED ACCORDING TO UTILITY RECORD INFORMATION AND IN-FIELD VISUAL INSPECTION. NO ELECTRONIC DESIGNATING INFORMATION WAS OBTAINED.

QL-C EXISTING UTILITY STRUCTURES HAVE BEEN FIELD LOCATED AND SURVEYED TO ASSIST IN DEPICTING THE UTILITIES SHOWN ON RECORDS. NO ELECTRONIC DESIGNATING INFORMATION WAS OBTAINED.

QL-B INFORMATION WAS OBTAINED THROUGH THE APPLICATION OF APPROPRIATE SURFACE GEOPHYSICAL METHODS TO DETERMINE THE EXISTENCE AND APPROPRIATE HORIZONTAL POSITION OF THE SUBSURFACE UTILITIES. QL-B DATA SHOULD BE REPRODUCIBLE BY SURFACE GEOPHYSICS AT ANY POINT OF THEIR DEPICTION. THS INFORMATION IS SURVEYED TO APPLICABLE TOLERANCES DEFINED BY THE PROJECT AND REDUCED ONTO PLAN DOCUMENTS.

QL-A OBTAIN PRECISE HORIZONTAL AND VERTICAL POSITION OF THE UTILITY LINE BY EXCAVATING A TEST HOLE. THE TEST HOLE SHALL BE DONE USING VACUUM EXCAVATION OR COMPARABLE NONDESTRUCTIVE EQUIPMENT IN A MANNER AS TO CAUSE NO DAMAGE TO THE UTILITY LINE. AFTER EXCAVATING A TEST HOLE, A FIELD SURVEY SHALL BE PERFORMED TO DETERMINE THE EXACT LOCATION AND POSITION OF THE UTILITY LINE.

TELEPHONE PAIR SIZE TABLE

TELEPHONE PAIR SIZE	TELEPHONE CABLE DIAMETER
5 - 100	0.50 TO 2.00 IN
101 - 2400	UP TO 3.50 IN

COMPLETING PLANS

Kimley-Horn and Associates, Inc.

GEORGIA DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION

OFFICE: UTILITIES

UTILITY PLANS LEGEND

SR 400 AT NORTHRIDGE ROAD
P.I. #751580-
TASK ORDER: N/A

DRAWING No. 24-000